

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3732	00-00215-00-BR	COOK	58	7
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	PROJECT BHM-7003(802)		
CONTRACT 83584				

EARTHWORK SCHEDULE

ASBURY AVENUE LOCATION STATION TO STATION	EARTH EXCAVATION (CU YD)	*UNDERCUT AND PGE REPLACEMENT (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE - 15%) (CU YD)	EMBANKMENT (CU YD)	EATHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)
STAGE I					
101+00 TO 102+00	50	-	43	6	37
102+00 TO 103+00	84	-	72	4	67
103+00 TO 104+00	66	-	56	2	55
104+00 TO 105+00	52	-	45	7	37
105+00 TO 105+50	26	-	22	3	19
STAGE I TOTAL	278	37	237	22	214
STAGE II					
101+00 TO 102+00	47	-	40	6	35
102+00 TO 103+00	113	-	96	3	93
103+00 TO 104+00	46	-	39	2	37
104+00 TO 105+00	66	-	56	6	51
105+00 TO 105+50	31	-	26	3	24
STAGE II TOTAL	304	37	258	19	239
TOTALS (CY):	582	74	495	41	454

* UNDERCUT DETERMINED IN FIELD BY ENGINEER

PAY ITEMS	STAGE I	STAGE II	TOTALS
EARTH EXCAVATION (CU YD)	278	304	582
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	37	37	74
POROUS GRANULAR EMBANKMENT (CU YD)	37	37	74

DATE: 10/27/2004
FILENAME: N:\PROJECTS\3732\Design\Misc_sheets\3732_SCHEDULE-Q-QUANT.dgn

REVISIONS	
NAME	DATE

Clorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014 Email: chicago@clorba.com

THE CITY OF EVANSTON
ASBURY AVENUE BRIDGE IMPROVEMENTS
SCHEDULE OF QUANTITIES

SCALE: N.T.S. DRAWN BY: NBV
DATE: OCTOBER, 2004 CHECKED BY: RAY