



BILL OF MATERIAL

Bar	No.	Size	Length	Shape
h403(E)	22	#15	8.90 m	—
h405(E)	22	#15	4.70 m	—
h406(E)	9	#15	5.80 m	—
h407(E)	13	#15	5.60 m	—
u401(E)	119	#15	1.53 m	⊏
v406(E)	30	#15	2.10 m	—
v413(E)	15	#15	2.69 m	—
v414(E)	15	#15	2.90 m	—
v415(E)	14	#15	3.14 m	—
v416(E)	7	#15	4.30 m	—
v417(E)	31	#15	1.24 m	—
Concrete Structures		Cu. M	28.7	
Reinforcement Bars,		kg	1,360	
Epoxy Coated				
Structure Excavation		Cu. M	15.0	
Permanent Steel				
Sheet Piling		Sq. M	185	
Pipe Handrail		Meter	36	

Bar	Radius	Length
h406(E)	32.10 m	5.80 m
h407(E)	27.90 m	5.60 m




BAR h406(E) AND h407(E)



BAR u401(E)

Bar	A	B
v416(E)	1.16 m	3.14 m



BAR v416(E)

Order Bars full length. Cut in Field as shown.

***NOTE:**

For horizontal curve and alignment information, see Plan & Profile drawings.

NOTES:

See Sheet S16 for Notes.

SHEET S18 of S28

REVISIONS		NAME	DATE

URS

1701 GOLF ROAD, SUITE 1000
ROLLING MEADOWS, IL 60008

TEL (847) 228-0707
FAX (847) 228-1115

VILLAGE OF ADDISON

SALT CREEK GREENWAY TRAIL

RET. WALL STA. 16+479 TO 16+497

PLAN & ELEVATION

DATE: 11/03/04

DESIGNED BY: MDS

DRAWN BY: MDS

CHECKED BY: GAT

