COUNTY TOTAL SHEET NO. FAU SECTION 2667 02-00165-00-RP DUPAGE TO STA. 22+50 STA. 13+30 FED. ROAD DIST, NO. 7 ILLINOIS FED. AID PROJECT LEGEND TEMPORARY EROSION CONTROL NOTES SYMBOL DESCRIPTION 1. THE CONTRACTOR WILL BE REQUIRED TO IMPLEMENT AND MAINTAIN EROSION CONTROL MEASURES IMMEDIATELY AFTER STRIPPING OF EXISTING VEGETATION. ALL CONSTRUCTION ACTIVITIES SHALL ALSO BE IN ACCORDANCE WITH THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM STORM WATER PERMIT. CONSTRUCTION WORK ZONE THE QUANTITY SHOWN FOR TEMPORARY DITCH CHECKS AND INLET AND PIPE PROTECTION IS SUFFICIENT FOR ONE (1) SET UP AND THREE (3) REPLACEMENTS OVER THE DURATION OF THE CONTRACT. THESE ITEMS ARE MEASURED AS EACH, REGARDLESS OF TYPE OR CONFIGURATION USED. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PREVENT POLLUTION OF STORM WATER AND SHALL FOLLOW IEPA & IDOT CONSTRUCTION MEMORANDUM NO. 02-60. TYPE II BARRICADE WITH STEADY BURN LIGHTS @ 50' C. TO C. (TYP) - 25' C. TO C. IN TAPERS, CURVES, AND RADII 6. A QUANTITY OF ONE (1) SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER AND TWO (2) INLET FILTER CLEANINGS HAVE BEEN PROVIDED FOR EVERY EXISTING AND PROPOSED INLET WITHIN THE PROJECT LIMITS. THE FILTERS SHALL BE INSTALLED SIGN ON PORTABLE OR PERMANENT SUPPORT 3. THE CONTRACTOR SHALL SURROUND ALL EARTH STOCKPILES WITH PERIMETER EROSION BARRIER. EROSION CONTROL MEASURES SHALL BE INSPECTED PRIOR TO CONSTRUCTION ACTIVITIES. VERTICAL PANELS WITH STEADY BURNING LIGHT BY THE CONTRACTOR AND ENGINEER WITHIN 24 HOURS OF ANY STORM EXCEEDING $\frac{1}{2}$ OF PRECIPITATION. 7. ALL DISTURBED AREAS SHALL BE SODDED AS SOON AS PRATICAL AFTER CONSTRUCTION ACTIVITIES IN THAT AREA HAVE CONCLUDED, AREAS THAT HAVE BEEN STRIPPED AND WILL NOT RECEIVE PERMANENT LANGSCAPING BEFORE THE END OF FALL SEEDING RESTRICTION SHALL RECEIVE TEMPORARY EROSION CONTROL SEEDING. **b** FLASHING LIGHT DIRECTION OF TRAFFIC FLOW ARROW BOARD SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER INLET AND PIPE PROTECTION (4 BALES EACH, SEE STANDARD 280001) PERIMETER EROSION BARRIER (SILT FENCE, SEE STANDARD 280001) -- 19.50' -- 18.50' TEMPORARY DITCH CHECK (URETHANE FOAM OR ROLLED EXCELSIOR, SEE STANDARD 280001) -LOCATION OF TEMPORARY INFORMATION SIGNING END 7.00" FRAME: TOP RING CONSTRUCTED FROM 1/4" X 1/4" X 1/4" X 1/6" ANGLE. BASE RING CONSTRUCTED FROM 1 1/2" X 1/2" X 1/6" CHANNEL. HANDLES AND SUSPENSION BRACKETS CONSTRUCTED FROM 1/4" X 1/4" FLAT. ALL STEEL CONFORMING TO ASTM-A36. CONSTRUCTION REPLACABLE BAG: CONSTRUCTED FROM 4 0Z/SO YD NON-WOVEN POLYPROPYLENE GEOTEXTILE REINFORCED WITH POLYESTER MESH. CONNECTED TO BASE RING WITH STAINLESS STEEL STRAP AND LOCK. TEMPORARY PAVEMENT MARKING TAPE, TYPE III, LETTERS AND SYMBOLS (TYP) TEMPORARY PAVEMENT MARKING TAPE,
TYPE III, 6" WHITE (2' LINE, 6' SPACE)

TEMPORARY PAVEMENT MARKING TAPE,
TYPE III, 4" WHITE EDGE LINE U.S. ROUTE 20 TEMPORARY PAVEMENT MARKING TAPE,
TYPE III, 4" DOUBLE YELLOW @ 11" C-C TEMPORARY PAVEMENT MARKING, 4" DOUBLE YELLOW @ 11" C-C -¢ CHURCH ROAD 25 MP.H. DO NOT PASS 25 M.P.H. TEMPORARY PAVEMENT MARKING, 24" WHITE STOP LINE (TYP) TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 4" WHITE EDGE LINE U.S. ROUTE 20 ROAD TEMPORARY PAVEMENT MARKING TAPE,
TYPE III, 4" DOUBLE YELLOW @ 11" C-C FISCHER FARM ROAD 21×15 CHURCH ROAD ILLINOIS DEPARTMENT OF TRANSPORTATION ROAD ONSTRUCTIO SUGGESTED CONSTRUCTION PROCEDURE AND MAINTENANCE OF TRAFFIC 25 MP.H STAGE I CHURCH ROAD STATION 13+30 TO STATION 22+50 7-9-04 DRAWN BY CHECKED BY SCALE IN FEET