

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY Y052	LIGHTING Y030-IF
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNITS	14	14	
20100210	TREE REMOVAL OVER 15 UNITS DIAMETER	UNITS	18	18	
20101100	TREE TRUNK PROTECTION	EACH	15	15	
* 20101200	TREE ROOT PRUNING	EACH	20	20	
20200100	EARTH EXCAVATION	CU YD	297	297	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	82	82	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	30	30	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	741	741	
* 25000400	NITROGEN FERTILIZER NUTRIENT	LBS	14	14	
* 25000500	POTASSIUM FERTILIZER NUTRIENT	LBS	14	14	
* 25000600	PHOSPHOROUS FERTILIZER NUTRIENT	LBS	14	14	
* 25200100	SODDING	SQ YD	741	741	
25301400	TREES TO BE TRANSPLANTED 4-4 1/2"	EACH	1	1	
28000400	PERIMETER EROSION BARRIER	FOOT	110	110	
35102100	AGGREGATE BASE COURSE, TYPE B 9"	SQ YD	422	422	
40400100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	290	290	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	6	6	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6"	SQ YD	64	64	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"	SQ YD	99	99	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQ FT	4993	4993	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	161	161	
44000300	CURB REMOVAL	FOOT	292	292	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	69	69	
44000600	SIDEWALK REMOVAL	SQ FT	3394	3394	
44001000	BITUMINOUS CONCRETE SURFACE REMOVAL	SQ YD	749	749	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	6	6	
60600605	CONCRETE CURB, TYPE B	FOOT	292	292	
60603800	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12	FOOT	24	24	
* 70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	
* 72000100	SIGN PANEL, TYPE 1	SQ FT	40	40	
72900100	METAL POST - TYPE A	FOOT	61	61	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4156	4156	
* 80700135	GROUND ROD, 5/8" DIA. X 8 FT.	EACH	8		8
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	48		48
* 81400100	HANDHOLE	EACH	3		3
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	542		542
* 81600915	UNIT DUCT, 3*6XLP, 1*6 XLP GROUND 1" POLYETHYLENE	FOOT	588		588
* 83600410	POLE FOUNDATION, SPECIAL	EACH	6		6
* X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	1047	1047	
X0350805	FOLD DOWN BOLLARDS	EACH	3	3	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE C, N50	TON	156	156	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N50	TON	17	17	
X8570100	DISCONNECT SWITCH	EACH	2	2	
Xx0001017	PIPE UNDERDRAINS, PERFORATED PVC, 6 INCH	FOOT	240	240	
* XX001249	ORNAMENTAL FENCE	FOOT	120	120	
* Z003100	BICYCLE RAILING	FOOT	207	207	
Z0077800	WOOD POST	EACH	3	3	

* - SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SHERIDAN ROAD BIKE PATH

SUMMARY OF QUANTITIES

SCALE: NONE

DRAWN BY:

DATE: 11/05/2004

CHECKED BY:

DATE	
BY	
SURVEYED	
PLANNED	
NOTED	
FILED	
NO.	

DATE	
BY	
SURVEYED	
PLANNED	
NOTED	
FILED	
NO.	

11/05/2004 11:05:00 AM