F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00069-00-PV	DUPAGE	146	11
STA. 10+70.70		TO STA. 66+16.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83781

STATION	DISTANCE	20200100 EARTH EXCAVATION	EXCAVATION FOR EMBANKMENT (REDUCED FOR SHRINKAGE 0.15%)	20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	EMBANKMENT	20400800 FURNISHED EXCAVATION EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	20700220 POROUS GRANULAR EMBAMKMENT, SUBGRADE	66900200 NONSPECIAL WASTE DISPOSAL
	FT	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
35+00.00	54.6	72.1	61.3	17.7	14.2	47.1	41.6	51.5
35+08.50	8.5	10.5	8.9	3.0	3.3	5.6	6.5	11.1
35+50.00	41.5	49.2	41.8	15.9	18.1	23.7	31.6	54.3
35+56.96	7.0	7.2	6.1	2.7	4.3	1.8	5.3	9.0
36+00.00	43.0	33.0	28.0	13.1	39.4	-11.4	32.8	46.6
36+54.25	54.3	27.2	23.2	14.6	33.6	-10.5	107.9	87.0
36+68.40	14.2	7.3	6.2	4.4	0.8	5.4	45.5	32.0
36+82.90	14.5	15.3	13.0	9.0	0.7	12.3	46.7	27.6
37+00.00	17.1	23.4	19.9	14.4	1.7	18.1	45.4	27.0
37+50.00	50.0	39.3	33.4	25.8	9.8	23.6	101.4	86.7
37+79.34	29.3	10.6	9.0	7.3	3.4	5.6	57.3	56.5
38+00.00	20.7	8.0	6.8	5.0	0.5	6.3	39.8	41.2
38+04.83	4.8	2.1	1.8	1.2	0.0	1.8	9.2	9.9
38+50.00	45.2	15.1	12.8	10.5	5.2	7.6	85.2	103.6
39+00.00	50.0	10.7	9.1	20.9	10.0	-0.9	91.8	127.6
39+50.00	50.0	12.6	10.8	25.7	5.1	5.7	81.5	115.7
40+00.00	50.0	13.4	11.4	10.4	7.9	3.5	36.3	65.7
40+46.99	47.0	22.1	18.8	0.0	7.9	10.9	0.0	28.3
40+50.00	3.0	1.4	1.2	0.0	0.2	1.0	0.0	1.9
40+72.25	22.3	6.7	5.7	0.0	1.2	4.5	0.0	13.3
41+00.00	27.8	7.8	6.6	0.0	3.9	2.7	0.0	14.1
41+50.00	50.0	10.9	9.2	0.0	12.6	-3.4	0.0	27.1
42+00.00	50.0	11.7	9.9	0.0	12.7	-2.8	0.0	39.7
42+50.00	50.0	11.2	9.5	3.7	12.8	-3.3	18.1	74.5
42+64.03	14.0	4.0	3.4	1.8	2.1	1.3	10.2	28.0
43+00.00	36.0	11.0	9.3	4.4	7.2	2.1	33.4	80.4
43+17.22	17.2	2.3	2.0	1.2	3.4	-1.4	23.1	46.9
43+50.00	32.8	2.3	1.9	0.3	10.0	-8.0	34.2	66.5
43+72.82	22.8	6.5	5.6	0.8	10.2	-4.7	12.3	24.8
43+96.27	23.5	11.1	9.4	1.2	7.4	2.1	12.7	26.5
44+00.00	3.7	1.9	1.6	0.2	1.3	0.3	2.0	4.3
44+50.00	50.0	28.8	24.5	2.8	13.0	11.5	27.0	53.5
44+62.39	12.4	7.4	6.3	0.7	1.7	4.6	6.7	10.3
45+00.00	37.6	15.3	13.0	2.2	18.1	-5.1	20.3	12.7
45+21.70	21.7	4.4	3.8	1.2	14.7	-10.9	11.7	0.0
45+50.00	28.3	4.8	4.1	1.5	18.7	-14.6	15.3	0.0
45+81.62	31.6	5.9	5.0	0.8	21.6	-16.6	8.5	0.0
46+00.00	18.4	4.2	3.6	0.0	9.7	-6.1	0.0	0.0
46+32.34	32.3	9.4	8.0	0.0	9.6	-1.6	0.0	9.0
46+50.00	17.7	5.4	4.6	0.0	5.9	-1.3	0.0	14.1
46+68.14	18.1	6.6	5.6	0.0	10.4	-4.8	0.0	22.0
46+87.74	19.6	13.6	11.5	0.0	6.8	4.8	0.0	28.4

STATION	DISTANCE	20200100 EARTH EXCAVATION	EXCAVATION FOR EMBANKMENT (REDUCED FOR SHRINKAGE 0.15%)	20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	EMBANKMENT	20400800 FURNISHED EXCAVATION EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	20700220 POROUS GRANULAR EMBAMKMENT, SUBGRADE	66900200 NONSPECIAL WASTE DISPOSAL
	FT	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
47+00.00	12.3	10.7	9.1	0.0	1.1	8.0	0.0	18.4
47+27.70	27.7	22.1	18.8	0.0	2.2	16.6	0.0	33.0
47+50.00	22.3	14.5	12.3	0.0	5.7	6.6	0.0	12.6
47+85.51	35.5	15.3	13.0	0.0	14.7	-1.7	0.0	4.0
48+00.00	14.5	5.7	4.8	0.0	6.6	-1.8	0.0	0.0
48+44.52	44.5	13.4	11.4	0.0	20.9	-9.5	0.0	0.0
48+50.00	5.5	1.1	0.9	0.0	2.1	-1.1	0.0	0.0
49+00.00	50.0	21.0	17.9	6.6	8.8	9.0	28.1	27.6
49+07.17	7.2	5.2	4.4	2.1	0.1	4.3	8.1	8.5
49+50.00	42.8	32.7	27.8	32.0	7.0	20.9	50.0	56.8
49+67.00	17.0	16.0	13.6	20.4	6.0	7.6	20.6	23.0
49+84.26	17.3	25.5	21.7	21.5	3.3	18.4	21.7	22.7
49+92.88	8.6	13.7	11.7	10.7	0.7	11.0	11.0	11.2
50+00.00	7.1	8.9	7.5	8.6	1.0	6.5	9.0	9.3
50+50.00	50.0	51.3	43.6	48.4	7.1	36.5	66.7	68.4
51+00.00	50.0	104.0	88.4	67.7	6.1	82.2	99.3	57.3
51+50.00	50.0	86.4	73.5	51.2	7.0	66.4	102.6	64.1
51+99.11	49.1	6.5	5.5	1.8	4.7	0.8	37.5	41.6
52+30.22	31.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0
52+50.00	100.0	14.8	12.5	4.8	6.3	6.3	76.3	81.6
53+00.00	50.0	14.9	12.6	5.0	5.2	7.5	76.3	89.4
53+11.86	161.9	95.9	81.5	24.0	10.4	71.1	246.9	329.5
53+50.00	38.1	23.9	20.3	19.6	1.2	19.1	58.2	81.2
54+00.00	50.0	40.6	34.5	56.0	0.8	33.8	80.9	111.1
54+32.45	32.4	23.3	19.8	57.6	0.2	19.6	68.9	99.1
54+50.00	17.6	17.2	14.6	32.1	0.0	14.6	36.5	47.5
54+84.57	34.6	46.4	39.4	47.4	0.0	39.4	50.9	54.8
55+00.00	15.4	11.9	10.1	18.4	0.4	9.7	20.2	24.1
55+50.00	50.0	33.9	28.8	45.0	1.4	27.4	63.2	77.7
55+56.68	6.7	4.7	4.0	3.9	0.1	3.9	8.2	10.3
56+00.00	43.3	21.3	18.1	15.0	6.7	11.4	51.4	60.9
56+35.31	35.3	13.1	11.1	5.7	7.5	3.6	39.8	48.3
56+50.00	14.7	6.1	5.2	2.8	1.5	3.6	16.0	21.6
56+57.99	8.0	3.0	2.6	1.9	0.5	2.1	8.6	11.9
56+91.92	33.9	13.6	11.6	13.1	1.8	9.8	36.7	50.6

PLAN
NOTE BOOK NO. ____
SURVEYED
PLOTTED
ALIGNMENT CHECKED
CADD FILE NAME
BY
DATE

PROFILE
NOTE BOOK NO. ____
SURVEYED
PLOTTED
GRADES CHECKED
BAR NOTED
STRUCTURE NOTATIONS CHKD
BY
DATE

Stanley Consultants INC.
8501 West Higgins Road
Suite 730
Chicago, Illinois 60631-2801 Illinois Firm Registration No. 184-00633

REVISIONS	
NAME	DATE

VILLAGE OF VILLA PARK, ILLINOIS

SOUTH VILLA AVENUE
SCHEDULE OF QUANTITIES
SHEET 2 OF 4

SCALE: NONE
DRAWN BY: E.D.
DATE: 11-NOV-2004
CHECKED BY: J.T.G.

O:\15367\Phase2\07-Design\05-Dwgs\sht\367soq01.dgn
11-NOV-2004