

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
99-00352-00-BT	CHAMPAIGN	38	3
STA.	TO STA.		
F.H.W.A. REG.	ILLINOIS	PROJECT	TE-0005(76)

SUMMARY OF QUANTITIES

Y052

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, B&B	EACH	1.0
XX006078	TREE, AMELANCHIER X GRAND. (APPLE SERVICEBERRY), 2" CALIPER, TREE FORM, B&B	EACH	5.0
XX006079	TREE, CORNUS MAS (CORNELIAN CHERRY DOGWOOD), 2" CALIPER, TREE FORM, B&B	EACH	13.0
XX006080	TREE, CHIONANTHUS VIRGINICUS (FRINGE TREE), 2" CALIPER, TREE FORM, B&B	EACH	3.0
XX006081	TREE, QUERCUS ACCUTISSMA (SAWTOOTH OAK), 2" CALIPER, B&B	EACH	1.0
B2006216	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2" CALIPER, TREE FORM, B&B	EACH	3.0
A2006616	TREE, ULMUS PARVIFOLIA "ALLEE" (ALLEE LACEBARK ELM), 2" CALIPER, B&B	EACH	1.0
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	235.0
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	74.0
20200100	EARTH EXCAVATION	CU YD	467.0
25000200	SEEDING, CLASS 2	ACRE	0.7
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	63.0
25100115	MULCH, METHOD 2	ACRE	0.7
25300910	SALVAGING AND TRANSPLANTING TREES, SPECIAL	EACH	9.0
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8 INCH	SQ YD	21.0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	75.0
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVT, 6 INCH	SQ YD	69.0
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVT, 8 INCH	SQ YD	67.0
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	113.0
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	31,348.0
44000100	PAVEMENT REMOVAL	SQ YD	104.5
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	152.0
X0919000	TEMPORARY DRIVEWAY PAVEMENT REMOVAL	SQ YD	54.0
44000600	SIDEWALK REMOVAL	SQ FT	17,359.0
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL & REPLACEMENT	FOOT	505.0
50102400	CONCRETE REMOVAL	CU YD	2.6
550A0050	STORM SEWERS, CLASS A, TYPE 1 12 INCH	FOOT	16.0
56109210	WATER VALVES TO BE ADJUSTED	EACH	9.0
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1.0
60255500	MANHOLES TO BE ADJUSTED	EACH	4.0
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1.0
60260100	INLETS TO BE ADJUSTED	EACH	1.0
60266300	VALVE VAULTS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1.0
60500060	REMOVING INLETS	EACH	1.0

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.0
78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	139.0
78005130	EPOXY PAVEMENT MARKING - LINE 6 INCH	FOOT	641.0
78005180	EPOXY PAVEMENT MARKING - LINE 24 INCH	FOOT	38.0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	307.0
81400115	HANDHOLE TO BE ADJUSTED	EACH	8.0
89500400	RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON POST	EACH	1.0
XX003000	CLASS SICRETE STEPS	CU YD	2.6
Z0013825	CONTROLLED LOW-STRENGTH MATERIAL (TRENCH BACKFILL)	CU YD	3.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0
Z0050500	REMOVE AND RESET EXISTING STREET LIGHTS	EACH	10.0