

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
601	(*)	PIKE	51	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
(*) 02-00077-00-RS				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1,650
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	4
(*) 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	28
63200310	GUARDRAIL REMOVAL	FOOT	1,274
(*) 63300905	VERTICAL ADJUSTMENT OF GUARD RAIL, TYPE A	FOOT	1,512.5
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,778
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	85,482
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,593
72000100	SIGN PANEL - TYPE 1	SQ FT	251
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	528
78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	85,482
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	297
(*) 78200410	GUARDRAIL MARKERS, TYPE A	EACH	94
(*) 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	28
(*) X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	5,378
(*) X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	69
(*) XX004949	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE	TON	722
(*) XX005347	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, N50	TON	5,826

(*) SEE SPECIAL PROVISIONS

CONSTRUCTION TYPE CODE: I000

ie consultants	INTERNATIONAL ENGINEERING CONSULTANTS, INC.			
	8420 SOUTH SIXTH STREET SPRINGFIELD, ILLINOIS 62707 TEL. (217) 528-8027 FAX (217) 528-4543 IESPRINGFIELD@IE-CONSULTANTS.COM WWW.IE-CONSULTANTS.COM			
SUMMARY OF QUANTITIES				
DRAWN BY: RG	CHECKED BY: CMS	DATE: 8-23-04	PROJECT: S03012	