

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
601	(*)	PIKE	51	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
(*) 02-00077-00-RS				

SCHEDULE OF QUANTITIES

SIGN SCHEDULE					
STA.	LT/RT	TYPE	SIZE	SIGN PANEL TYPE 1 (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)
5+02	LT	R1-1	30x30	6.25	12
5+62	LT		24x30	5.00	12
5+92	RT		24x30	5.00	12
7+04	RT	R2-1	24x30	5.00	12
8+30	LT	R2-1	24x30	5.00	12
12+75	LT	R2-5A	24x30	5.00	12
22+10	RT	R4-2	24x30	---	---
24+29	RT	R2-1	24x30	5.00	12
27+26	RT	S2-1	36x36	9.00	12
33+85	LT	R4-1	24x30	---	---
35+33	LT	R2-1	24x30	5.00	12
35+33	RT	R2-1	24x30	5.00	12
38+06	RT	R4-1	24x30	---	---
51+17	LT	R4-2	24x30	---	---
53+81	RT	R4-2	24x30	5.00	12
54+46	RT		24x30	5.00	12
55+00	LT	R2-1	24x30	5.00	12
61+52	LT	R1-1	30x30	6.25	12
64+54	LT	R4-1	24x30	5.00	12
66+87	LT	W2-2R	30x30	6.25	12
67+69	RT	R4-1	24x30	5.00	12
73+04	RT	W1-4L	30x30	6.25	12
76+17	LT	R4-2	24x30	5.00	12
105+30	RT	W2-3R	30x30	6.25	12
110+09	LT	R1-1	30x30	6.25	12
115+62	LT	W2-3R	30x30	6.25	12
119+60	LT	W1-4L	30x30	6.25	12
125+63	RT	R4-2	24x30	---	---
139+00	RT	R4-2	24x30	5.00	12
140+18	LT	R4-1	24x30	5.00	12
162+06	RT	R4-1	24x30	5.00	12
166+45	RT	W1-2L	30x30	6.25	12
171+89	LT	R4-2	24x30	5.00	12
172+93	RT	W1-10L	30x30	6.25	12
177+11	RT	R1-1	30x30	6.25	12
180+79	LT	W1-10R	30x30	6.25	12
183+25	RT	W2-2R	30x30	6.25	12
188+62	RT	R1-1	30x30	6.25	12
191+92	RT	R4-2	24x30	5.00	12
192+98	LT	W2-2L	30x30	6.25	12
197+07	LT	W1-2R	30x30	6.25	12
201+92	LT	R4-1	24x30	5.00	12
211+89	RT	R4-1	24x30	5.00	12
219+14	RT	W1-2R	30x30	6.25	12
222+90	LT	R4-2	24x30	5.00	12
223+43	RT	W2-2L	30x30	6.25	12
227+36	LT	R1-1	30x30	6.25	12
236+87	LT	R1-1	30x30	6.25	12
241+31	LT	W2-3R	30x30	6.25	12
TOTAL				250.25	528
USE				251	528

EARTHWORK SCHEDULE											
STA.	TO	STA.	LT/RT	EARTH EXCAVATION (CU YD)	EMBANKMENT (CU YD)	SEEDING CLASS 2 (ACRE)	FERTILIZER NUTRIENT			AGG GROUND LIMESTONE (TON)	MULCH METHOD 2 (ACRE)
							NITROGEN (POUND)	PHOSPHORUS (POUND)	POTASSIUM (POUND)		
AREA 1											
5+00.00		16+50.00	LT & RT	154.7	90.9	0.23	21	21	21	0.09	0.23
AREA 2											
38+00.00		52+00.00	RT	93.6	103.8	0.19	17	17	17	0.37	0.19
TOTALS				248.3	194.7	0.42	38	38	38	0.46	0.42
USE				249	195	0.5	38	38	38	0.5	0.5

CONCRETE CURB / GUTTER SCHEDULE							
STA.	TO	STA.	LT/RT	COMB CONC C & G REM (FOOT)	CONC GUTTER TYPE A SPECIAL (FOOT)	COMB CONC C & G TY B-6.12 (FOOT)	CL SI CONC (OUTLET) (CU YD)
4+90.0		6+44.0	RT	154.0	---	154.0	---
5+35.5		8+55.5	LT	320.0	---	320.0	---
8+98.0		10+20.0	LT	122.0	---	122.0	---
10+20.0		10+31.5	LT	11.5	11.5	---	---
10+31.5		10+76.5	LT	10.0	---	---	6.6
10+76.5		11+27.5	LT	---	51.0	---	---
11+27.5		11+72.5	LT	---	---	---	6.6
11+72.5		12+23.5	LT	---	51.0	---	---
12+23.5		12+68.5	LT	---	---	---	6.6
12+68.5		13+03.5	LT	---	35.0	---	---
13+03.5		13+48.5	LT	---	---	---	6.6
13+48.5		13+52.0	LT	---	3.5	---	---
13+52.0		14+10.0	LT	---	---	---	5.0
TOTAL				617.5	152.0	596.0	31.4
USE				618	152	596	32

FURNISHED EXCAVATION				
	EARTH EXCAVATION	EARTH EXCAVATION -25% SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
TOTALS	249	186.8	195	-8.3
			USE	9

FILE: G:\NS03012\CAD\3012S01.DGN 06/24/04 06:27:52 AM



INTERNATIONAL ENGINEERING CONSULTANTS, INC.
6420 SOUTH SIXTH STREET
SPRINGFIELD, ILLINOIS 62707
TEL: (217) 528-8027
FAX: (217) 528-4543
IESPRINGFIELD@IE-CONSULTANTS.COM
WWW.IE-CONSULTANTS.COM

SCHEDULE OF QUANTITIES

DRAWN BY: RG	CHECKED BY: CMS	DATE: 8-23-04	PROJECT: S03012
-----------------	--------------------	------------------	--------------------