

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE													
				80% FED. 20% STATE ROADWAY J000-2A	80% FED. 20% STATE ROADWAY I000-2A	80% FED./10% STATE 10% BANNOCKBURN TRAFFIC SIGNALS Y031-1F	20% STATE TRAFFIC SIGNALS Y031-1F	80% FED./10% STATE 10% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	80% FED./13.3% STATE 6.7% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	80% FED. 20% STATE INTERCONNECT Y031-1F	50% STATE 50% BANNOCKBURN SIDEWALK SFTY-1B	100% HIGHLAND PARK EMERGENCY PRE-EMPTION Y031-3D	100% BANNOCKBURN EMERGENCY PRE-EMPTION Y031-3D				
4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,168		1,168												
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	115		115												
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,073		448							625					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	77		77												
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,559		2,559												
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	235		235												
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	57,364	57,364													
42001300	PROTECTIVE COAT	SQ YD	73,289	73,289													
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	35,896	2,545								33,351					
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	1,037	474								563					
42400800	DETECTABLE WARNINGS	SQ FT	1,175	1,175													
44000100	PAVEMENT REMOVAL	SQ YD	44,221	44,221													
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	22,491		22,491												
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,841	2,841													
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	24,263	24,263													
44000600	SIDEWALK REMOVAL	SQ FT	13,015	13,015													
X4402805	ISLAND REMOVAL	SQ FT	973	973													
44003100	MEDIAN REMOVAL	SQ FT	98,660	98,660													
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	334		334												
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	80		80												
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	26		26												
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	8,409	8,409													
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	42	42													
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4													
50105220	PIPE CULVERT REMOVAL	FOOT	1,108	1,108													
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	14	14													
54213672	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 27"	EACH	1	1													
54216180	REINFORCED CONCRETE PIPE TEE, 12" PIPE WITH 12" RISER	EACH	19	19													
54216185	REINFORCED CONCRETE PIPE TEE, 15" PIPE WITH 12" RISER	EACH	2	2													
54216190	REINFORCED CONCRETE PIPE TEE, 18" PIPE WITH 12" RISER	EACH	9	9													

* SPECIALTY ITEMS

(SHEET 2 OF 10)

FILE NAME : W:\ILRTE22\2013 REVISIONS\CADD Sheets\1160860-shr-500.dgn	USER NAME : #USER#	DESIGNED - LP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL. ROUTE 22 SUMMARY OF QUANTITIES			F.A.P. RTE. 337	SECTION 20R-4	COUNTY LAKE	TOTAL SHEETS 232	SHEET NO. 4
PLOT SCALE : #SCALE#		DRAWN - LP	REVISED -		SCALE: NTS	SHEET NO. 4 OF 232 SHEETS	STA.	TO STA.	CONTRACT NO. 60860			
CHECKED - JP		DATE - 05/14/2010	REVISED -		ILLINOIS FED. AID PROJECT							
PLOT DATE : 5/16/2010			REVISED -									