

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE																
				80% FED. 20% STATE ROADWAY J000-2A	80% FED. 20% STATE ROADWAY I000-2A	80% FED./10% STATE 10% BANNOCKBURN TRAFFIC SIGNALS Y031-1F	80% FED. 20% STATE TRAFFIC SIGNALS Y031-1F	80% FED./10% STATE 10% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	80% FED./13.3% STATE 6.7% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	80% FED. 20% STATE INTERCONNECT Y031-1F	50% STATE 50% BANNOCKBURN SIDEWALK SFTY-1B	100% HIGHLAND PARK J000-2A	100% BANNOCKBURN J000-2A							
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	50	50																
* Z0033060	PREFORMED DETECTOR LOOP	FOOT	2,653			1,006	1,647													
* Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1									1								
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	4			1	1	1	1											
X7030104	PAVEMENT MARKING WET TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	54,921	54,921																
X7030106	PAVEMENT MARKING WET TEMPORARY TAPE TYPE III, 6 INCH	FOOT	8,684	8,684																
X7030112	PAVEMENT MARKING WET TEMPORARY TAPE TYPE III, 12 INCH	FOOT	435	435																
X7030124	PAVEMENT MARKING WET TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	302	302																
X7030120	PAVEMENT MARKING WET TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	2,198	2,198																
X0325825	PAVEMENT REPLACEMENT	SQ YD	1,662	1,662																
X0325888	TEMPORARY CULVERT 24"	FOOT	295	295																
Z0033644	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1																	
* X0326270	RAILROAD, FULL-ACTUATED CONTROLLER AND TYPE V CABINET (SPECIAL)	EACH	1				1													
Z0062456	TEMPORARY PAVEMENT	SQ YD	16,411	16,411																
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	26	26																
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	14	14																
X4023000	TEMPORARY ACCESS (ROAD)	EACH	17	17																
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	4			1	1	1	1											
* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	4			1	1	1	1											
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MMI2F SM12F	FOOT	16,508									16,508								
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2,632			562	1,136	461	473											
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	2,299			545	1,231	258	265											
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	78,699	78,699																
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1																
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	26	26																
Z0022800	FENCE REMOVAL	FOOT	1,801	1,801																
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1				1													
Z0068426	STEEL CASINGS 66"	FOOT	50	50																
* A2007932	TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 4" CALIPER, BALLED AND BURLAPPED	EACH	39																	39
* B2013460	TREE, MALUS GOLDEN RAINDROPS (GOLDEN RAINDROPS CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6																	6

* SPECIALTY ITEMS

Non-Participating

(SHEET 9 OF 10)

FILE NAME W:\ILRTE22\2010\REVISIONS\CADD Sheets\162060-sht-500.dgn	USER NAME = #USER#	DESIGNED - LP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL. ROUTE 22 SUMMARY OF QUANTITIES			F.A.P. RTE. 337	SECTION 20R-4	COUNTY LAKE	TOTAL SHEETS 232	SHEET NO. 11
PLOT SCALE = #SCALE#	CHECKED - JP	DATE - 05/14/2010	REVISED -		SCALE: NTS	SHEET NO. 11 OF 232 SHEETS	STA.	TO STA.	CONTRACT NO. 60860			
PLOT DATE = 5/16/2010	DATE - 05/14/2010	REVISED -			ILLINOIS FED. AID PROJECT							