



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 13, 2011

SUBJECT: FAI Route 80
Project ACIM-080-4 (191) 141
Section 99-5-Y
Will County
Contract No. 60I47
Item No. 105, January 21, 2011 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page iv of the Table of Contents to the Special Provisions.
3. Added page 254 to the Special Provisions.
4. Revised sheets 7 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
K0029618	WEED CONT BROADLF TRF	GALLON	19.000				
K0029624	WEED CONTROL TEASEL	GALLON	7.500				
K0029632	WEED CONT N SEL/N RES	GALLON	20.000				
K1003660	MOWING CYCLES	EACH	2.000				
K1005418	TEMPORARY SEEDING	ACRE	23.000				
XX007665	PRO SS CONN TO EX CUL	EACH	1.000				
X0300247	REMOV WOOD POST	EACH	2.000				
X0321750	REM TEMP CONC BAR SO	FOOT	16,196.000				
X0322118	REM CON FLAR END SEC	EACH	13.000				
X0322446	CAB HOUSING EQU TY 3	EACH	8.000				
X0323260	SEDIMENT BASIN	EACH	5.000				
X0323898	CCTV DOME CAMERA	EACH	4.000				
X0323914	FOC SPLICE - LATERAL	EACH	11.000				
X0323957	FOC SPLICE - MAINLINE	EACH	5.000				
X0324876	CONC BARRIER SPL	FOOT	181.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0325040	FO INNERDUCT 1 1/4"	FOOT	36,400.000				
X0325222	WEED CONT BASAL TRTMT	GALLON	10.000				
X0326266	ETHERNET SWITCH	EACH	9.000				
X0326366	ELECT EQPT REM/SALV	EACH	1.000				
X0326445	CONC BAR DBL FACE SPL	FOOT	2,195.000				
X0326462	BDGT ALWNC TWY FO CON	L SUM	1.000				
X0326465	MOD EX VID DSTN SYS	L SUM	1.000				
X0326945	CCTV CAMERA EQUIPMENT	EACH	4.000				
X0326946	CCTV CAMERA INSTALL	EACH	4.000				
X0326948	CCTV CAMERA STR 50 MH	EACH	4.000				
X0326949	CCTV CAMERA ST FD 30D	FOOT	40.000				
X0326964	FO INTERCONNECT CAB	EACH	2.000				
X0327113	MAN CONN OV EX CULVRT	EACH	2.000				
X0327114	RADAR VEH SENSING SYS	EACH	16.000				
X0327115	RS232 ETHERNET CONVRT	EACH	16.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0327116	SOLAR POWER ASSEMBLY	EACH	8.000				
X0327117	ATMS SYS INTEGRATION	L SUM	1.000				
X0327118	SP RVSD SSR ANT POLE	EACH	12.000				
X0327119	RVSD POLE ON BAR WALL	EACH	6.000				
X2020110	GRADING & SHAP SHLDRS	UNIT	299.000				
X2501800	SEEDING CL 4 MOD	ACRE	10.000				
X2503110	MOWING SPL	ACRE	0.230				
X2503315	INTERSEED CL 4A MOD	ACRE	20.000				
X6020091	MAN TA 6D T20 FG R-P	EACH	5.000				
X6300130	SPBGR TY A SPL	FOOT	350.000				
X6350120	DELINEATOR REMOVAL	EACH	49.000				
X6370250	C BAR VAR X-SEC 42HT	FOOT	6,303.000				
X6370279	CONC BAR 1F 42HT SPL	FOOT	181.000				
X6700410	ENGR FLD OFF A SPL	CAL MO	12.000				
X7011015	TR C-PROT EXPRESSWAYS	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X7030035	WET REF TEM TAPE T3 5	FOOT	600.000				
X7040210	REL TEMP CONC BAR SPL	FOOT	315.000				
X8050010	SERV INSTALL GRND MT	EACH	3.000				
X8360105	LT POLE FDN INT BW 24	FOOT	60.000				
X8710035	FIB OPT CBL 96F SM	FOOT	43,500.000				
X8710036	FIB OPT CBL 12F SM	FOOT	3,300.000				
X8710054	FO TERM PANEL 12F 24F	EACH	8.000				
Z0001050	AGG SUBGRADE 12	SQ YD	46,820.000				
Z0012710	CONC HDWL - P UNDR RM	EACH	55.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0014800	CULVERT TO BE CLEANED	FOOT	1,055.000				
Z0023600	FILL EXIST CULVERTS	EACH	5.000				
Z0030030	IMP ATTEN FRD NAR TL3	EACH	3.000				
Z0030250	IMP ATTN TEMP NRD TL3	EACH	5.000				
Z0033028	MAINTAIN LIGHTING SYS	CAL MO	10.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0033052	COMMUNICATIONS VAULT	EACH	28.000				
Z0042002	POROUS GRAN EMB SUBGR	CU YD	500.000				
Z0056220	SAND MOD IMP ATT REM	EACH	5.000				
Z0064800	SELECTIVE CLEARING	UNIT	853.000				
Z0076870	UNDR CONNECT TO STR	EACH	94.000				
20100110	TREE REMOV 6-15	UNIT	338.000				
20100210	TREE REMOV OVER 15	UNIT	146.000				
20101300	TREE PRUN 1-10	EACH	20.000				
20101350	TREE PRUN OVER 10	EACH	20.000				
20200100	EARTH EXCAVATION	CU YD	15,380.000				
20201200	REM & DISP UNS MATL	CU YD	12,721.000				
20800150	TRENCH BACKFILL	CU YD	11,083.000				
21001000	GEOTECH FAB F/GR STAB	SQ YD	2,500.000				
21101605	TOPSOIL F & P 2	SQ YD	94,800.000				
21101615	TOPSOIL F & P 4	SQ YD	58,080.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25000210	SEEDING CL 2A	ACRE	2.000				
25000400	NITROGEN FERT NUTR	POUND	90.000				
25000500	PHOSPHORUS FERT NUTR	POUND	90.000				
25000600	POTASSIUM FERT NUTR	POUND	90.000				
25000750	MOWING	ACRE	33.000				
25100105	MULCH METHOD 1	ACRE	10.000				
25100115	MULCH METHOD 2	ACRE	10.000				
25100630	EROSION CONTR BLANKET	SQ YD	9,430.000				
28000305	TEMP DITCH CHECKS	FOOT	1,180.000				
28000400	PERIMETER EROS BAR	FOOT	1,345.000				
28000500	INLET & PIPE PROTECT	EACH	213.000				
28100101	STONE RIPRAP CL A1	SQ YD	190.000				
28100107	STONE RIPRAP CL A4	SQ YD	190.000				
28100207	STONE RIPRAP CL A4	TON	1,163.000				
28200200	FILTER FABRIC	SQ YD	190.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
31200502	STAB SUBBASE HMA 4.5	SQ YD	49,890.000				
42001300	PROTECTIVE COAT	SQ YD	15,320.000				
44000100	PAVEMENT REM	SQ YD	662.000				
44000400	GUTTER REM	FOOT	41.000				
44004000	PAVED DITCH REMOVAL	FOOT	120.000				
44200577	CL A PATCH T2 12	SQ YD	40.000				
44200581	CL A PATCH T3 12	SQ YD	110.000				
44200583	CL A PATCH T4 12	SQ YD	40.000				
44213000	PATCH REINFORCEMENT	SQ YD	190.000				
44213200	SAW CUTS	FOOT	780.000				
44213204	TIE BARS 3/4	EACH	235.000				
48101200	AGGREGATE SHLDS B	TON	1,106.000				
48101500	AGGREGATE SHLDS B 6	SQ YD	509.000				
48300705	PCC SHOULDERS 12 1/4	SQ YD	44,440.000				
50102400	CONC REM	CU YD	3.600				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50104400	CONC HDWL REM	EACH	5.000				
50105220	PIPE CULVERT REMOV	FOOT	4.000				
50200100	STRUCTURE EXCAVATION	CU YD	89.000				
50300225	CONC STRUCT	CU YD	50.300				
50800205	REINF BARS, EPOXY CTD	POUND	4,130.000				
54213663	PRC FLAR END SEC 18	EACH	1.000				
54213669	PRC FLAR END SEC 24	EACH	1.000				
54213675	PRC FLAR END SEC 30	EACH	1.000				
54213687	PRC FLAR END SEC 42	EACH	1.000				
54213705	PRC FLAR END SEC 60	EACH	2.000				
54215418	CIP RC END SEC 18	EACH	1.000				
54215430	CIP RC END SEC 30	EACH	1.000				
54247130	GRATING-C FL END S 24	EACH	1.000				
54247150	GRATING-C FL END S 30	EACH	1.000				
54247180	GRATING-C FL END S 42	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
54248510	CONCRETE COLLAR	CU YD	1.000				
550A0050	STORM SEW CL A 1 12	FOOT	43.000				
550A0140	STORM SEW CL A 1 30	FOOT	25.000				
550A0160	STORM SEW CL A 1 36	FOOT	50.000				
550A0340	STORM SEW CL A 2 12	FOOT	1,070.000				
550A0360	STORM SEW CL A 2 15	FOOT	825.000				
550A0380	STORM SEW CL A 2 18	FOOT	2,427.000				
550A0400	STORM SEW CL A 2 21	FOOT	450.000				
550A0410	STORM SEW CL A 2 24	FOOT	3,301.000				
550A0430	STORM SEW CL A 2 30	FOOT	3,612.000				
550A0450	STORM SEW CL A 2 36	FOOT	2,455.000				
550A0470	STORM SEW CL A 2 42	FOOT	665.000				
550A0480	STORM SEW CL A 2 48	FOOT	955.000				
55100500	STORM SEWER REM 12	FOOT	30.000				
55200600	STORM SEWERS JKD 18	FOOT	206.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
55200900	STORM SEWERS JKD 24	FOOT	91.000				
55201100	STORM SEWERS JKD 30	FOOT	177.000				
55201500	STORM SEWERS JKD 42	FOOT	96.000				
55201600	STORM SEWERS JKD 48	FOOT	268.000				
55201800	STORM SEWERS JKD 60	FOOT	320.000				
58600100	SAND BACKFILL	CU YD	250.000				
60107700	PIPE UNDERDRAINS 6	FOOT	33,400.000				
60108200	PIPE UNDERDRAIN 6 SP	FOOT	572.000				
60200205	CB TA 4 DIA T1F CL	EACH	3.000				
60200805	CB TA 4 DIA T8G	EACH	2.000				
60201310	CB TA 4 DIA T20F&G	EACH	80.000				
60201320	CB TA 4 DIA T21F&G	EACH	6.000				
60219510	MAN TA 4 DIA T20F&G	EACH	19.000				
60219520	MAN TA 4 DIA T21F&G	EACH	3.000				
60221100	MAN TA 5 DIA T1F CL	EACH	11.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60221700	MAN TA 5 DIA T8G	EACH	2.000				
60222210	MAN TA 5 DIA T20F&G	EACH	57.000				
60222220	MAN TA 5 DIA T21F&G	EACH	3.000				
60224035	MAN TA 6 DIA T20F&G	EACH	10.000				
60500050	REMOV CATCH BAS	EACH	1.000				
60500060	REMOV INLETS	EACH	2.000				
60600095	CLASS SI CONC OUTLET	CU YD	4.000				
60615400	PAVED DITCH TA-15	FOOT	45.000				
60618320	CONC MEDIAN SURF 6	SQ FT	2,090.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	575.000				
63100045	TRAF BAR TERM T2	EACH	2.000				
63100089	TRAF BAR TERM T6B	EACH	1.000				
63100105	TRAF BAR TERM T10	EACH	1.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	3.000				
63200310	GUARDRAIL REMOV	FOOT	860.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63301210	REM RE-E SPBGR TY A	FOOT	100.000				
63700175	CONC BAR 1F 42HT	FOOT	1,708.000				
63700275	CONC BAR 2F 42HT	FOOT	6,297.000				
63700805	CONC BAR TRANS	FOOT	907.000				
63700900	CONC BARRIER BASE	FOOT	17,410.000				
64200105	SHOULDER RUMBLE STRIP	FOOT	47,585.000				
66700205	PERM SURV MKRS T1	EACH	2.000				
66700705	FUR ERECT DRAIN MKRS	EACH	3.000				
** 66900200	NON SPL WASTE DISPOSL	CU YD	1,100.000				
** 66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
** 66900530	SOIL DISPOSAL ANALY	EACH	2.000				
67100100	MOBILIZATION	L SUM	1.000				
70102620	TR CONT & PROT 701501	L SUM	1.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	9.000				
70300520	PAVT MARK TAPE T3 4	FOOT	64,800.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70300550	PAVT MARK TAPE T3 8	FOOT	9,050.000				
70300560	PAVT MARK TAPE T3 12	FOOT	680.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	28,320.000				
70400100	TEMP CONC BARRIER	FOOT	39,650.000				
70400500	TEMP CON BAR ST OWN	FOOT	466.000				
70400600	REL TEMP CONC BAR SO	FOOT	17,290.000				
72000100	SIGN PANEL T1	SQ FT	37.000				
72000200	SIGN PANEL T2	SQ FT	508.000				
72000300	SIGN PANEL T3	SQ FT	3,332.000				
72400100	REMOV SIN PAN ASSY TA	EACH	15.000				
72400200	REMOV SIN PAN ASSY TB	EACH	29.000				
72400330	REMOV SIGN PANEL T3	SQ FT	3,009.000				
72600100	MILEPOST MKR ASSEMBLY	EACH	14.000				
72800100	TELES STL SIN SUPPORT	FOOT	199.000				
73000100	WOOD SIN SUPPORT	FOOT	306.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
73301810	OSS WALKWAY TY A	FOOT	46.000				
73302170	OSS CANT 2CA 3-0X5-6	FOOT	28.000				
73400100	CONC FOUNDATION	CU YD	24.400				
73400200	DRILL SHAFT CONC FDN	CU YD	74.400				
73500100	RELOC OH SIN STR-SPAN	EACH	2.000				
73500200	RELOC OH SIN STR-CANT	EACH	1.000				
73700100	REM GR MT SIN SUPPORT	EACH	2.000				
73700200	REM CONC FDN-GR MT	EACH	2.000				
73700300	REM CONC FDN-OVHD	EACH	6.000				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	338.000				
78008210	POLYUREA PM T1 LN 4	FOOT	56,588.000				
78008220	POLYUREA PM T1 LN 5	FOOT	16,652.000				
78008240	POLYUREA PM T1 LN 8	FOOT	16,285.000				
78008250	POLYUREA PM T1 LN 12	FOOT	3,130.000				
78100100	RAISED REFL PAVT MKR	EACH	791.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78100300	REPLACEMENT REFLECTOR	EACH	160.000				
78200100	MONODIR PRIS BAR REFL	EACH	90.000				
78200410	GUARDRAIL MKR TYPE A	EACH	25.000				
78200530	BAR WALL MKR TYPE C	EACH	2,720.000				
78201000	TERMINAL MARKER - DA	EACH	3.000				
78300100	PAVT MARKING REMOVAL	SQ FT	29,258.000				
80400200	ELECT UTIL SERV CONN	L SUM	1.000		3,000.000		3,000.000
81000600	CON T 2 GALVS	FOOT	250.000				
81000800	CON T 3 GALVS	FOOT	350.000				
81013000	CON T 4 PVC	FOOT	16,500.000				
81018700	CON P 3 GALVS	FOOT	975.000				
81018900	CON P 4 GALVS	FOOT	1,125.000				
81400200	HD HANDHOLE	EACH	10.000				
81603037	UD 2#6#6G XLPUSE 1.25	FOOT	900.000				
81900200	TR & BKFIL F ELECT WK	FOOT	17,700.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60147

State Job # - C-91-046-10
 PPS NBR - 1-77247-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-5-Y

Project Number
 ACIM-0804/191/141

Route
 FAI 80

** REVISED : JANUARY 13, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
83600200	LIGHT POLE FDN 24D	FOOT	120.000				
83800105	BKWY DEV TR B 11.5BC	EACH	12.000				
84200600	REM LT U NO SALV	EACH	2.000				
84200804	REM POLE FDN	EACH	2.000				
87800200	CONC FDN TY D	FOOT	40.000				
89502200	MOD EX CONTR	EACH	1.000				

IMPACT ATTENUATORS (BDE).....	179
IMPACT ATTENUATORS, TEMPORARY (BDE).....	180
IMPROVED SUBGRADE (BDE).....	182
LIQUIDATED DAMAGES (BDE).....	184
MULCH (BDE).....	184
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE)	187
PAVEMENT MARKING REMOVAL (BDE).....	188
PAVEMENT PATCHING (BDE).....	188
PAYMENTS TO SUBCONTRACTORS (BDE)	188
POST MOUNTING OF SIGNS (BDE).....	189
PRECAST CONCRETE HANDLING HOLES (BDE)	190
RAISED REFLECTIVE PAVEMENT MARKERS (BDE).....	191
SEEDING (BDE)	191
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE).....	193
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	195
TEMPORARY EROSION CONTROL (BDE)	195
TRAFFIC CONTROL SURVEILLANCE (BDE).....	198
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID).....	198
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)	201
STORM WATER POLLUTION PREVENTION PLAN.....	205
NOTICE OF INTENT.....	221
TRENCH AND BACKFILL FOR ELECTRICAL WORK	224
FIBER OPTIC INTERCONNECT CABINET	224
ELECTRIC SERVICE INSTALLATION – GROUND MOUNT	226
FIBER OPTIC CABLE, SINGLE MODE.....	228
MODIFICATION OF EXISTING CCTV DISTRIBUTION SYSTEM.....	241
CCTV EQUIPMENT	245
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	254

Revised 01/13/2011

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

This work shall be according to Article 669 of the Standard Specifications and the following:

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

General. This Special Provision will likely require the Contractor to subcontract for the execution of certain activities. .

All contaminated materials shall be managed as non-special waste. This work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances.

A) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage any excavated soils **within the construction limits of this project as fill**. Although the soil concentrations exceed a residential property's Tier 1 soil remediation objective for the ingestion exposure pathway, they can be utilized within the construction limits as fill because the roadway is not considered a residential property. All storm sewer excavated soils can be placed back into the excavated trench as backfill unless trench backfill is specified. If the soils cannot be utilized within the construction limits as fill then they must be managed off-site as a non-special waste. The following areas can be managed within the construction limits as fill.

1. Station 295+00 to Station 305+70 0 to 100 feet LT (METRA Railroad Tracks, Site 1628A/V-106, 1200-1800 blocks of West Lincoln Highway) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
2. Station 308+00 to Station 311+50 0 to 100 feet LT (State ROW, Site 1628A/V-112, approximately Station 306+00 to 320+00) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
3. Station 322+00 to Station 326+00 0 to 100 feet LT (METRA Railroad Tracks, Site 1628A/V-106, 1200-1800 blocks of West Lincoln Highway) – non-special waste. Contaminants of concern sampling parameters: Arsenic.

Added 01/13/2011