


CODE NO.	ITEM	UNIT	90% FED. 10% STATE		ROADWAY 0003	LANDSCAPING 0031
			URBAN TOTAL			
44213000	PATCHING REINFORCEMENT	SQ YD	190		190	
44213200	SAW CUTS	FOOT	780		780	
44213204	TIE BARS 3/4"	EACH	235		235	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,106		1,106	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	509		509	
48300705	PORTLAND CEMENT CONCRETE SHOULDERS 12 1/4"	SQ YD	44,440		44,440	
50102400	CONCRETE REMOVAL	CU YD	3.6		3.6	
50104400	CONCRETE HEADWALL REMOVAL	EACH	5		5	
50200100	STRUCTURE EXCAVATION	CU YD	89		89	
50300225	CONCRETE STRUCTURES	CU YD	50.3		50.3	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4,130		4,130	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1		1	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1		1	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1		1	
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1		1	
54215418	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 18"	EACH	1		1	

* DENOTES SPECIALTY ITEM

CODE NO.	ITEM	UNIT	90% FED. 10% STATE		ROADWAY 0003	LANDSCAPING 0031
			URBAN TOTAL			
54215430	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30"	EACH	1		1	
54217722	REINFORCED CONCRETE PIPE TEE, 48" PIPE WITH 24" RISER	EACH	1		1	
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1		1	
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1		1	
54247180	GRATING FOR CONCRETE FLARED END SECTION 42"	EACH	1		1	
54248510	CONCRETE COLLAR	CU YD	1		1	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	43		43	
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	25		25	
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	50		50	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,070		1,070	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	825		825	
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	2,427		2,427	
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	450		450	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	3,301		3,301	
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	3,612		3,612	
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	2,455		2,455	

n:\proj\338942\ext\design\mascamhwa\33894-50002.dgn

 ENGINEERING CONSULTANT Clorn Group Inc. CONSULTING ENGINEERS <small>6007 North Cumberland Avenue, Suite 402 Chicago, Illinois 60630 Tel: 773.776.4000 Fax: 773.776.4014 Email: cgroup@clorn.com</small>	USER NAME = jvondra	DESIGNED - CRC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.I. 80 FROM US 30 TO NS RAILROAD SUMMARY OF QUANTITIES	F.A.I. RTE. 80	SECTION 99-5-Y	COUNTY WILL	TOTAL SHEETS 277	SHEET NO. 5
	PLT SCALE = 1:8000' / IN. PLT DATE = 10/28/2010	DRAWN - JMK CHECKED - MRJ DATE - 10/27/2010	REVISED - REVISED - REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 60147			

Rev.