

90% FED.
10% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0003	LANDSCAPING 0031
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3	
63200310	GUARDRAIL REMOVAL	FOOT	860	860	
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	100	100	
6330120	DELINEATOR REMOVAL	EACH	49	49	
63700175	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	1,708	1,708	
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	6,297	6,297	
6370279	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT (SPECIAL)	FOOT	181	181	
63700805	CONCRETE BARRIER TRANSITION	FOOT	907	907	
63700900	CONCRETE BARRIER BASE	FOOT	17,410	17,410	
64200105	SHOULDER RUMBLE STRIPS	FOOT	47,585	47,585	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	2	2	
66700705	FURNISHING AND ERECTING DRAINAGE MARKERS	EACH	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	9	9	

* DENOTES SPECIALTY ITEM

90% FED.
10% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0003	LANDSCAPING 0031
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	64,800	64,800	
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	9,050	9,050	
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	680	680	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	28,320	28,320	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	39,650	39,650	
7040210	RELOCATE TEMPORARY CONCRETE BARRIER, SPECIAL	FOOT	315	315	
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	466	466	
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	17,290	17,290	
* 72000100	SIGN PANEL-TYPE 1	SQ FT	37	37	
* 72000200	SIGN PANEL-TYPE 2	SQ FT	508	508	
* 72000300	SIGN PANEL-TYPE 3	SQ FT	3,332	3,332	
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	15	15	
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	29	29	
* 72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	3,009	3,009	
72600100	MILEPOST MARKER ASSEMBLY	EACH	14	14	

n:\pro\3384\2-west\design\masshwy3384-50004.dgn



USER NAME = jvandra	DESIGNED - CRC	REVISED -
PLOT SCALE = 1/8" = 1' IN.	DRAWN - JMK	REVISED -
PLOT DATE = 12/28/2010	CHECKED - MRJ	REVISED -
	DATE - 10/27/2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.I. 80 FROM US 30 TO NS RAILROAD SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.I. RTE. 80	SECTION 99-5-Y	COUNTY WILL	TOTAL SHEETS 277	SHEET NO. 7
CONTRACT NO. 60147				
ILLINOIS FED. AID PROJECT				

Rev.