

CODE NO.	ITEM	UNIT	90% FED. 10% STATE		
			URBAN TOTAL	ROADWAY 0003	LANDSCAPING 0031
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	199	199	
* 73000100	WOOD SIGN SUPPORT	FOOT	306	306	
* 73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36"x5'-6")	FOOT	28	28	
* 73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	46	46	
* 73400100	CONCRETE FOUNDATIONS	CU YD	24.4	24.4	
* 73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	74.4	74.4	
* 73500100	RELOCATE OVERHEAD SIGN STRUCTURE - SPAN	EACH	2	2	
* 73500200	RELOCATE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1	1	
* 73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	6	6	
* 73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	2	2	
* 73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	2	2	
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	338	338	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	56,588	56,588	
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	16,652	16,652	
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	16,285	16,285	
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	3,130	3,130	

* DENOTES SPECIALTY ITEM

CODE NO.	ITEM	UNIT	90% FED. 10% STATE		
			URBAN TOTAL	ROADWAY 0003	LANDSCAPING 0031
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	791	791	
* 78100300	REPLACEMENT REFLECTOR	EACH	160	160	
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	90	90	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	25	25	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	2,720	2,720	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	29,258	29,258	
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1	
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	250	250	
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	350	350	
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	16,500	16,500	
* 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	975	975	
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	1125	1125	
* 81400200	HEAVY-DUTY HANDHOLE	EACH	10	10	
* 81603037	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA., POLYETHYLENE	FOOT	900	900	

N:\PROJ\3384\2-West\Design\Misc\Sheet\3384-5006.dgn



USER NAME = oodriwell
 PLOT SCALE = 1/8" = 1' / IN.
 PLOT DATE = 10/28/2010

DESIGNED - CRC
 DRAWN - JMK
 CHECKED - MRJ
 DATE - 10/27/2010

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

F.A.I. 80 FROM US 30 TO NS RAILROAD
 SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE. 80 SECTION 99-5-Y COUNTY WILL TOTAL SHEETS 277 SHEET NO. 8 CONTRACT NO. 60147 ILLINOIS FED. AID PROJECT

Rev.