

STATION			STAGE 1					STAGE 2				
			20200100		20201200			20200100		20201200		
EARTH EXCAVATION			EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION			EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	
(CU YD)			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
I-80 FROM US 30 TO NS RAILROAD												
711+00.00	TO	712+00.00	0.0	0.0	0.0	0.0	0.0	130.2	110.7	50.0	4.3	106.4
712+00.00	TO	713+00.00	0.0	0.0	0.0	0.0	0.0	138.9	118.1	56.9	0.7	117.3
713+00.00	TO	714+00.00	0.0	0.0	0.0	0.0	0.0	135.7	115.4	100.7	15.7	99.6
714+00.00	TO	715+00.00	0.0	0.0	0.0	0.0	0.0	138.0	117.3	124.3	20.2	97.1
715+00.00	TO	715+85.95	0.0	0.0	0.0	0.0	0.0	48.9	41.5	61.9	14.0	27.5
715+85.95	TO	716+00.00	10.8	9.2	8.2	0.2	9.0	0.0	0.0	5.3	3.8	-3.8
716+00.00	TO	717+00.00	78.0	66.3	58.5	3.3	62.9	0.0	0.0	33.1	24.1	-24.1
717+00.00	TO	717+25.00	19.4	16.5	15.3	1.1	15.4	0.0	0.0	3.5	3.6	-3.6
717+25.00	TO	717+40.00	11.7	10.0	9.6	0.5	9.5	0.0	0.0	3.0	3.3	-3.3
717+40.00	TO	718+00.00	50.1	42.6	36.7	2.2	40.4	0.0	0.0	10.9	9.8	-9.8
718+00.00	TO	719+00.00	81.5	69.3	58.5	8.9	60.4	0.0	0.0	0.0	0.0	0.0
719+00.00	TO	720+00.00	81.5	69.3	58.5	8.5	60.7	0.0	0.0	0.0	0.0	0.0
720+00.00	TO	721+00.00	89.4	76.0	58.5	3.0	73.1	0.0	0.0	0.0	0.0	0.0
721+00.00	TO	722+00.00	89.4	76.0	58.5	2.6	73.4	0.0	0.0	0.0	0.0	0.0
722+00.00	TO	723+00.00	83.7	71.1	58.5	4.3	66.9	0.0	0.0	0.0	0.0	0.0
723+00.00	TO	724+00.00	77.0	65.5	58.5	8.3	57.1	0.0	0.0	0.0	0.0	0.0
724+00.00	TO	725+00.00	75.0	63.8	58.5	8.5	55.2	0.0	0.0	0.0	0.0	0.0
725+00.00	TO	726+00.00	69.1	58.7	58.3	11.3	47.4	0.0	0.0	0.0	0.0	0.0
726+00.00	TO	727+00.00	61.7	52.4	58.3	20.9	31.5	0.0	0.0	0.0	0.0	0.0
727+00.00	TO	728+00.00	68.3	58.1	58.3	21.5	36.6	0.0	0.0	0.0	0.0	0.0
728+00.00	TO	729+00.00	93.5	79.5	58.3	8.9	70.6	0.0	0.0	0.0	0.0	0.0
729+00.00	TO	730+00.00	89.1	75.7	58.5	7.4	68.3	0.0	0.0	0.0	0.0	0.0
730+00.00	TO	731+00.00	69.4	59.0	58.5	16.1	42.9	0.0	0.0	0.0	0.0	0.0
731+00.00	TO	732+00.00	72.6	61.7	58.5	17.0	44.7	0.0	0.0	0.0	0.0	0.0
732+00.00	TO	733+00.00	73.9	62.8	58.5	15.6	47.3	0.0	0.0	0.0	0.0	0.0
733+00.00	TO	734+00.00	79.8	67.8	58.5	11.9	56.0	0.0	0.0	0.0	0.0	0.0
734+00.00	TO	735+00.00	82.2	69.9	58.5	11.3	58.6	0.0	0.0	0.0	0.0	0.0
735+00.00	TO	736+00.00	75.4	64.1	58.5	13.3	50.7	0.0	0.0	0.0	0.0	0.0
736+00.00	TO	737+00.00	75.2	63.9	58.5	14.4	49.5	0.0	0.0	0.0	0.0	0.0
737+00.00	TO	738+00.00	82.8	70.4	58.5	15.0	55.4	0.0	0.0	0.0	0.0	0.0
738+00.00	TO	739+00.00	83.5	71.0	61.9	15.2	55.8	83.5	71.0	67.8	7.4	63.6
739+00.00	TO	740+00.00	76.9	65.3	61.9	15.2	50.1	138.3	117.6	123.7	9.4	108.1
740+00.00	TO	741+00.00	73.1	62.2	58.5	13.7	48.5	81.9	69.6	91.3	3.3	66.2
741+00.00	TO	742+00.00	76.3	64.9	58.5	11.5	53.4	27.0	23.0	35.4	1.3	21.7
742+00.00	TO	743+00.00	128.5	109.2	60.0	5.0	104.2	10.0	8.5	16.7	1.3	7.2
743+00.00	TO	744+00.00	115.9	98.5	66.5	25.6	73.0	14.8	12.6	31.9	2.2	10.4
744+00.00	TO	745+00.00	57.0	48.5	69.8	38.7	9.8	17.4	14.8	40.4	2.2	12.6
745+00.00	TO	746+00.00	65.2	55.4	67.6	23.9	31.5	13.1	11.2	56.7	9.1	2.1
746+00.00	TO	747+00.00	75.6	64.2	67.0	18.3	45.9	5.0	4.3	66.9	27.4	-23.2
747+00.00	TO	747+35.00	26.3	22.4	23.3	4.5	17.9	1.6	1.3	22.7	15.7	-14.4
747+35.00	TO	747+50.00	10.4	8.9	9.9	1.5	7.4	0.0	0.0	9.1	8.0	-8.0
747+50.00	TO	748+00.00	37.8	32.1	32.7	4.0	28.1	1.4	1.2	28.3	22.3	-21.1
748+00.00	TO	749+00.00	81.5	69.3	65.0	6.7	62.6	3.7	3.1	55.9	50.9	-47.8
749+00.00	TO	750+00.00	74.8	63.6	65.0	7.0	56.6	5.2	4.4	77.0	49.1	-44.7
750+00.00	TO	751+00.00	61.3	52.1	66.9	23.5	28.6	6.1	5.2	69.8	35.9	-30.7
751+00.00	TO	752+00.00	60.0	51.0	67.4	28.0	23.0	7.2	6.1	49.3	23.3	-17.2
752+00.00	TO	753+00.00	66.5	56.5	66.1	15.6	41.0	5.4	4.6	26.1	1.9	2.7
753+00.00	TO	754+00.00	67.2	57.1	62.4	16.1	41.0	0.0	0.0	0.0	0.0	0.0
754+00.00	TO	755+00.00	67.4	57.3	58.5	16.5	40.8	0.0	0.0	0.0	0.0	0.0
755+00.00	TO	756+00.00	71.3	60.6	58.5	12.2	48.4	0.0	0.0	0.0	0.0	0.0
756+00.00	TO	757+00.00	73.7	62.6	58.5	11.3	51.4	0.0	0.0	0.0	0.0	0.0

c:\pco\13304\2\_earth\design\chicago\13304w\_01\_earth.dgn

**ENGINEERING CONSULTANT**  
 **Giorba Group, Inc.**  
 CONSULTING ENGINEERS  
 600 North Dearborn Street, Suite 402  
 Chicago, Illinois 60654  
 Tel: 773.775.4000 Fax: 773.775.4014  
 Email: chicago@giorba.com

USER NAME = ccornwell	DESIGNED - CRC	REVISED -
FLUT SCALE = 1:8000' / IN.	DRAWN - JMK	REVISED -
PLOT DATE = 10/27/2010	CHECKED - MRJ	REVISED -
	DATE - 10/27/2010	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**F.A.I. 80 FROM US 30 TO NS RAILROAD  
EARTHWORK SCHEDULES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99-5-Y	WILL	276	15
CONTRACT NO. 60147				
ILLINOIS FED. AID PROJECT				