

STATION			STAGE 1					STAGE 2				
			20200100		20201200			20200100		20201200		
EARTH EXCAVATION			EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION			EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	
(CU YD)			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
I-80 FROM US 30 TO NS RAILROAD												
757+00.00	TO	758+00.00	70.4	59.8	58.5	14.3	45.6	0.0	0.0	0.0	0.0	0.0
758+00.00	TO	759+00.00	68.9	58.6	58.5	17.0	41.5	0.0	0.0	0.0	0.0	0.0
759+00.00	TO	760+00.00	68.5	58.2	58.3	37.8	20.5	0.0	0.0	0.0	0.0	0.0
760+00.00	TO	761+00.00	70.0	59.5	58.3	35.9	23.6	0.0	0.0	0.0	0.0	0.0
761+00.00	TO	762+00.00	72.2	61.4	58.5	16.1	45.3	0.0	0.0	0.0	0.0	0.0
762+00.00	TO	763+00.00	68.0	57.8	58.5	18.1	39.6	0.0	0.0	0.0	0.0	0.0
763+00.00	TO	764+00.00	67.4	57.3	58.5	18.9	38.4	0.0	0.0	0.0	0.0	0.0
764+00.00	TO	765+00.00	71.3	60.6	58.5	16.9	43.8	0.0	0.0	0.0	0.0	0.0
765+00.00	TO	766+00.00	70.7	60.1	58.3	14.4	45.7	0.0	0.0	0.0	0.0	0.0
766+00.00	TO	767+00.00	75.7	64.4	58.3	10.7	53.6	0.0	0.0	8.7	3.5	-3.5
767+00.00	TO	767+20.00	15.4	13.1	12.3	2.2	10.9	0.0	0.0	3.6	1.4	-1.4
767+20.00	TO	768+00.00	60.6	51.5	49.2	9.3	42.2	0.0	0.0	12.4	5.0	-5.0
768+00.00	TO	769+00.00	78.5	66.7	58.3	10.2	56.6	0.0	0.0	12.0	3.9	-3.9
769+00.00	TO	770+00.00	75.6	64.2	61.5	10.9	53.3	0.0	0.0	10.0	2.0	-2.0
770+00.00	TO	771+00.00	64.3	54.6	65.2	17.8	36.8	0.0	0.0	4.4	0.7	-0.7
771+00.00	TO	772+00.00	71.3	60.6	64.3	13.5	47.1	0.0	0.0	0.0	0.0	0.0
772+00.00	TO	773+00.00	89.6	76.2	63.1	1.5	74.7	0.0	0.0	0.0	0.0	0.0
773+00.00	TO	774+00.00	91.1	77.4	63.1	0.2	77.3	0.0	0.0	0.0	0.0	0.0
774+00.00	TO	775+00.00	84.3	71.6	63.0	0.7	70.9	0.0	0.0	0.0	0.0	0.0
775+00.00	TO	776+00.00	85.7	72.9	60.7	0.9	72.0	0.0	0.0	0.0	0.0	0.0
776+00.00	TO	777+00.00	82.4	70.0	58.5	6.9	63.2	0.0	0.0	0.0	0.0	0.0
777+00.00	TO	778+00.00	77.0	65.5	58.5	10.4	55.1	0.0	0.0	0.0	0.0	0.0
778+00.00	TO	779+00.00	81.7	69.4	58.5	5.0	64.4	0.0	0.0	0.0	0.0	0.0
779+00.00	TO	780+00.00	76.9	65.3	58.5	6.1	59.2	0.0	0.0	0.0	0.0	0.0
780+00.00	TO	781+00.00	73.0	62.0	58.5	7.4	54.6	0.0	0.0	0.0	0.0	0.0
781+00.00	TO	782+00.00	78.1	66.4	58.5	2.8	63.6	0.0	0.0	0.0	0.0	0.0
782+00.00	TO	783+00.00	76.3	64.9	61.1	3.9	61.0	0.0	0.0	0.0	0.0	0.0
783+00.00	TO	784+00.00	65.4	55.6	64.3	13.5	42.0	0.2	0.2	11.9	3.0	-2.8
784+00.00	TO	785+00.00	64.4	54.8	64.8	14.4	40.3	0.2	0.2	21.1	4.4	-4.3
785+00.00	TO	786+00.00	68.9	58.6	64.6	9.8	48.7	5.6	4.7	62.4	7.2	-2.5
786+00.00	TO	787+00.00	68.0	57.8	64.4	13.7	44.1	8.0	6.8	78.1	10.7	-4.0
787+00.00	TO	788+00.00	67.8	57.6	64.6	15.0	42.6	4.1	3.5	55.6	8.9	-5.4
788+00.00	TO	789+00.00	72.4	61.5	64.6	12.8	48.8	8.1	6.9	50.6	4.8	2.1
789+00.00	TO	790+00.00	71.9	61.1	64.6	10.9	50.1	6.7	5.7	30.4	3.0	2.7
790+00.00	TO	791+00.00	64.1	54.5	64.3	11.1	43.4	0.9	0.8	25.4	3.7	-2.9
791+00.00	TO	792+00.00	73.5	62.5	63.1	6.5	56.0	0.9	0.8	34.3	5.4	-4.6
792+00.00	TO	793+00.00	80.4	68.3	63.3	4.8	63.5	0.4	0.3	36.3	7.4	-7.1
793+00.00	TO	794+00.00	78.5	66.7	63.5	5.2	61.6	8.9	7.6	62.4	7.0	0.5
794+00.00	TO	795+00.00	75.9	64.5	63.1	3.0	61.6	10.7	9.1	82.2	9.3	-0.1
795+00.00	TO	796+00.00	71.9	61.1	63.9	4.6	56.4	3.7	3.1	67.2	10.7	-7.6
796+00.00	TO	797+00.00	83.0	70.5	64.1	2.4	68.1	8.9	7.6	67.6	8.1	-0.6
797+00.00	TO	798+00.00	82.6	70.2	63.1	1.5	68.7	15.0	12.8	82.0	6.1	6.6
798+00.00	TO	799+00.00	86.7	73.7	62.0	1.1	72.6	27.4	23.3	88.9	3.9	19.4
799+00.00	TO	800+00.00	118.9	101.1	60.4	0.0	101.1	19.6	16.7	44.1	1.1	15.6
800+00.00	TO	801+00.00	120.7	102.6	54.8	0.0	102.6	0.0	0.0	0.0	0.0	0.0
801+00.00	TO	802+00.00	84.6	71.9	54.4	9.3	62.7	0.0	0.0	0.0	0.0	0.0
802+00.00	TO	803+00.00	69.1	58.7	58.3	19.6	39.1	0.0	0.0	0.0	0.0	0.0
803+00.00	TO	804+00.00	72.4	61.5	59.6	15.6	46.0	0.0	0.0	0.0	0.0	0.0
804+00.00	TO	805+00.00	72.8	61.9	59.8	11.7	50.2	0.0	0.0	0.0	0.0	0.0
805+00.00	TO	806+00.00	69.4	59.0	58.5	15.6	43.5	0.0	0.0	0.0	0.0	0.0
806+00.00	TO	807+00.00	71.3	60.6	58.3	15.4	45.2	0.0	0.0	0.0	0.0	0.0

c:\pco\338412\west\design\misc\sheet_33841-EM_schert02.dgn



ENGINEERING CONSULTANT	USER NAME = ccoarnwell	DESIGNED - CRC	REVISED -
CLORBA GROUP, INC.	PLLOT SCALE = 1:8000' / IN.	DRAWN - JMK	REVISED -
	PLLOT DATE = 10/27/2010	CHECKED - MRJ	REVISED -
		DATE - 10/27/2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**F.A.I. 80 FROM US 30 TO NS RAILROAD
EARTHWORK SCHEDULES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99-5-Y	WILL	276	16
CONTRACT NO. 60147			ILLINOIS FED. AID PROJECT	