


STATION	STAGE 1					STAGE 2						
	20200100		20201200			20200100		20201200				
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
I-80 FROM US 30 TO NS RAILROAD	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)		
807+00.00	TO	808+00.00	70.0	59.5	58.3	17.2	42.3	0.0	0.0	0.0	0.0	
808+00.00	TO	809+00.00	59.1	50.2	58.5	23.0	27.3	0.0	0.0	0.0	0.0	
809+00.00	TO	810+00.00	64.8	55.1	58.5	15.4	39.7	0.0	0.0	0.0	0.0	
810+00.00	TO	811+00.00	72.8	61.9	58.5	5.6	56.3	0.0	0.0	0.0	0.0	
811+00.00	TO	812+00.00	93.3	79.3	58.5	2.2	77.1	0.0	0.0	0.0	0.0	
812+00.00	TO	813+00.00	126.1	107.2	58.5	0.0	107.2	0.0	0.0	0.0	0.0	
813+00.00	TO	814+00.00	129.1	109.7	59.4	0.0	109.7	0.0	0.0	0.0	0.0	
814+00.00	TO	815+00.00	99.1	84.2	61.9	3.0	81.3	0.0	0.0	0.0	0.0	
815+00.00	TO	816+00.00	68.0	57.8	64.8	17.2	40.5	36.9	31.3	36.7	0.7	30.6
816+00.00	TO	817+00.00	61.9	52.6	66.5	26.7	25.9	173.0	147.0	82.4	1.5	145.5
817+00.00	TO	818+00.00	60.4	51.3	66.5	25.0	26.3	399.4	339.5	100.6	1.3	338.2
818+00.00	TO	819+00.00	63.3	53.8	62.4	18.3	35.5	542.0	460.7	124.6	1.1	459.6
819+00.00	TO	820+00.00	69.3	58.9	58.5	9.8	49.1	278.7	236.9	69.8	0.6	236.3
820+00.00	TO	821+00.00	72.4	61.5	58.5	6.5	55.1	0.0	0.0	0.0	0.0	0.0
821+00.00	TO	822+00.00	69.3	58.9	58.5	10.7	48.1	0.0	0.0	0.0	0.0	0.0
822+00.00	TO	823+00.00	64.8	55.1	58.5	15.0	40.1	0.0	0.0	0.0	0.0	0.0
823+00.00	TO	824+00.00	59.3	50.4	58.5	47.8	2.6	0.0	0.0	0.0	0.0	0.0
824+00.00	TO	825+00.00	68.0	57.8	58.5	42.8	15.0	0.0	0.0	0.0	0.0	0.0
825+00.00	TO	826+00.00	90.6	77.0	58.5	1.7	75.3	0.0	0.0	0.0	0.0	0.0
826+00.00	TO	827+00.00	110.9	94.3	58.5	0.0	94.3	0.0	0.0	0.0	0.0	0.0
827+00.00	TO	828+00.00	133.9	113.8	58.5	0.0	113.8	0.0	0.0	0.0	0.0	0.0
828+00.00	TO	829+00.00	145.6	123.7	58.5	0.0	123.7	0.0	0.0	0.0	0.0	0.0
829+00.00	TO	830+00.00	110.0	93.5	58.5	6.1	87.4	0.0	0.0	0.0	0.0	0.0
830+00.00	TO	831+00.00	72.2	61.4	58.5	12.6	48.8	0.0	0.0	0.0	0.0	0.0
831+00.00	TO	832+00.00	71.5	60.8	58.5	14.6	46.1	0.0	0.0	0.0	0.0	0.0
832+00.00	TO	833+00.00	71.9	61.1	58.5	17.4	43.7	0.0	0.0	0.0	0.0	0.0
833+00.00	TO	834+00.00	71.7	60.9	58.5	21.3	39.6	0.0	0.0	0.0	0.0	0.0
834+00.00	TO	835+00.00	70.0	59.5	52.4	19.6	39.9	0.0	0.0	0.0	0.0	0.0
835+00.00	TO	836+00.00	68.3	58.1	52.4	15.7	42.3	0.0	0.0	0.0	0.0	0.0
836+00.00	TO	837+00.00	62.4	53.0	58.5	18.9	34.2	0.0	0.0	0.0	0.0	0.0
837+00.00	TO	838+00.00	63.0	53.5	58.5	18.7	34.8	0.0	0.0	0.0	0.0	0.0
838+00.00	TO	839+00.00	64.8	55.1	58.5	17.4	37.7	0.0	0.0	0.0	0.0	0.0
839+00.00	TO	840+00.00	68.3	58.1	58.5	16.5	41.6	0.0	0.0	0.0	0.0	0.0
840+00.00	TO	841+00.00	73.0	62.0	58.5	13.9	48.1	0.0	0.0	0.0	0.0	0.0
841+00.00	TO	842+00.00	67.6	57.5	58.5	18.3	39.1	0.0	0.0	0.0	0.0	0.0
842+00.00	TO	843+00.00	65.7	55.9	58.5	21.1	34.8	0.0	0.0	0.0	0.0	0.0
843+00.00	TO	844+00.00	66.9	56.8	58.5	20.7	36.1	0.0	0.0	0.0	0.0	0.0
844+00.00	TO	845+00.00	62.8	53.4	58.5	19.4	33.9	0.0	0.0	0.0	0.0	0.0
845+00.00	TO	846+00.00	60.6	51.5	58.5	20.6	30.9	0.0	0.0	0.0	0.0	0.0
846+00.00	TO	847+00.00	61.3	52.1	58.3	23.0	29.1	0.0	0.0	0.0	0.0	0.0
847+00.00	TO	848+00.00	65.0	55.3	58.3	18.7	36.5	0.0	0.0	0.0	0.0	0.0
848+00.00	TO	849+00.00	72.6	61.7	58.5	12.2	49.5	0.0	0.0	0.0	0.0	0.0
849+00.00	TO	850+00.00	76.1	64.7	58.5	6.3	58.4	0.0	0.0	0.0	0.0	0.0
850+00.00	TO	851+00.00	75.2	63.9	58.5	6.3	57.6	0.0	0.0	0.0	0.0	0.0
851+00.00	TO	852+00.00	73.3	62.3	58.5	8.9	53.4	0.0	0.0	0.0	0.0	0.0
852+00.00	TO	853+00.00	69.1	58.7	58.5	14.3	44.5	0.0	0.0	0.0	0.0	0.0
853+00.00	TO	854+00.00	68.0	57.8	58.5	16.1	41.7	0.0	0.0	0.0	0.0	0.0
854+00.00	TO	855+00.00	69.3	58.9	58.5	16.7	42.2	0.0	0.0	0.0	0.0	0.0
855+00.00	TO	856+00.00	71.9	61.1	58.3	14.8	46.3	0.0	0.0	0.0	0.0	0.0
856+00.00	TO	857+00.00	71.9	61.1	58.3	10.0	51.1	0.0	0.0	0.0	0.0	0.0
857+00.00	TO	858+00.00	70.4	59.8	58.3	13.1	46.7	0.0	0.0	0.0	0.0	0.0

n:\proj\1338412\env\1\design\misc\sheet\338412-EV_sch02.dgn

 ENGINEERING CONSULTANT Clorba Group, Inc. CONSULTING ENGINEERS <small>507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60610 Tel: 773.775.4008 Fax: 773.775.4014 Email: clorba@clorba.com</small>	USER NAME = ccorneill PLOT SCALE = 1:2000' / IN. PLOT DATE = 10/27/2010	DESIGNED - CRC DRAWN - JMK CHECKED - MRJ DATE - 10/27/2010	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.I. 80 FROM US 30 TO NS RAILROAD EARTHWORK SCHEDULES	SCALE:	SHEET NO. OF SHEETS STA. TO STA.	F.A.I. RTE. 80	SECTION 99-5-Y	COUNTY WILL	TOTAL SHEETS 276	SHEET NO. 17	CONTRACT NO. 60147	ILLINOIS FED. AID PROJECT
	ILLINOIS FED. AID PROJECT													