


STATION	STAGE 1					STAGE 2						
	20200100		20201200			20200100		20201200				
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
I-80 FROM US 30 TO NS RAILROAD	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)		
858+00.00	TO	859+00.00	74.8	63.6	58.3	14.6	49.0	0.0	0.0	0.0	0.0	
859+00.00	TO	860+00.00	73.0	62.0	58.5	16.3	45.7	0.0	0.0	0.0	0.0	
860+00.00	TO	861+00.00	75.4	64.1	58.5	14.6	49.4	0.0	0.0	0.0	0.0	
861+00.00	TO	862+00.00	77.4	65.8	58.5	10.4	55.4	0.0	0.0	0.0	0.0	
862+00.00	TO	863+00.00	75.7	64.4	58.3	6.7	57.7	0.0	0.0	0.0	0.0	
863+00.00	TO	864+00.00	79.6	67.7	58.3	3.0	64.7	0.0	0.0	0.0	0.0	
864+00.00	TO	865+00.00	82.8	70.4	58.5	2.8	67.6	0.0	0.0	0.0	0.0	
865+00.00	TO	866+00.00	80.0	68.0	58.5	3.9	64.1	0.0	0.0	0.0	0.0	
866+00.00	TO	867+00.00	75.9	64.5	58.5	6.5	58.1	0.0	0.0	0.0	0.0	
867+00.00	TO	868+00.00	72.2	61.4	58.5	12.8	48.6	0.0	0.0	0.0	0.0	
868+00.00	TO	869+00.00	101.5	86.3	58.5	8.9	77.4	0.0	0.0	0.0	0.0	
869+00.00	TO	870+00.00	130.4	110.8	58.5	0.0	110.8	0.0	0.0	0.0	0.0	
870+00.00	TO	871+00.00	93.1	79.2	58.5	10.4	68.8	0.0	0.0	0.0	0.0	
871+00.00	TO	872+00.00	59.8	50.8	61.9	20.9	29.9	0.0	0.0	0.0	0.0	
872+00.00	TO	873+00.00	62.6	53.2	64.8	17.6	35.6	0.0	0.0	0.0	0.0	
873+00.00	TO	874+00.00	68.7	58.4	65.2	17.2	41.2	0.0	0.0	0.0	0.0	
874+00.00	TO	875+00.00	65.7	55.9	66.7	27.2	28.7	0.0	0.0	0.0	0.0	
875+00.00	TO	876+00.00	64.3	54.6	63.0	31.5	23.1	0.0	0.0	0.0	0.0	
876+00.00	TO	877+00.00	67.0	57.0	58.5	28.3	28.6	0.0	0.0	0.0	0.0	
877+00.00	TO	878+00.00	70.6	60.0	58.5	22.2	37.8	0.0	0.0	0.0	0.0	
878+00.00	TO	879+00.00	75.7	64.4	58.5	16.1	48.3	6.1	5.2	13.7	0.9	
879+00.00	TO	880+00.00	76.1	64.7	58.5	15.4	49.3	6.1	5.2	13.7	0.9	
880+00.00	TO	881+00.00	77.6	66.0	58.5	12.8	53.2	0.0	0.0	0.0	0.0	
881+00.00	TO	882+00.00	79.3	67.4	58.5	10.2	57.2	0.0	0.0	0.0	0.0	
882+00.00	TO	882+50.00	39.3	33.4	27.1	6.0	27.4	0.0	0.0	0.0	0.0	
TOTALS			12,795	10,876	10,009	2,154	8,721	2,585	2,197	2,711	499	1,698

SUMMARY						
	20200100		20201200			20400800
STAGE	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	FURNISHED EXCAVATION
1	12,795	10,876	10,009	2,154	8,721	0
2	2,585	2,197	2,711	499	1,698	0
TOTAL	15,380	13,073	12,721	2,653	10,419	0

n:\pro\133842\east\design\Misc\Sheets\33944-FW\_sch266.dgn

 <b>ENGINEERING CONSULTANT</b> Clorba Group, Inc. CONSULTING ENGINEERS 5007 North Cumberland Avenue, Suite 402 Chicago, Illinois 60630 Tel: 773.776.4003 Fax: 773.776.4014 Email: clogr@clorba.com	USER NAME = caarnwell	DESIGNED - CRC	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>F.A.I. 80 FROM US 30 TO NS RAILROAD</b> <b>EARTHWORK SCHEDULES</b>	F.A.I. RTE. = 80	SECTION = 99-5-Y	COUNTY = WILL	TOTAL SHEETS = 276	SHEET NO. = 18
	PLOT SCALE = 1:8000 / IN.	CHECKED - MRJ	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 60147	
	PLOT DATE = 10/27/2010	DATE = 10/27/2010	REVISED -			ILLINOIS FED. AID PROJECT				