

TREE REMOVAL (6 TO 15 UNIT DIAMETER) (20100110)		
LOCATION	AMOUNT	UNIT
STATION		
734+15	6	10
735+50	6	10
740+53	1	8
743+83	3	6
744+10	4	6
744+67	1	6
744+95	1	6
746+91	1	6
751+50	2	6
818+15	1	14
818+31	1	10
818+68	1	12
818+84	1	12
831+82	1	10
874+71	8	5
875+21	8	5
TOTAL		338

GUTTER REMOVAL (44000400)			
STATION	STATION		FEET
741+30	741+66		36
		TOTAL	36

CONCRETE HEADWALL REMOVAL (50104400)				
Station	Location	Type	Volume (cu yd)	Each
741+34	LT	60" SKEWED	9.25	1
742+90	LT	60" SKEWED	6.1	1
801+72	RT	36"	1.3	2
868+60	CL	24"	1	1
TOTAL				5

TRAFFIC BARRIER TERMINAL, TYPE 2 (63100045)		
FROM STATION	L/R	EACH
WESTBOUND LANES		
741+14.49	L	1
EASTBOUND LANES		
770+60.36	R	1
TOTAL		2

PAVED DITCH REMOVAL (44004000)		
STATION	L/R	FEET
743+25	93' LT	75
875+30	93' LT	45
TOTAL		120

REMOVING CATCH BASINS (60500050)	
LOCATION	EACH
STATION	
743+98	1
TOTAL	1

TRAFFIC BARRIER TERMINAL, TYPE 6B (63100089)		
FROM STATION	L/R	EACH
WESTBOUND LANES		
745+15.28	L	1
TOTAL		1

AGGREGATE SHOULDERS, TYPE B 6" (48101500)			
LOCATION			SQUARE YARD
STATION	STATION	Length	
741+27	742+39	113	50
745+58	747+08	150	67
767+48	770+60	313	139
741+14		13	6
770+60		13	6
745+15		43	19
742+39		2	1
716+94		50	22
747+08		50	22
766+98		50	22
713+44		350	156
TOTAL			509

REMOVING INLETS (60500060)	
LOCATION	EACH
STATION	
770+67	1
823+89	1
TOTAL	2

TRAFFIC BARRIER TERMINAL, TYPE 10 (63100105)		
FROM STATION	L/R	EACH
WESTBOUND LANES		
742+39.49	L	1
TOTAL		1

STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2" (31200502)			
LOCATION		WIDTH	SQUARE YARD
STATION	STATION		
715+85	742+92	27	8120
742+92	743+53	24	163
743+53	800+44	27	17074
800+45	801+32	24	228
801+32	813+03	27	3513
813+03	813+66	24	166
813+66	828+06	27	4318
828+06	828+68	23	162
828+68	882+50	27	16146
TOTAL		230	49890

STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS (6300001)				
FROM STATION	L/R	TO STATION	L/R	LENGTH (FOOT)
WESTBOUND LANES				
741+26.99	L	742+39.49	L	112.5
745+58.43	L	747+08.43	L	150.0
EASTBOUND LANES				
767+47.86	R	770+60.36	R	312.5
TOTAL				575.0

TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) TANGENT (63100167)		
FROM STATION	L/R	EACH
WESTBOUND LANES		
716+93.84	L	1
747+08.43	L	1
EASTBOUND LANES		
766+97.86	R	1
TOTAL		3

PORTLAND CEMENT CONCRETE SHOULDERS 12 1/4"(48300705)			
LOCATION			SQUARE YARD
STATION	STATION	Length	
715+85	882+50	16665	44440
TOTAL			44440

STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL) (630000130)				
FROM STATION	L/R	TO STATION	L/R	LENGTH (FOOT)
WESTBOUND LANES				
713+43.84	L	716+93.84	L	350.0
EASTBOUND LANES				
TOTAL				350.0

GUARDRAIL REMOVAL (63200310)				
FROM STATION	L/R	TO STATION	L/R	LENGTH (FOOT)
WESTBOUND LANES				
713+44	L	713+94	L	50
745+15	L	745+98	L	83
MEDIAN				
727+51		728+33		82
729+06		729+88		81
759+57		760+38		81
761+06		761+86		81
795+01		797+15		213
839+66		841+55		189
TOTAL				860

PAVEMENT REMOVAL (44000100)		
LOCATION		SQUARE YARD
STATION	STATION	
728+54	728+81	81
742+77	743+08	26
743+37	743+73	28
760+55	760+82	81
794+98	797+22	75
801+17	801+69	92
813+51	814+04	88
828+53	829+04	91
839+64	841+60	54
869+36	869+64	22
869+80	870+15	23
TOTAL		661

CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT (63700175)			
LOCATION			LENGTH (FOOT)
WB / EB	STATION	STATION	
EB	742+32	744+13	181
EB	799+55	802+21	266
WB	799+55	802+21	266
EB	812+08	814+62	254
WB	812+08	814+62	254
EB	827+15	829+59	244
WB	827+15	829+59	244
TOTAL			1708

c:\pco\1338A\2-west\design\m\contract\m\1338A\2-west\sheet\sheet2.dwg