



- LEGEND**
- ① PROPOSED PORTLAND CEMENT CONCRETE SHOULDER, 12 1/4" (48300705)
  - ② PROPOSED STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2" (31200502)
  - ③ PROPOSED AGGREGATE SUBGRADE, 12" (20001050)
  - ④ PROPOSED CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT (63700275)
  - ⑤ PROPOSED CONCRETE BARRIER, VARIABLE CROSS SECTION, 42" HEIGHT (X6370250)
  - ⑥ PROPOSED CONCRETE BARRIER, DOUBLE FACE (SPECIAL) (X0326445)
  - ▨ CLASS A PATCHES, 12 1/4"

**NOTES:**  
 SHOULDER CROSS-SLOPES INDICATED AT STATIONS ENDING IN +00 AND +50 THROUGHOUT SHOULDER WARPING AREAS.

TOP OF WALL	813+00	814+00	815+00	816+00	817+00	818+00	819+00	820+00	821+00	822+00	823+00	824+00	825+00	826+00	827+00	828+00																
	693.93	694.38	694.81	695.14	695.47	695.77	696.09	696.33	696.51	696.69	696.87	697.06	697.24	697.42	697.60	697.78	697.82	697.90	697.82	697.65	697.57	697.48	697.40	697.43	697.47	697.41	697.30	697.16	698.55			
705																																
700																																
695																																
690																																
WB CMB BASE	690.41	690.88	691.31	691.64	691.97	692.27	692.59	692.83	693.01	693.19	693.37	693.56	693.74	693.92	694.10	694.28	694.46	694.64	694.82	695.00	695.18	695.36	695.54	695.72	695.90	696.08	696.26	696.44	696.62	696.80		
EB CMB BASE	690.87	691.30	691.69	692.04	692.39	692.73	693.02	693.32	693.60	693.80	694.03	694.20	694.34	694.50	694.66	694.80	694.96	695.10	695.24	695.38	695.52	695.66	695.80	695.94	696.08	696.22	696.36	696.50	696.64	696.78	696.92	
WB PCL	690.81	691.26	691.70	692.05	692.42	692.73	693.07	693.37	693.62	693.83	694.03	694.23	694.34	694.48	694.60	694.70	694.82	694.94	695.06	695.18	695.30	695.42	695.54	695.66	695.78	695.90	696.02	696.14	696.26	696.38		
EB PCL	690.87	691.30	691.69	692.04	692.39	692.73	693.02	693.32	693.60	693.80	694.03	694.20	694.34	694.48	694.60	694.70	694.82	694.94	695.06	695.18	695.30	695.42	695.54	695.66	695.78	695.90	696.02	696.14	696.26	696.38		
	813+00	814+00	815+00	816+00	817+00	818+00	819+00	820+00	821+00	822+00	823+00	824+00	825+00	826+00	827+00	828+00																

<p><b>Clorba Group, Inc.</b>          CONSULTING ENGINEERS          2507 North Campground Avenue, Suite 402          Chicago, Illinois 60642          Tel: 773.775.4200 Fax: 773.775.4214          Email: cgroup@clorba.com</p>	USER NAME = coornwell DESIGNED - CRC DRAWN - JMK CHECKED - MRJ DATE - 10/27/2010	REVISED - REVISED - REVISED - REVISED -	<p align="center"><b>STATE OF ILLINOIS          DEPARTMENT OF TRANSPORTATION</b></p>	<p align="center"><b>F.A.I. 80 FROM US 30 TO NS RAILROAD          ROADWAY PLAN &amp; PROFILE</b></p>	F.A.I. SECTION COUNTY TOTAL SHEET NO. 80 99-5-Y WILL 276 41
	PLOT SCALE = 50.0000' / IN. PLOT DATE = 10/27/2010	DATE - 10/27/2010	SCALE: 1" = 50' SHEET NO. OF SHEETS STA. 813+00 TO STA. 826+00	CONTRACT NO. 60147 ILLINOIS FED. AID PROJECT	