

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAI 90/94 & 80	2010-054 BR	COOK & WILL	13	4

CONTRACT NO.: 60L29

SUMMARY OF QUANTITIES		CONSTRUCTION TYPE CODE: 0014			
CODE NO.	ITEMS	UNITS	100% STATE		
			URBAN TOTAL QUANTITIES	COOK CO SN 016-1153 I-90/94	WILL CO SN 099-0175 I-80
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	12800		12800
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.5	0.5
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.5	0.5
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	7160		7160
Z0001905	STRUCTURAL STEEL REPAIR	POUND	1110	1110	
Z0003600	BEAM STRAIGHTENING	L SUM	1	1	
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.5	0.5
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	77.10	51.40	25.70
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1		1
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1		1

ILLINOIS DEPARTMENT OF
TRANSPORTATION

1) I-90/94 @ 55th ST (WB) (SN 016-1153)
2) I-80 @ WHEELER RD (SN 099-0175)

SUMMARY OF QUANTITIES