

INDEX OF SHEETS:

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	COVER SHEET
2	GENERAL NOTES AND STATE STANDARDS
3	SUMMARY OF QUANTITIES
4	BUILDING DEMOLITION PLAN
5-6	EROSION CONTROL PLAN
7-9	PLAT OF HIGHWAYS (FOR INFORMATION ONLY)
10	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)
11	ARTERIAL ROAD INFORMATION SIGN (TC-22)

LIST OF STANDARDS:

- 000001-~~06~~ STANDARD SYMBOLS, ABBREVIATION AND PATTERNS
- 280001-~~05~~ TEMPORARY EROSION CONTROL SYSTEMS
- 701101-~~02~~ OFF-ROAD OPERATION, MULTILANE LESS THAN 4.5m (15') AWAY FOR SPEEDS > 45 MPH
- 701106-~~02~~ OFF-ROAD OPERATION, MULTILANE MORE THAN 4.5m (15') AWAY FOR SPEEDS > 45 MPH
- ~~702001~~ TRAFFIC CONTROL DEVICES
- 701901-01

GENERAL NOTES:

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE AT 800-892-0123 (OR 811) FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED).

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION.

THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING A DEMOLITION PERMIT FROM THE VILLAGE OF ALGONQUIN.

THE CONTRACTOR MUST CONTACT THE VILLAGE OF ALGONQUIN FOR CORRESPONDING UTILITY DISCONNECTION REQUIREMENTS.

THE CONTRACTOR MUST COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF ALGONQUIN.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED AND ONE (1) WEIGHTED SANDBAG ACROSS EACH BOTTOM FAIL.

BACKFILL USED FOR ANY HOLES, SUCH AS BASEMENTS, SHALL BE FILLED WITH POROUS GRANULAR EMB/NKMENT AND SHALL BE INCLUDED IN THE UNIT COST FOR BUILDING REMOVAL.

ALL TRAFFIC CONTROL SHALL BE INCLUDED IN THE UNIT PRICE FOR BUILDING REMOVAL.

DUST CONTROL FOR EACH SITE SHALL BE IN ACCORDANCE TO ARTICLE 107.36 OF THE STANDARD SPECIFICATIONS; AND SHALL BE INCLUDED IN THE UNIT COST FOR EACH BUILDING REMOVAL.

FILE NAME =	USER NAME = becker tom	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES AND STATE STANDARDS	F.A.P. RTG.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
at\p\work\p\jdo\becker tom\024354\Sh	ets.dgn	DRAWN -	REVISED -			860	2010-139-DM	MCHENRY	11	2	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 60N17					
	PLOT DATE = 11/1/2010	DATE -	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO. 1 OF 1 SHEETS		STA.	TO STA.		