

SUMMARY OF QUANTITIES				100% STATE						90% STATE	93.3% STATE	93.3% STATE	100% STATE	90% STATE	80% STATE	100% STATE	
				ROADWAY FAP 365	ROADWAY NAPERVILLE RD HERRICK RD	ROADWAY CROSS RDS.	IL 56	TRAFFIC SIGNAL INTERCONNECT		90% STATE WHEATON 5% DUPAGE	93.3% STATE WHEATON 6.7% DUPAGE	93.3% STATE WHEATON 6.7% DUPAGE	100% WHEATON (50% WARRENVILLE FOR HERRICK ONLY)	90% STATE 10% DUPAGE	80% STATE 20% DUPAGE	SIGNING	LANDSCAPING
CODE	DESCRIPTION	UNIT	TOTAL QUANTITY	IL 56	DUPAGE CO.	WHEATON	CULVERTS	IL 56 BUTTERFIELD RD	NAPERVILLE RD	TRAF. SIG. HERRICK-WIES. RD	TRAF. SIG. ONCHARD RD	TRAF. SIG. CROMWELL DR	EMERGENCY VEHICLE PRE-EMPTION	TRAFFIC SIGNALS NAPERVILLE RD	TRAFFIC SIGNALS DAMADA SQ.	0021	0031
28100107	STONE RIPRAP, CLASS A4	SQ YD	310	171			139										
28200200	FILTER FABRIC	SQ YD	1,088	949			139										
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	8,289	8,289													
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	640	40	600												
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	450	260	54	136											
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	355	293	62												
35600720	HOT-MIX ASPHALT BASE COURSE WIDENING, 11"	SQ YD	145			145											
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	129	106	20	3											
40600300	AGGREGATE (PRIME COAT)	TON	324	265	50	9											
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	234	58	176												
40600895	CONSTRUCTING TEST STRIP	EACH	2	2													
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	476	342	42	92											
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	21	19	2												
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	421		421												
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	302	63	224	15											
<del>40603153</del>	<del>POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80</del>	<del>TON</del>	<del>15,211</del>	<del>14,850</del>		<del>361</del>											
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	178			178											
<del>40603140</del>	<del>POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80</del>	<del>TON</del>	<del>15,211</del>	<del>14,850</del>		<del>361</del>											
40701941	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13"	SQ YD	24,497		24,497												
<del>40701961</del>	<del>HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"</del>	<del>SQ YD</del>	<del>136,815</del>	<del>132,623</del>		<del>3,292</del>											
42001300	PROTECTIVE COAT	SQ YD	16,589	12,275	4,190	124											
<del>X0327145</del>	<del>POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90, 10"</del>	<del>SQ YD</del>	<del>135,815</del>	<del>132,589</del>		<del>3,226</del>											
<del>40702700</del>	<del>FURNISH PROFILOGRAPH</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>													
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	72,919	52,901	19,017	1,001											
Z0007430	TEMPORARY SIDEWALK	SQ FT	1,037	1,037													
42400800	DETECTABLE WARNINGS	SQ FT	743	626	117												
44000100	PAVEMENT REMOVAL	SQ YD	110,655	87,770	20,966	1,919											
X4401190	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,442			1,442											
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,574	1,349	125	100											
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	8,410	3,763	4,311	336											
44000600	SIDEWALK REMOVAL	SQ FT	33,910	26,053	6,521	1,336											
44003100	MEDIAN REMOVAL	SQ FT	24,386	17,384	7,002												
44004000	PAVED DITCH REMOVAL	FOOT	143	143													
44004250	PAVED SHOULDER REMOVAL	SQ YD	18,228	15,909	1,615	704											
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	192	171		21											
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2758	2758													
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,697		988	709											
48203053	HOT-MIX ASPHALT SHOULDERS, 14"	SQ YD	30,658	30,658													

• SPECIALTY ITEMS  
 ◆◆◆ NON PARTICIPATING ITEM

FILE NAME =	DESIGNED - JMM	REVISED -
...General\0162419-002.dgn	DRAWN - TMB	REVISED -
USER NAME = BENESCH	CHECKED - RMT	REVISED -
PLOT DATE = 12/3/2010	DATE - 12/6/10	REVISED -

**benesch**

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: N.T.S. SHEET NO. 2 OF 12 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(57 & 58)WRS-2	DUPAGE	681	6
CONTRACT NO. 62419			[ILLINOIS] FED. AID PROJECT	

Rev. 1-11-11