

SUMMARY OF QUANTITIES				100% STATE						90% STATE 5% WHEATON 5% DUPAGE	93.3% STATE 6.7% WHEATON	93.3% STATE 6.7% WHEATON	100% WHEATON (50% WHEATON 50% WARRENVILLE FOR HERRICK ONLY)	90% STATE 10% DUPAGE	80% STATE 20% DUPAGE	100% STATE	
				ROADWAY FAP 365	ROADWAY NAPERVILLE RD HERRICK RD	ROADWAY CROSS RDS.	IL 56	TRAFFIC SIGNAL INTERCONNECT								SIGNING	LANDSCAPING
CODE	DESCRIPTION	UNIT	TOTAL QUANTITY	0003	0003	0004	0040	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100	100													
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	14,833					11,377		620	610	551		1,209		466	
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	313							36	10	94		173			
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	321							140	14	36		76		55	
81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	27													27	
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	237							20	20	157		20		20	
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	2,590					1,357		254	235	123		406		215	
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	2,805							560	438	260		1,142		405	
81400100	HANDHOLE	EACH	24					12		1		1		5		5	
81400200	HEAVY-DUTY HANDHOLE	EACH	53					28		7	8	4		6			
81400300	DOUBLE HANDHOLE	EACH	9							2	1	1		4		1	
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	15,723					11,377		638	741	911		1,489		567	
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	2													2	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1					1									
85700205	FULL ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	5							1	1	1		1		1	
86000105	MASTER CONTROLLER (SPECIAL)	EACH	1					1									
86400100	TRANSCEIVER - FIBER OPTIC	EACH	5							1	1	1		1		1	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	6,738							2,285	187	229		2,467		1,570	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	8,062							2,083	200	565		3,099		2,115	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	10,256							997	1,067	1,958		5,021		1,213	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	10,318							3,636	2,385	571		2,286		1,440	
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	20,681							4,069	2,740	2,485		10,583		804	
87301615	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 16 6 PAIR	FOOT	843													843	
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	504							130	80	65		79		150	
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	4							1				3			
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1									1					
87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	1								1						
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	5							2				3			
87601100	PEDESTRIAN PUSH-BUTTON POST, GALVANIZED STEEL, TYPE I	EACH	1							1							
87700120	STEEL MAST ARM ASSEMBLY AND POLE, 16 FT.	EACH	1													1	
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1									1					
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1											1			
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1							1							
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	2								1			1			
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2									1		1			

* SPECIALTY ITEMS
 ** NON-PARTICIPATING ITEM

FILE NAME =	DESIGNED - JMM	REVISED -
...\\genet\1\0162419-007.dgn	DRAWN - TMB	REVISED -
USER NAME = BENESCH	CHECKED - RMT	REVISED -
PLOT DATE = 12/3/2010	DATE - 12/6/10	REVISED -

benesch

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
F.A.P. RTE. 365	SECTION (57 & 58) WRS-2	COUNTY DUPAGE	TOTAL SHEETS 681
SCALE: N.T.S.		SHEET NO. 7 OF 12 SHEETS	SHEET NO. 11
CONTRACT NO. 62419		ILLINOIS FED. AID PROJECT	

Rev. 1-7-11