

NAPERVILLE WM RELOCATION

SUMMARY OF QUANTITIES				100% STATE								90% STATE 5% WHEATON 5% DUPAGE	93.3% STATE 6.7% WHEATON	93.3% STATE 6.7% WHEATON	100% WHEATON (50% WHEATON 50% WARRENVILLE FOR HERRICK ONLY)	90% STATE 10% DUPAGE	80% STATE 20% DUPAGE	100% STATE	
				ROADWAY FAP 365	ROADWAY NAPERVILLE RD HERRICK RD	ROADWAY CROSS RDS.	IL 56	TRAFFIC SIGNAL INTERCONNECT										SIGNING	LANDSCAPING
CODE	DESCRIPTION	UNIT	TOTAL QUANTITY	0003	0003	0003	0004	0040	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021
X0327001	PERMANENT DITCH CHECK WITH 12" PIPE	EACH	5	5															
50105220	PIPE CULVERT REMOVAL	FOOT	96	96															
Z0062456	TEMPORARY PAVEMENT	SQ YD	8,289	8,289															
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	5	5															
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	15	15															
X4023000	TEMPORARY ACCESS (ROAD)	EACH	11	11															
X5610712	WATER MAIN REMOVAL, 12"	FOOT	6,900																
X5610716	WATER MAIN REMOVAL, 16"	FOOT	480																
X7011005	TRAFFIC CONTROL & PROTECTION FOR TEMPORARY DETOUR	L SUM	±	±															
X7030030	REFLECTIVE WET TEMPORARY TAPE TYPE III, 4 INCH	FOOT	228,342	228,342															
X7030040	REFLECTIVE WET TEMPORARY TAPE TYPE III, 6 INCH	FOOT	27,481	27,481															
X7030050	REFLECTIVE WET TEMPORARY TAPE TYPE III, 12 INCH	FOOT	8,602	8,602															
X7030055	REFLECTIVE WET TEMPORARY TAPE TYPE III, 24 INCH	FOOT	1,640	1,640															
X7030025	REFLECTIVE WET TEMPORARY TAPE TYPE III, LETTERS AND SYMBOLS	SQ FT	5,922	5,922															
X7810300	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	179	11	168														
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	5								1	1	1			1	1		
X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	5								1	1	1			1	1		
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	15,672						15,672										
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	3,763								660	519	796			1,070	718		
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	3,044												3,044				
Z0001056	AGGREGATE SUBGRADE 16"	SQ YD	30,025		30,025														
XX000882	WOODEN FENCE	FOOT	500	500															
Z0033050	COAXIAL CABLE IN CONDUIT	FOOT	843															843	
XX004096	REMOVE AND RE-INSTALL CONCRETE FLARED END SECTIONS	EACH	3	3															
XX006722	TEMPORARY AGGREGATE BERM-COURSE AGGREGATE	TON	450	450															
XX006723	TEMPORARY AGGREGATE BERM - RIPRAP	TON	986	986															
XX006821	CONCRETE TRUCK WASHOUT	L SUM	1	1															
XX008001	AGGREGATE PATH, 8"	SQ YD	1,607	1,607															
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	161,533	156,984			4,549												
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1															
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	3	3															
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	3	3															
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	3	3															
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	3	3															
Z0064800	SELECTIVE CLEARING	UNIT	25	25															

5,900

1000
480

IL 54 WATER RELOCATION - 0043

Rev. 1-7-11

FILE NAME =	DESIGNED - JMM	REVISED -
...General\0162419-soq-011.dgn	DRAWN - TMB	REVISED -
USER NAME = BENESCH	CHECKED - RMT	REVISED -
PLOT DATE = 12/3/2010	DATE - 12/6/10	REVISED -

benesch

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 11 OF 12 SHEETS STA. TO STA.

F.A.P. RTE. 365	SECTION (57 & 58)WRS-2	COUNTY DUPAGE	TOTAL SHEETS 681	SHEET NO. 15
CONTRACT NO. 62419			ILLINOIS FED. AID PROJECT	