

TEMPORARY ACCESS SCHEDULE

Station	Location	X4021000	X4022000	X4023000
		TEMPORARY ACCESS (PRIVATE ENTRANCE) (EACH)	TEMPORARY ACCESS (COMMERCIAL ENTRANCE) (EACH)	TEMPORARY ACCESS (ROAD) (EACH)
261+29.85	Private Driveway	1		
264+75	Private Entrance	1		
264+87	Private Driveway	1		
265+19.56	Private Entrance	1		
809+30	Private Entrance	1		
288+44.93	Commercial Entrance		1	
321+80.52	Arrowhead Golf Entrance		1	
344+37.14	Golf Entrance		1	
391+23.85	Shopping Centre Entrance		1	
393+71.90	Shopping Centre Entrance		1	
408+72.11	Danada SQ E		1	
410+98.21	Shopping Centre Entrance		1	
11037+60	Shopping Centre Entrance		1	
11036+51	Brahms Circle		1	
11034+72	Shopping Centre Entrance		1	
11034+68	Danada SQ E		1	
11032+08	Shopping Centre Entrance		1	
11032+01	Shopping Centre Entrance		1	
11028+68	Shopping Centre Entrance		1	
818+46	Commercial Entrance		1	
267+22.24	Madison St			1
290+38.56	Lakeview Dr			1
297+56.55	Forest Preserve Entrance			1
303+78.11	Legends Dr			1
321+74.39	Arrowhead Dr			1
322+10.92	Arrowhead Dr			1
325+82.40	Cree Ln			1
329+21.04	Wendelin Ct			1
344+37.14	Orchard Rd			1
370+78.07	Cromwell Dr			1
388+04.02	W Loop Rd			1
		5	15	11

TEMPORARY PAVEMENT (VARIABLE DEPTH) SCHEDULE

Location	Station		Offset	RT/LT	Stage	X0325509
	From	To				TEMPORARY PAVEMENT (VARIABLE DEPTH)
IL-56	399+82	400+16	38.00'	RT	Stage 1	75.88
IL-56	400+02	400+77	39.00'	LT	Stage 1	85.89
IL-56	400+79	401+32	27.00'	RT	Stage 1	56.02
IL-56	412+00	415+78	11.5'	RT	Stage 1	129.30
Herrick Rd	814+22	814+66	24'	RT	Stage 1-1	42.80
Herrick Rd	814+20	814+53	18'	LT	Stage 1-2	53.93
IL-56	266+98	267+63	2.00'	LT	Stage 2	104.26
IL-56	290+06	290+80	15.00'	RT	Stage 2	179.87
IL-56	303+38	304+28	29.00'	LT	Stage 2	292.29
IL-56	321+33	322+40	9.00'	LT	Stage 2	116.36
IL-56	325+37	326+13	22.50'	LT	Stage 2	207.41
IL-56	328+70	329+47	48.50'	LT	Stage 2	416.87
IL-56	343+81	344+66	9.50'	LT	Stage 2	90.92
IL-56	370+14	371+12	9.00'	LT	Stage 2	95.91
IL-56	387+66	388+59	14.50'	RT	Stage 2	150.21
IL-56	390+79	391+69	12.00'	RT	Stage 2-1	30.92
IL-56	393+33	394+11	11.00'	RT	Stage 2-1	42.99
IL-56	400+18	400+71	59.00'	RT	Stage 2-1	51.35
IL-56	400+60	401+01	5.00'	LT	Stage 2-1	51.11
IL-56	408+31	409+11	13.00'	RT	Stage 2-1	17.21
IL-56	410+49	412+00	14.00'	RT	Stage 2-1	138.28
TOTAL						2430

REMOVAL SCHEDULE

LOCATION	ROAD	Station From	Station To	44000100	44000200	44000500	44000600	44004250	44003100
				PAVEMENT REMOVAL (SQ YD)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	SIDEWALK REMOVAL (SQ FT)	PAVED SHOULDER REMOVAL (SQ YD)	MEDIAN REMOVAL (SQ FT)
IL56		255+00.00	258+00.00	821				642	
IL56		258+00.00	273+00.00	4822	639			2211	
IL56		273+00.00	288+00.00	7832		317	1410	1234	
IL56		288+00.00	303+00.00	6019	434		4741	1325	
IL56		303+00.00	318+00.00	6060		282	7329	1228	
IL56		318+00.00	333+00.00	7031	84	785	5766	1022	761
IL56		333+00.00	348+00.00	7188			300	1509	
IL56		348+00.00	363+00.00	5487				1330	
IL56		363+00.00	378+00.00	8911	98	411	1362	1287	
IL56		378+00.00	393+00.00	10449		595		557	155
IL56		393+00.00	408+00.00	18219	94	883	1280	1858	6715
IL56		408+00.00	417+54.62	7129		490		1707	9753
HERRICK		806+65.00	813+47.00	2340	44	618		632	
WIESBROOK		815+71.00	819+71.00			336		267	
ORCHARD		900+80.00	909+43.00	1919	100		1101	704	
NAPERVILLE		11010+75.62	11024+00.00	6770	82	1103	6254	983	
NAPERVILLE		11024+00.00	11038+50.00	11856		2590			7002
WIESBROOK TO LAKEVIEW WM CONSTR							4100		
TOTALS				110655	1575	8410	33910	18228	24386

TEMPORARY PAVEMENT SCHEDULE

Location	Station	Offset	RT/LT	Stage	X0712400	31101200	48101200	
					TEMPORARY PAVEMENT (SQ YD)	SUB-BASE GRANULAR MATERIAL, TYPE B, 4"	AGGREGATE SHOULDER, TYPE B (TON)	
Herrick Rd	803+27	814+49.3	12.50'	LT	Prestage	1667.61	1667.61	113
IL-56	395+72.5	399+83	1.50'	LT	Prestage	338.36	338.36	
IL-56	401+09	401+28	52.00'	LT	Prestage	33.05	33.05	
IL-56	401+15	408+23	7.50'	RT	Prestage	279.37	279.37	
IL-56	409+22	417+55	1.00'	LT	Prestage	1073.57	1073.57	
IL-56	418+42	424+24	3.00'	LT	Prestage	655.59	655.59	
Naperville Rd	11024+80	11029+00	2.00'	RT	Prestage	242.12	242.12	
Naperville Rd	11032+48	11037+45	0	0	Prestage	462.96	462.96	
IL-56	285+49	290+08	15'	RT	Stage 1	640.82	640.82	
IL-56	304+24	308+52	14'	RT	Stage 1	349.65	349.65	
IL-56	322+42	325+75	15'	RT	Stage 1	429.17	429.17	
IL-56	345+20	349+31	12.00'	RT	Stage 1	279.44	279.44	
Naperville Rd	11018+28	11023+12	12.00'	LT	Stage 1	915.3	915.3	
IL-56	388+49	393+33	12.00'	LT	Stage 2-1	752.53	752.53	
IL-56	401+18	401+97	12.00'	RT	Stage 2-1	54.58	54.58	
Naperville Rd	11024+96	11025+37	52.00'	RT	Stage 2-1	56.8	56.8	
Naperville Rd	11018+99	11020+30	4.00'	LT	Stage 2-2	57.83	57.83	
TOTAL						8289	8289	113

TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION	X7030104	X7030106	X7030112	X7030124	X7030120					
	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 4 INCH	WET TEMPORARY PAVEMENT MARKING TAPE TYPE III, 6 INCH	WET TEMPORARY PAVEMENT MARKING TAPE TYPE III, 12 INCH	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 24 INCH	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, LETTERS AND SYMBOLS					
	FOOT	FOOT	FOOT	FOOT	SQ FT					
PRESTAGE	10996	2242	0	0	473					
STAGE 1	61616	3463	2966	257	762					
STAGE 1-1 (HERRICK)	5971	164	261	45	72.6					
STAGE 1-2 (HERRICK)	4734	145	166	20	72.6					
STAGE 2	74783	5549	2935	362	1383					
STAGE 2-1 (NAPERVILLE)	17854	3429	1045	182	508.2					
STAGE 2-2 (NAPERVILLE)	12822	1486	707	178	436					
STAGE 2-3 (NAPERVILLE)	6271	1754	0	107	726					
STAGE 2-4 (NAPERVILLE)	14810	5512	522	237	762					
STAGE 3	18485	3737	0	252	726					
TOTAL						228342	27481	8602	1640	5922

RELOCATE TEMPORARY CONCRETE BARRIER
70400200
FOOT

Stage 2-1	From Sta.	To Sta.	Side	Length
Butterfield Rd	279+40	282+30	RT	290
Butterfield Rd	347+40	350+35	RT	295
Butterfield Rd	371+80	374+40	RT	260
TOTAL				845

TEMPORARY SIDEWALK SCHEDULE
42400610

LOCATION			42400610
ROAD	From	To	TEMPORARY SIDEWALK (SQ FT)
IL56	283+42.00	284+39.00	1,036.08
TOTAL			1,037

TEMPORARY CONCRETE BARRIER SCHEDULE
70400100
FOOT

Stage 1-1	From Sta.	To Sta.	Side	Length
Wiesbrook Rd	815+50	820+80	LT	0
Butterfield Rd	277+50	280+70	LT	320
Butterfield Rd	346+12	348+80	LT	268
Butterfield Rd	370+15	373+20	LT	305
TOTAL				893

TEMPORARY INFO SIGNING
X0322256
SQ FT

SIGN NAME	AREA	QTY	TOT AREA
ENTRANCE	6.25	19	118.75
DRIVEWAY ENTRANCE	6.25	8	50
		27	169

DETECTABLE WARNINGS SCHEDULE

LOCATION	42400800	
LOCATION	DETECTABLE WARNINGS (SQ FT)	
IL-56/Herrick	173	
IL-56/Legends	24	
IL-56/Arrowhead	46	
IL-56/Cree	28	
IL-56/Wendelin	30	
IL-56/Orchard	22	
IL-56/Cromwell	40	
IL-56/Naperville	203	
Entrance Sta 408+75	23	
Entrance Sta 411+00	27	
Entrance Sta 418+00	10	
Naperville/Danada	41	
Entrance Sta 11034+50	50	
Entrance Sta 11037+50	26	
TOTAL		743

FILE NAME =	DESIGNED - JMM	REVISED - ADDENDUM 1/1/10/11
...\\Genera\1\162419-sch-094.dgn	DRAWN - TMB	REVISED -
USER NAME = t51ank	CHECKED - RMT	REVISED -
PLOT DATE = 1/10/2011	DATE - 12/6/10	REVISED -

benesch

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 3 OF 11 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(57 & 58)WRS-2	DUPAGE	681	30
ILLINOIS FED. AID PROJECT				CONTRACT NO. 62419