

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING	NON-PARTICIPATING 100% VILLAGE OF TINLEY PARK
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE							
					004	004	021	031	021	021	042	043
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	33	33							
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	42	42							
	20101100	TREE TRUNK PROTECTION	EACH	7	7							
	20200100	EARTH EXCAVATION	CU YD	3823	3823							
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	100							
	20800150	TRENCH BACKFILL	CU YD	509	59							450
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4840	4840							
*	25000210	SEEDING, CLASS 2A	ACRE	1	1							
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90							
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90							
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90							
*	25100630	EROSION CONTROL BLANKET	SQ YD	4840	4840							
	28000400	PERIMETER EROSION BARRIER	FOOT	1203	1203							
	28000510	INLET FILTERS	EACH	9	9							
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	596	596							
	31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	223	223							
	35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	223	223							
	35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	317	317							
	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	81	81							
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	808	808							
	40600300	AGGREGATE (PRIME COAT)	TON	12	12							
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	10	10							
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1							
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	46	46							
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	23	23							
	40701846	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/4"	SQ YD	5223	5223							
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	5356	5356							
	42400800	DETECTABLE WARNINGS	SQ FT	128	128							
	44000100	PAVEMENT REMOVAL	SQ YD	4208	4208							
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	719	719							
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2872	2872							
	44000600	SIDEWALK REMOVAL	SQ FT	3474	3474							
	44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	5	5							
	550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	18	18							
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	84	84							
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	280	280							
	55100500	STORM SEWER REMOVAL 12"	FOOT	157	157							
*	56103000	DUCTILE IRON WATER MAIN 6"	FOOT	85								85
*	56103100	DUCTILE IRON WATER MAIN 8"	FOOT	1025								1025
*	56103200	DUCTILE IRON WATER MAIN 10"	FOOT	20								20
*	56108800	TAPPING VALVES AND SLEEVES 6"	EACH	3								3
*	56108900	TAPPING VALVES AND SLEEVES 8"	EACH	2								2
*	56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	60								60
*	56300300	ADJUSTING WATER SERVICE LINES	FOOT	60								60
*	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	3								3
*	56500700	DOMESTIC WATER SERVICE BOXES TO BE REMOVED	EACH	2								2
*	56500800	DOMESTIC WATER SERVICE BOXES	EACH	2								2
	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1							
	60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	2	2							

* - INDICATES SPECIALTY ITEMS

FILE NAME = 06508-QUAN-01 - P01

USER NAME =	DESIGNED -- WPD	REVISED --
	CHECKED -- WPD	REVISED --
PLOT SCALE = 1=1"	DRAWN -- AG	REVISED --
PLOT DATE = 10-14-10	CHECKED -- AG	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

175TH STREET AT HARLEM AVENUE
INTERSECTION IMPROVEMENTS
SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	08-00104-00-CH	COOK	80	4
CONTRACT NO. 63453				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-HSIP-8003 (851)				

SCALE: NA SHEET NO. 4 OF 80 SHEETS STA. TO STA.