

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
					80% FEDERAL 20% STATE		100% LOCAL
					ROADWAY 0004 RURAL	BRIDGE 0011 RURAL	ROADWAY 0004 RURAL
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	72	72		
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	204	204		
	20101000	TEMPORARY FENCE	FOOT	30	30		
	20200100	EARTH EXCAVATION	CU YD	410	410		
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,460	2,460		
	20400800	FURNISHED EXCAVATION	CU YD	1,040	1,040		
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	2,357	2,357		
	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	365	365		
S	25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25		
S	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	248	248		
S	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	248	248		
S	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	248	248		
S	25100630	EROSION CONTROL BLANKET	SQ YD	7,260	7,260		
S	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	303	303		
	28000305	TEMPORARY DITCH CHECKS	FOOT	50	50		
	28000400	PERIMETER EROSION BARRIER	FOOT	2,220	2,220		
	28000500	INLET AND PIPE PROTECTION	EACH	3	3		
	28100105	STONE RIPRAP, CLASS A3	SQ YD	21	21		
	28100107	STONE RIPRAP, CLASS A4	SQ YD	517		517	
	28200200	FILTER FABRIC	SQ YD	538	21	517	
	31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	55	47		8
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3	3		
	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	105			105
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	153	153		
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	872	840		32
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	418	187		231
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	46	46		
	44000100	PAVEMENT REMOVAL	SQ YD	1,798	1,798		
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	730	730		
	48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	110	110		
	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	24			24
	48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	560	560		
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
	50104000	BRIDGE RAIL REMOVAL	FOOT	186		186	

FILE NAME = P:\CIBEL\WEST Projects\2009\09-0802\Bolon\Plan\Civil\Drawings\500_01.dwg



USER NAME = #USER#	DESIGNED -	REVISED -
PLOT SCALE =	DRAWN -	REVISED -
PLOT DATE = 10/21/2010	CHECKED -	REVISED -
	DATE - 10/22/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 3	OF 73 SHEETS	STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2332	03-14185-02-BR	KANE	73	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
CONTRACT NO. 63521				