

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0021	0021	0021	0031	0043
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (LIGHTING)	SAFETY (SIDEWALKS)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	NON-PARTICIPATING
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	27	27						
20101000	TEMPORARY FENCE	FOOT	440	440						
20101100	TREE TRUNK PROTECTION	EACH	11	11						
20101200	TREE ROOT PRUNING	EACH	11	11						
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	6	6						
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	5						
20200100	EARTH EXCAVATION	CU YD	2294	1616	678					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1040	1040						
20400800	FURNISHED EXCAVATION	CU YD	1303	1228	75					
20800150	TRENCH BACKFILL	CU YD	2281	340	1					1940
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3237						3237	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	40						40	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	40						40	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	40						40	
25200100	SODDING	SQ YD	3237						3237	
25200200	SUPPLEMENTAL WATERING	UNIT	49						49	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	67	63	4					
28000305	TEMPORARY DITCH CHECKS	FOOT	72		72					
28000510	INLET FILTERS	EACH	61	54	7					
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	457		457					
31101180	SUBBASE GRANULAR MATERIAL, TYPE B 2"	SQ YD	1654					1654		
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	13574	12284	1290					
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	1584	1584						
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	330		330					
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2650		2650					
40600300	AGGREGATE (PRIME COAT)	TON	26		26					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40		40					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1526		1526					
40600895	CONSTRUCTING TEST STRIP	EACH	1		1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	205		205					
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	215		215					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1298		1298					
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	30	30						
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	8542	8542						
42001300	PROTECTIVE COAT	SQ YD	16043	13763	626			1654		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	14887					14887		
42400800	DETECTABLE WARNINGS	SQ FT	109					109		
44000100	PAVEMENT REMOVAL	SQ YD	13030	13014	16					

● SPECIALTY ITEM

FILE NAME = ...load\sheet\2362\_Sum\_Quant.dgn

USER NAME = big	DESIGNED - BLG	REVISED -
PLOT SCALE = 50.0000' / IN.	DRAWN - BLG	REVISED -
PLOT DATE = 11/3/2010	CHECKED - DJK	REVISED -
	DATE - 10-22-10	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET NO. 1 OF 7 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	09-00056-00-CH	COOK	111	4
CONTRACT NO. 63527				
FED. ROAD DIST. NO. 1   ILLINOIS FED. AID PROJECT M-9003(659)				