

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0021	0021	0021	0031	0043
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (LIGHTING)	SAFETY (SIDEWALKS)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	NON-PARTICIPATING
88700200	LIGHT DETECTOR	EACH	4							4
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1							1
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8			8				
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1				
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	4737			3389	1348			
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1				
89502380	REMOVE EXISTING HANDHOLE	EACH	12			12				
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	10			10				
A2001228	TREE, ACER RUBRUM RED SUNSET (RED SUNSET RED MAPLE), 4" CALIPER, BALLED AND BURLAPPED	EACH	1						1	
A2008132	TREE, TILIA CORDATA GREENSPIRE (GREENSPIRE LITTLE LEAF LINDEN), 4" CALIPER, BALLED AND BURLAPPED	EACH	2						2	
Z0012450	CONCRETE STEPS	CU YD	2	2						
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	6		6					
Z0018911	DRILL AND GROUT #6 TIE BARS	EACH	1069		1069					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	415	364	51					
Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	9				9			
Z0033044	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1			1				
Z0033060	PERFORMED DETECTOR LOOP	FOOT	845			845				
Z0033090	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5669			5669				
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1040	1040						
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	357	357						
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	62	62						
Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	103	103						
Z0056614	STORM SEWER (WATER MAIN REQUIREMENTS) 21 INCH	FOOT	68	68						
Z0056624	STORM SEWER (WATER MAIN REQUIREMENTS) 42 INCH	FOOT	40	40						
Z0056800	SANITARY SEWER 6"	FOOT	27							27
Z0057100	SANITARY SEWER 12"	FOOT	202							202
Z0058200	SANITARY SEWER, TYPE 1 6"	FOOT	109							109
Z0058400	SANITARY SEWER, TYPE 1 10"	FOOT	42							42
Z0062456	TEMPORARY PAVEMENT	SQ YD	2075	2075						
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1			1				
Z0076600	TRAINEES	HOUR	1500	1500						
X0300020	WATER SERVICE CONNECTION	EACH	4							4
X0323134	REMOVE EXISTING HELIX FOUNDATION	EACH	2				2			
X0323651	REMOVE AND REINSTALL EXISTING LIGHTING UNIT	EACH	2				2			
X0323857	EXISTING LIGHT POLE FOUNDATION ADJUSTMENT	EACH	5				5			
X0325207	TELEVISION INSPECTION OF SEWER	FOOT	2942		2942					
X0487700	SANITARY SEWER REMOVAL 10"	FOOT	42							42
X0487800	SANITARY SEWER REMOVAL 12"	FOOT	202							202

△ 0042
● SPECIALTY ITEM

FILE NAME = ...\\eod\sheet\2362_Sum_Quant.dgn
PLOT SCALE = 50.0000' / IN.
PLOT DATE = 11/3/2010

DESIGNED - BLG
DRAWN - BLG
CHECKED - DJK
DATE - 10-22-10
REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET NO. 6 OF 7 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	09-00056-00-CH	COOK	111	9
CONTRACT NO. 63527				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003659				