

IL 84 SCHEDULE OF QUANTITIES

25000750 - MOWING

LOCATION	ACRE	REMARK
TRIBUTARY TO APPLE RIVER		
STA. 161+77 - 162+53	RT 0.02	
STA. 162+57 - 165+11	RT 0.19	
STA. 162+00 - 164+71	LT 0.19	
STA. 165+89 - 169+50	LT 0.20	
STA. 166+29 - 169+50	RT 0.13	
DUKE CREEK		
STA. 333+50 - 334+26	RT 0.03	
STA. 334+35 - 336+17	RT 0.13	
STA. 334+25 - 336+17	LT 0.07	
STA. 336+68 - 339+05	LT 0.12	
STA. 336+68 - 338+52	RT 0.11	
STA. 338+71 - 339+05	RT 0.01	
TOTAL	1.19	

25100630 - EROSION CONTROL BLANKET

LOCATION	SQ_YD	REMARK
TRIBUTARY TO APPLE RIVER		
STA. 161+77 - 162+53	RT 73.5	
STA. 162+57 - 165+11	RT 898.8	
STA. 162+00 - 164+71	LT 898.6	
STA. 165+89 - 169+50	LT 985.8	
STA. 166+29 - 169+50	RT 640.0	
DUKE CREEK		
STA. 333+50 - 334+26	RT 133.1	
STA. 334+35 - 336+17	RT 614.4	
STA. 334+25 - 336+17	LT 356.4	
STA. 336+68 - 339+05	LT 575.4	
STA. 336+68 - 338+52	RT 554.3	
STA. 338+71 - 339+05	RT 46.8	
TOTAL	5777	

28000250 - TEMPORARY EROSION CONTROL SEEDING

LOCATION	POUND	REMARK
TRIBUTARY TO APPLE RIVER		
STA. 161+77 - 162+53	RT 9.1	
STA. 162+57 - 165+11	RT 111.4	
STA. 162+00 - 164+71	LT 111.4	
STA. 165+89 - 169+50	LT 122.2	
STA. 166+29 - 169+50	RT 79.3	
DUKE CREEK		
STA. 333+50 - 334+26	RT 16.5	
STA. 334+35 - 336+17	RT 76.2	
STA. 334+25 - 336+17	LT 44.2	
STA. 336+68 - 339+05	LT 71.3	
STA. 336+68 - 338+51	RT 68.7	
STA. 338+73 - 339+05	RT 5.8	
TOTAL	716	

28000400 - PERIMETER EROSION BARRIER

LOCATION	EQOI	REMARK
TRIBUTARY TO APPLE RIVER		
STA. 161+77 - 162+53	RT 84.3	
STA. 162+50 - 164+50	LT 179.3	
STA. 162+66 - 164+00	RT 135.6	
STA. 166+50 - 168+00	RT 125.3	
STA. 167+19 - 168+50	RT 133.0	
DUKE CREEK		
STA. 333+50 - 334+26	RT 82.6	
STA. 334+38 - 336+17	RT 185.8	
STA. 335+00 - 336+17	LT 119.7	
STA. 336+68 - 338+50	LT 185.8	
STA. 336+68 - 338+52	RT 190.0	
TOTAL	1422	

28000315 - AGGREGATE DITCH CHECK

LOCATION	ION	REMARK
TRIBUTARY TO APPLE RIVER		
STA. 162+76	RT 0.5	
STA. 163+32	RT 0.5	
STA. 163+98	RT 0.5	
STA. 164+47	RT 0.5	
STA. 167+16	LT 0.5	
STA. 167+66	LT 0.5	
STA. 168+16	LT 0.5	
STA. 168+66	LT 0.5	
DUKE CREEK		
STA. 333+95	RT 0.5	
STA. 334+56	RT 0.5	
STA. 335+02	LT 0.5	
STA. 335+05	RT 0.5	
STA. 335+48	LT 0.5	
STA. 335+56	RT 0.5	
STA. 335+88	LT 0.5	
STA. 336+01	RT 0.5	
STA. 337+01	LT 0.5	
STA. 337+02	RT 0.5	
STA. 337+56	RT 0.5	
STA. 337+57	LT 0.5	
STA. 338+04	RT 0.5	
STA. 338+16	LT 0.5	
TOTAL	11	

28000500 - INLET AND PIPE PROTECTION

LOCATION	EACH	REMARK
DUKE CREEK		
STA. 334+10	RT 1	
STA. 338+35	RT 1	
TOTAL	2	