

**SUMMARY OF QUANTITIES**

0011

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80% FED / 20% STATE
54213447	END SECTIONS 12"	EACH	2	2
54213453	END SECTIONS 18"	EACH	6	6
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	141	141
60100945	PIPE DRAINS 12"	FOOT	27	27
60900515	CONCRETE THRUST BLOCKS	EACH	2	2
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	2	2
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	250.0	250.0
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	5	5
63200310	GUARDRAIL REMOVAL	FOOT	1,569	1,569
63500105	DELINEATORS	EACH	8	8
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	5	5
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	353	353
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	4,920	4,920
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	25	25
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,190	1,190
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,100	1,100

\* SPECIALTY ITEMS  
;) NON PARTICIPATING 100% STATE

0011

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80% FED / 20% STATE
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,075	1,075
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4,992	4,992
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	20	20
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	6	6
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6
78300100	PAVEMENT MARKING REMOVAL	SQ FT	475	475
Z0001000	AGGREGATE FOR TEMPORARY CROSSING	TON	40	40
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22	22
Z0004552	APPROACH SLAB REMOVAL	SQ YD	156	156
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	168	168
Z0062456	TEMPORARY PAVEMENT	SQ YD	489	489
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	2,020	2,020
* A2001714	TREE, ACER SACCHARUM (SUGAR MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	6	6
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	11	11
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	198	198
X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	489	489
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1	1
X0327105	USGS GAGE EQUIPMENT PAD	EACH	1	1
X0327106	USGS GAGE EQUIPMENT CABINET, SPECIAL	EACH	1	1

\* SPECIALTY ITEMS  
;) NON PARTICIPATING 100% STATE

FILE NAME : G:\ENR\08-0798-14A D2 Bridge Phase 2\1182\CAD\Civil\Sheet\0284020-11-500\_2.dgn



USER NAME = #USER#	DESIGNED - JNH	REVISED -
PLOT SCALE = #SCALE#	DRAWN - JNH	REVISED -
PLOT DATE = 10/28/2010	CHECKED - KMB	REVISED -
	DATE - 08/27/2010	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
IL 82 OVER GREEN RIVER**

F.A.P. RTE. 638	SECTION 129BR-4	COUNTY HENRY	TOTAL SHEETS 93	SHEET NO. 5
CONTRACT NO. 64D25				
[ILLINOIS] FED. AID PROJECT				

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.