

**SCHEDULE OF QUANTITIES**

**35101400 AGGREGATE BASE COURSE, TYPE B**

TON	LOCATION
	<b>IL 82</b>
35	Sta 1260+20.8 FE Field Entrance RT
55	Sta 1261+13.3 FE Field Entrance LT
63	Sta 1267+42.55 FE Field Entrance LT
<b>153</b>	<b>TOTAL</b>

**40600400 MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS**

TON	LOCATION
	<b>IL 82</b>
5	AS NEEDED & DIRECTED BY THE RESIDENT ENGINEER
<b>5</b>	<b>TOTAL</b>

**44000100 PAVEMENT REMOVAL**

SQ YD	LOCATION
	<b>IL 82</b>
41	Sta 1263+66.63 - 1263+81.39
130	Sta 1265+96.47 - 1266+43.13
<b>171</b>	<b>TOTAL</b>

**48101200 AGGREGATE SHOULDERS, TYPE B**

TON	LOCATION
	<b>IL 82</b>
34	Sta 1259+50 - 1260+84.29 LT
16	Sta 1261+42.29 - 1262+07 LT
49	Sta 1269+31.97 - 1271+25 LT
<b>99</b>	<b>TOTAL</b>

**50100100 REMOVAL OF EXISTING STRUCTURES**

EACH	LOCATION
	<b>IL 82</b>
1	Sta 1264+90.39 EXISTING BRIDGE OVER GREEN RIVER
<b>1</b>	<b>TOTAL</b>

**50200100 STRUCTURE EXCAVATION**

CU YD	LOCATION
	<b>IL 82</b>
392	Sta 1265+04.88
<b>392</b>	<b>TOTAL</b>

**50200450 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES**

CU YD	LOCATION
	<b>IL 82</b>
18	Sta 1263+73.53 - 1263+83.88
19	Sta 1266+25.89 - 1266+36.24
<b>37</b>	<b>TOTAL</b>

**50300100 FLOOR DRAINS**

EACH	LOCATION
	<b>IL 82</b>
24	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>24</b>	<b>TOTAL</b>

**50300225 CONCRETE STRUCTURES**

CU YD	LOCATION
	<b>IL 82</b>
273.3	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>273.3</b>	<b>TOTAL</b>

**50300255 CONCRETE SUPERSTRUCTURE**

CU YD	LOCATION
	<b>IL 82</b>
446	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>446</b>	<b>TOTAL</b>

**50300260 BRIDGE DECK GROOVING**

SQ YD	LOCATION
	<b>IL 82</b>
1,086	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>1,086</b>	<b>TOTAL</b>

**50300280 CONCRETE ENCASEMENT**

CU YD	LOCATION
	<b>IL 82</b>
15.4	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>15.4</b>	<b>TOTAL</b>

**50300300 PROTECTIVE COAT**

SQ YD	LOCATION
	<b>IL 82</b>
1,330	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>1,330</b>	<b>TOTAL</b>

**50400905 FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.**

FOOT	LOCATION
	<b>IL 82</b>
1,157.5	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>1,157.5</b>	<b>TOTAL</b>

**50800105 REINFORCEMENT BARS**

POUND	LOCATION
	<b>IL 82</b>
6,470	Sta BOX CULVERT
<b>6,470</b>	<b>TOTAL</b>

**50800205 REINFORCEMENT BARS, EPOXY COATED**

POUND	LOCATION
	<b>IL 82</b>
128,920	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>128,920</b>	<b>TOTAL</b>

**50800515 BAR SPLICERS**

EACH	LOCATION
	<b>IL 82</b>
1,127	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>1,127</b>	<b>TOTAL</b>

**51201800 FURNISHING STEEL PILES HP14X73**

FOOT	LOCATION
	<b>IL 82</b>
1,242	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>1,242</b>	<b>TOTAL</b>

**51202305 DRIVING PILES**

FOOT	LOCATION
	<b>IL 82</b>
1,242	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>1,242</b>	<b>TOTAL</b>

**51203800 TEST PILE STEEL HP14X73**

EACH	LOCATION
	<b>IL 82</b>
4	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>4</b>	<b>TOTAL</b>

**51204650 PILE SHOES**

EACH	LOCATION
	<b>IL 82</b>
28	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
<b>28</b>	<b>TOTAL</b>

**51500100 NAME PLATES**

EACH	LOCATION
	<b>IL 82</b>
1	Sta 1265+04.88 BRIDGE OVER GREEN RIVER
1	Sta 1269+05.61 BOX CULVERT
<b>2</b>	<b>TOTAL</b>

**54002080 EXPANSION BOLTS 3/4 INCH X 18 INCH**

EACH	LOCATION
	<b>IL 82</b>
40	Sta BOX CULVERT
<b>40</b>	<b>TOTAL</b>

**54003000 CONCRETE BOX CULVERTS**

CU YD	LOCATION
	<b>IL 82</b>
47.6	Sta
<b>47.6</b>	<b>TOTAL</b>

**542D0223 PIPE CULVERTS, CLASS D, TYPE 1 18"**

FOOT	LOCATION
	<b>IL 82</b>
46	Sta 1260+20 RT FE
46	Sta 1261+14 LT FE
<b>92</b>	<b>TOTAL</b>

**542D1063 PIPE CULVERTS, CLASS D, TYPE 2 18"**

FOOT	LOCATION
	<b>IL 82</b>
49	Sta 1267+34.0 LT FE
<b>49</b>	<b>TOTAL</b>

FILE NAME = G:\ENR\06-07-09-14A D2 Bridge Phase 2\IL82\CORD\Civil\Sheet\AD26425-INT-002.dgn



USER NAME = #USER#	DESIGNED - AAS	REVISED -
PLOT SCALE = #SCALE#	DRAWN - AAS	REVISED -
PLOT DATE = 10/26/2010	CHECKED - KMB	REVISED -
	DATE - 08/27/2010	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SCHEDULE OF QUANTITIES IL 82 OVER GREEN RIVER</b>	
SCALE:	SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A.P. RTE. 638	SECTION 129BR-4	COUNTY HENRY	TOTAL SHEETS 93	SHEET NO. 7
CONTRACT NO. 64D25				
ILLINOIS FED. AID PROJECT				