

80% FEDERAL
20% STATE

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 0004	STRUCTURE NO. 006-0146 (EX) 006-0182 (PR) 0011
20200100	EARTH EXCAVATION	CU YD	825	825	
20300100	CHANNEL EXCAVATION	CU YD	735	735	
20400800	FURNISHED EXCAVATION	CU YD	530	530	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	72		72
* 25000300	SEEDING, CLASS 3	ACRE	1.25	1.25	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	114	114	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	114	114	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	114	114	
* 25100630	EROSION CONTROL BLANKET	SO YD	5,781	5,781	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	375	375	
28000305	TEMPORARY DITCH CHECKS	FOOT	150	150	
28000400	PERIMETER EROSION BARRIER	FOOT	150	150	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
28100109	STONE RIPRAP, CLASS A5	SO YD	1,340		1,340
28200200	FILTER FABRIC	SO YD	1,340		1,340
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	36	36	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	451	451	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	95	95	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	160	160	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	181	181	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	38	38	

* SPECIALTY ITEM

80% FEDERAL
20% STATE

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 0004	STRUCTURE NO. 006-0146 (EX) 006-0182 (PR) 0011
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	23	23	
44000100	PAVEMENT REMOVAL	SO YD	138	138	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	252	252	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	580	580	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	290	290	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	914	914	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	174		174
50300225	CONCRETE STRUCTURES	CU YD	149.0		149.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	353.3		353.3
50300260	BRIDGE DECK GROOVING	SO YD	546		546
50300280	CONCRETE ENCASEMENT	CU YD	8.6		8.6
50300300	PROTECTIVE COAT	SO YD	703		703
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	81,020		81,020
51200958	FURNISHING METAL SHELL PILES 14"x0.250"	FOOT	1,432		1,432
51202305	DRIVING PILES	FOOT	1,432		1,432
51203200	TEST PILE METAL SHELLS	EACH	2		2
51204650	PILE SHOES	EACH	18		18
51500100	NAME PLATES	EACH	1		1
54213447	END SECTIONS 12"	EACH	2	2	
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	40		40

* SPECIALTY ITEM

FILE NAME =	USER NAME = schwankerg	DESIGNED - JML	REVISED -
ca\pwwork\pwwork\schwankerg\d0114834\0366909-ahs-S00.dgn		DRAWN - JJO	REVISED -
	PLOT SCALE = 1.0000' / IN.	CHECKED - MSW	REVISED -
	PLOT DATE = Oct 21, 2010 - 04:28:43 PM	DATE - 10/08/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE. 1249	SECTION (23 BR/BR)	COUNTY BUREAU	TOTAL SHEETS 39	SHEET NO. 3
CONTRACT NO. 66909			ILLINOIS FED. AID PROJECT	