

CODE NUMBER	ITEM	UNIT	TOTAL	80% FEDERAL 20% STATE	
				ROADWAY 0004	STRUCTURE NO. 006-0104 (EX) 006-0181 (PR) 011
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	10	10	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	16	16	
20101000	TEMPORARY FENCE	FOOT	139	139	
20200100	EARTH EXCAVATION	CU YD	935	935	
20300100	CHANNEL EXCAVATION	CU YD	3,204	3,204	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	116		116
* 25000100	SEEDING, CLASS 1	ACRE	0.25	0.25	
* 25000300	SEEDING, CLASS 3	ACRE	1.25	1.25	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	137	137	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	137	137	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	137	137	
* 25100630	EROSION CONTROL BLANKET	SO YD	5,369	5,369	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SO YD	477	477	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	450	450	
28000305	TEMPORARY DITCH CHECKS	FOOT	105	105	
28000400	PERIMETER EROSION BARRIER	FOOT	554	554	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
28100107	STONE RIPRAP, CLASS A4	SO YD	1,733		1,733
28200200	FILTER FABRIC	SO YD	1,733		1,733
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SO YD	352	352	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	643	643	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	84	84	

\* SPECIALTY ITEM

CODE NUMBER	ITEM	UNIT	TOTAL	80% FEDERAL 20% STATE	
				ROADWAY 0004	STRUCTURE NO. 006-0104 (EX) 006-0181 (PR) 0011
40600990	TEMPORARY RAMP	SO YD	60	60	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	232	232	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	4	4	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	37	37	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	22	22	
44000100	PAVEMENT REMOVAL	SO YD	748	748	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	1,117	1,117	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	868	868	
48203033	HOT-MIX ASPHALT SHOULDERS, 9"	SO YD	761	761	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	209		209
50300225	CONCRETE STRUCTURES	CU YD	101.0		101.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	293.9		293.9
50300260	BRIDGE DECK GROOVING	SO YD	683		683
50300280	CONCRETE ENCASEMENT	CU YD	12.1		12.1
50300300	PROTECTIVE COAT	SO YD	885		885
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	2,160		2,160
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	82,220		82,220
50800515	BAR SPLICERS	EACH	785		785
51201800	FURNISHING STEEL PILES HP14x73	FOOT	645		645

\* SPECIALTY ITEM

FILE NAME =	USER NAME = schwenkerg	DESIGNED - JML	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 698	SECTION (101 BRIBR)	COUNTY BUREAU	TOTAL SHEETS 47	SHEET NO. 3		
or\pwwork\pwwork\schwenkerg\d8114884\066910-eh-t-S00.dgn	PLOT SCALE = 1.0000 / IN.	CHECKED - MSW	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 66910
	PLOT DATE = Oct 21, 2010 04:17:37 PM	DATE - 10/08/10	REVISED -							REVISED: 10/21/10	IDOT	24-8371
FARNSWORTH GROUP, INC.		CONSULTING ENGINEERS - 2709 MCGRAW DRIVE BLOOMINGTON, ILLINOIS 61704 (309) 663-8435 / (309) 663-1571 FAX										