

MAINTENANCE OF TRAFFIC SCHEDULE

LOCATION	TEMP. CONCRETE BARRIER	RELOCATE TEMP. CONCRETE BARRIER	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMP. PAVEMENT MARKING LINE 4"	TEMP. PAVEMENT MARKING LINE 8"	TEMP. PAVEMENT MARKING LINE 24"	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	PAVEMENT MARKING TAPE, TYPE III 4"	PAVEMENT MARKING TAPE, TYPE III 6"	PAVEMENT MARKING TAPE, TYPE III 24"	IMPACT ATTN., TEMP (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTN., REL (FULLY REDIRECTIVE), TEST LEVEL 3
	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	EACH	EACH
STAGE 1	337.5		32848	172	23442	857	86	125	29529	472	26	2	
STAGE 2		337.5											2

BARRIER WALL MARKERS, TYPE B

TEMP. CONC. BARRIER	337.5	FOOT
NO. OF SECTION	27	EACH
BARRIER WALL MARKERS	108	EACH

TERMINAL MARKER - DIRECT APPLIED

STATION	OFFSET	ALIGNMENT	EACH
9+21.14	LT	Cameron	1
12+25.00	LT	Cameron	1
18+82.85	LT	Wheeler	1
18+82.85	RT	Wheeler	1
341+34.71	LT	US24	1
12+10.25	RT	Cameron	1
TOTAL			6

PAVEMENT MARKING REMOVAL

PAY ITEM	LENGTH (FT)	WIDTH (FT)	AREA (SQ FT)
78005100	N/A	N/A	172
78005110	23442	0.33	7736
78005140	857	0.667	571
78005180	86	2	172
TOTAL			8651

END SECTION TO BE REMOVED

STATION	OFFSET	ALIGNMENT	EACH
8+55	RT	Cameron	1
11+11	RT	Cameron	1
11+09	LT	Cameron	1
336+65	RT	US24	1
339+36	RT	US24	1
339+93	LT	US24	1
340+79	LT	US24	1
340+83	RT	US24	1
TOTAL			8

CONSTRUCTION LAYOUT

JOB SITE	1	LSUM
----------	---	------

DRAINAGE STRUCTURE TO BE REMOVED

STATION	OFFSET	ALIGNMENT	EACH
336+13	RT	US24	1
339+00	RT	US24	1
339+05	RT	US24	1
340+81	RT	US24	1
TOTAL			4

IMPACT ATTENUATOR REMOVAL

JOB SITE	8	EACH
----------	---	------

IMPACT ATTENUATORS (FULLY RE-DIRECTIVE, NARROW), TEST LEVEL 3

JOB SITE	8	EACH
----------	---	------

SAW CUTS

STATION	OFFSET	ALIGNMENT	LENGTH (FOOT)
330+38	RT	US24	45
332+00	LT	US24	45
343+50	RT	US24	45
343+72	LT	US24	45
8+25	CL	Cameron	17
11+99	CL	Cameron	58
19+10	CL	Wheeler	25
TOTAL			280

EPOXY PAVEMENT MARKING - LINE 8"

STATION	OFFSET	ALIGNMENT	STATION	OFFSET	ALIGNMENT	LENGTH (FOOT)
332+80	RT	US24	334+80	RT	US24	200
336+31	LT	US24	340+07	LT	US24	377
337+52	RT	US24	339+92	RT	US24	240
340+75	LT	US24	341+15	LT	US24	40
TOTAL						857

EPOXY PAVEMENT MARKING - LINE 24"

STATION	OFFSET	ALIGNMENT	STATION	OFFSET	ALIGNMENT	LENGTH (FOOT)
335+36	LT	US24	335+53	LT	US24	18
335+79	RT	US24	335+98	RT	US24	32
336+16	RT	US24	336+23	RT	US24	17
340+34	LT	US24	340+53	LT	US24	19
TOTAL						86

CONCRETE MEDIAN REMOVAL

STATION	OFFSET	ALIGNMENT	STATION	OFFSET	ALIGNMENT	AREA (SQ FT)
10+46	RT	Cameron	12+00	RT	Cameron	1299
336+02	RT	US24	336+15	RT	US24	91
336+17	RT	US24	336+94	RT	US24	532
338+92	RT	US24	340+30	RT	US24	1056
340+84	RT	US24	342+62	RT	US24	1755
TOTAL						4733

PAVED DITCH REMOVAL

STATION	OFFSET	ALIGNMENT	LENGTH (FOOT)
336+28	RT	US24	10
TOTAL			10

DATE: _____ BY: _____
 SURVEYED: _____ CHECKED: _____
 PLAN: _____ NOTE BOOK: _____
 NO. _____

DATE: _____ BY: _____
 SURVEYED: _____ CHECKED: _____
 PROFILE: _____ NOTE BOOK: _____
 NO. _____