

THERMOPLASTIC PAVEMENT MARKING - LINES

TYPE	STA	LENGTH	LINE, 4" (WHITE)	LINE, 4" (YELLOW)	LINE, 6" (WHITE)	LINE, 12" (WHITE)	LINE, 24" (WHITE)
			FOOT (78000200)	FOOT (78000200)	FOOT (78000400)	FOOT (78000600)	FOOT (78000600)
	0+77.00						
ISLAND	3+72.94	295.94				87	
	999+62.54						
		37.46		37.46			
EQ.STA	1000+00.00						
	0+00.00						
		77.00	154				
	0+77.00						
		295.94	591.88	621.474			
	3+72.94						
	322+51.00						
SKIP DASH		2,247.00		561.75	0		
	344+98.00						
DBL YELLOW		243.00		486	0		
	347+41.00						
RR X-ING		47.00		94	0		
	347+88.00						
DBL YELLOW		243.00		486	0		
	350+31.00						
SKIP DASH		1,422.00		355.5	0		
	364+53.00						
DBL YELLOW		297.00		594	0		
	367+50.00						
	352+74.60				42		
CROSSWALK					42		
	352+80.60						
	352+74.60						
CROSSWALK						78	
	352+80.60						
RR X-ing							
3 bars NB		20 X 3					60.0
3 Bars SB		20 X 3					60.0
5 stop bars		13					65.0
TOTAL			745.88	2,577.25	84	165	185
			3,323.13				

PAINT PAVEMENT MARKING, LINE 4"

(78001110)

TYPE	STATION	LENGTH	4" YELLOW	4" WHITE
	3+72.94			
SKIP DASH	27+64.00	2,391.06	597.77	4,782.12
SB NO PASS	35+25.00	761.00	951.25	1,522.00
SKIP DASH	38+00.00	275.00	68.75	550.00
NB NO PASS	47+00.00	900.00	1,125.00	1,800.00
SB NO PASS	58+00.00	1,100.00	1,375.00	2,200.00
DBL YELLOW	66+60.00	860.00	1,720.00	1,720.00
NB NO PASS	79+00.00	1,240.00	1,550.00	2,480.00
SKIP DASH	82+30.00	330.00	82.50	660.00
SB NO PASS	90+04.00	774.00	967.50	1,548.00
NB NO PASS	100+00.00	996.00	1,245.00	1,992.00
SB NO PASS	229+20.00	12,920.00	16,150.00	25,840.00
SB NO PASS	238+60.00	940.00	1,175.00	1,880.00
DBL YELLOW	241+30.00	270.00	540.00	540.00
NB NO PASS	243+70.00	240.00	300.00	480.00
SKIP DASH	322+51.00	7,881.00	1,970.25	15,762.00
SUB-TOTALS			29,818.02	63,756.12
TOTAL			93,574.0	

SHORT TERM PAVEMENT MARKING

(70300100)

STATION	LENGTH	FOOT	APPLICATIONS	TOTAL
384+00.00				
	* 1,752.00	175.2	3	525.6
366+48.00	** 4,368.00	436.8	2	873.6
322+80.00				
	* 32,280.00	3,228.0	3	9,684.0
0+00.00				
TOTAL		3,840.00		11,083.20

*Three applications for milling, level binder and surface

**TWO applications for milling and surface

WORK ZONE PAVEMENT MARKING REMOVAL

(70301000)

STATION	LENGTH	FOOT	SQ FT	TOTAL
384+00.00				
	1,752.00	175.2	58.4	
366+48.00				
	4,368.00	436.8	145.6	
322+80.00				
	32,280.00	3,228.0	1,076.0	
0+00.00				
TOTAL		3,840.0		1,280.0

FILE NAME =	USER NAME = bucklesJJ	DESIGNED -	REVISED -
ct:\pw\work\pmdot\bucklesJJ\d0155680\0570273-sh-t-schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 10/14/2010	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
PAVEMENT MARKS, PAVEMENT MARKING REMOVAL			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
741	(7S,8,28)RS-3	PIATT	202	12
CONTRACT NO. 70273				
ILLINOIS FED. AID PROJECT				