

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	CONSTRUCTION TYPE CODE:	LOCATION OF WORK:	FUNDING BREAKOUT:			
				80% FED. / 20% STATE	80% FED. / 20% STATE	80% FED. / 20% STATE	80% FED. / 20% STATE
		UNIT	PIATT CO. FAS 1531 MONTICELLO-CISCO RD	PIATT CO. FAS 1531 MONTICELLO-CISCO RD S.N. 074-2007	PIATT CO. FAS 1531 MONTICELLO-CISCO RD S.N. 074-8606	PIATT CO. FAS 1531 MONTICELLO-CISCO RD S.N. 074-2006	
			TOTAL QUANTITY	0011 QUANTITY	0040 QUANTITY	0011 QUANTITY	
20200100	EARTH EXCAVATION	CU YD	639.0	274.0	161.0	204.0	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1,400.0	436.2	244.3	719.5	
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	645.0	210.0	120.0	315.0	
* 25000200	SEEDING, CLASS 2	ACRE	0.8	0.2	0.1	0.5	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	67.5	15.8	8.2	43.5	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	67.5	15.8	8.2	43.5	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	67.5	15.8	8.2	43.5	
* 25100115	MULCH, METHOD 2	ACRE	0.8	0.2	0.1	0.5	
* 25100630	EROSION CONTROL BLANKET	SQ YD	3,096.0	841.0	429.0	1,826.0	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	75.0	17.5	9.1	48.4	
28000305	TEMPORARY DITCH CHECKS	FOOT	128.0	32.0	32.0	64.0	
28000400	PERIMETER EROSION BARRIER	FOOT	1,210.0	310.0	180.0	720.0	
28000500	INLET AND PIPE PROTECTION	EACH	4.0		4.0		
28100107	STONE RIPRAP, CLASS A4	SQ YD	744	329	196	219	
28100201	STONE RIPRAP, CLASS A1	TON	550.0	224.8	125.6	199.6	
28200200	FILTER FABRIC	SQ YD	1,457.0	616.0	357.0	484.0	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	21.0		21.0		
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	460.0	195.7	107.7	156.6	
44201299	DOWEL BARS 1 1/2"	EACH	280.0	100.0	80.0	100.0	
44213100	PAVEMENT FABRIC	SQ YD	460.0	195.7	107.7	156.6	
44213200	SAW CUTS	FOOT	44.0		44.0		
44213208	TIE BARS 1 1/4"	EACH	94.0	40.0	22.0	32.0	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	167.0	71.1	39.2	56.7	

* SPECIALTY ITEMS

FILE NAME *	USER NAME * coombessf	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pvidot\coombessf\d0135397\7058-sht-500.dgn		DRAWN -	REVISED -			1531	10B-1 & 11B-1	PIATT	88	4	
PLOT SCALE = 48.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 7045B					
PLOT DATE = 10/20/2010		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					