

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	11N&TS-1	McLEAN	497	10
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 70514				

		Funding	80% Federal	80% Federal	80% Federal	80% Federal	80% State	80% Federal	80% Federal	80% Federal	100% City	80% Federal	80% Federal	100% City	80% Federal	100% City	
		Breakout	20% State	20% State	20% State	10% State	20% City	10% State	13% State	20% City		20% State	20% City		20% State		
		URBAN															
		Construction															
		Code	0004	0040	0040	0021	0038	0021	0021	0021	0021	0021	0021	0021	0043	0021	0021
		TOTAL QTY	ROADWAY	RETAINING WALL S.N.057-W001	RETAINING WALL S.N.057-W002	SIDEWALK	BIKE PATH	** SEE BELOW	*** SEE BELOW	**** SEE BELOW	EMERGENCY PREEMPTION	INTERCONNECT	INTERCONNECT	UTILITY ADJUSTMENTS	COMBINATION LIGHTING	COMBINATION LIGHTING	
*	M2510630	EROSION CONTROL BLANKET	SQ M	7,368	7,368												
	M2800305	TEMPORARY DITCH CHECKS	METER	260	260												
	M2800400	PERIMETER EROSION BARRIER	METER	1,175	1,175												
	M2810105	STONE RIPRAP, CLASS A3	SQ M	45	45												
	M2810107	STONE RIPRAP, CLASS A4	SQ M	697	697												
	M2820200	FILTER FABRIC	SQ M	742	742												
	M3110300	SUB-BASE GRANULAR MATERIAL, TYPE A 300MM	SQ M	38,410	38,410												
	M3511150	AGGREGATE BASE COURSE, TYPE B 150MM	SQ M	5,709	5,063					646							
	M3550590	HOT-MIX ASPHALT BASE COURSE, 290MM	SQ M	3,566	3,566												
	M4021010	AGGREGATE SURFACE COURSE, TYPE B	MTON	200	200												
	M4080895	CONSTRUCTING TEST STRIP	EACH	3	3												
	M4080990	TEMPORARY RAMP	SQ M	343	343												
	M4082115	LEVELING BINDER (MACHINE METHOD), N30	MTON	13						13							
	M4083305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	MTON	186						186							
	M4083240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N90	MTON	494	494												
	M4083570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	MTON	1,496	1,496												
	M4080100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	27,090	25,847					1243							
	M4202215	PORTLAND CEMENT CONCRETE PAVEMENT 210MM (JOINTED)	SQ M	5,348	5,348												
	M4202225	PORTLAND CEMENT CONCRETE PAVEMENT 220MM (JOINTED)	SQ M	17,133	17,133												
	M4202235	PORTLAND CEMENT CONCRETE PAVEMENT 230 MM (JOINTED)	SQ M	8,403	8,403												
	M4230150	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150MM	SQ M	3,670	3,670												
	M4240100	PORTLAND CEMENT CONCRETE SIDEWALK 100MM	SQ M	299.5						299.5							
	M4248000	DETECTIBLE WARNINGS	SQ M	14.98						14.98							
	M4400730	HOT-MIX ASPHALT SURFACE REMOVAL, 30MM	SQ M	13,262	13,262												
	M4402000	PAVEMENT REMOVAL	SQ M	21,887	21,887												

- * SPECIALTY ITEMS
- ** VETERANS & MORRIS TRAFFIC SIGNALS
- *** VETERANS & GREENWOOD TRAFFIC SIGNALS
- **** MORRIS & SIX POINTS TRAFFIC SIGNALS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES SHEET 5 OF 12
		DRAWN BY
		CHECKED BY
		DATE 05-27-09

SUMMARY OF QUANTITIES