

SUMMARY OF QUANTITIES

F.A.P. RTE. 704	SECTION (LIN&TS-1)	COUNTY McLEAN	TOTAL SHEETS 497	SHEET NO. 11
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 70514				

		Funding	80% Federal	80% Federal	80% Federal	80% Federal	80% State	80% Federal	80% Federal	80% Federal	100% City	80% Federal	80% Federal	100% City	80% Federal	100% City
		Breakout	20% State	20% State	20% State	10% State	20% City	10% State	13% State	20% City		20% State	20% City		20% State	
		URBAN				10% City		10% City	7% City							
		Construction														
	Code	TOTAL QTY	0004 ROADWAY	0040 RETAINING WALL S.N.057-W001	0040 RETAINING WALL S.N.057-W002	0021 SIDEWALK	0038 BIKE PATH	0021 ** SEE BELOW	0021 *** SEE BELOW	0021 **** SEE BELOW	0021 EMERGENCY PREEMPTION	0021 INTERCONNECT	0021 INTERCONNECT	0043 UTILITY ADJUSTMENTS	0021 COMBINATION LIGHTING	0021 COMBINATION LIGHTING
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	3,303	3,303												
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	758	758												
M4402050	SIDEWALK REMOVAL	SQ M	223	223												
M4402420	MEDIAN REMOVAL	SQ M	190.4	190.4												
M4402030	GUTTER REMOVAL	METER	10	10												
M4405000	PAVED DITCH REMOVAL	METER	281	281												
* M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	1,209	1,209												
M4812150	AGGREGATE SHOULDERS, TYPE B 150MM	SQ M	2,156	2,156												
M4812000	AGGREGATE SHOULDERS, TYPE B	MTON	24	24												
M4820600	HOT-MIX ASPHALT SHOULDERS 200MM	SQ M	2,447	2,447												
M4830150	PORTLAND CEMENT CONCRETE SHOULDERS - 150MM	SQ M	679	679												
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4												
MZ075498	CONCRETE RETAINING WALL REMOVAL	METER	3	3												
M5010522	PIPE CULVERT REMOVAL	METER	345	345												
M5020100	STRUCTURE EXCAVATION	CUM	1,289		381	908										
M5030350	CONCRETE STRUCTURES	CUM	520	3	258	259										
M5030450	PROTECTIVE COAT	SQ M	221		109	112										
M5080105	REINFORCEMENT BARS	KG	1,480	1,480												
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	41,530		21,190	20,340										
MZ007128	HANDRAIL REMOVAL	METER	12	12												
M5080540	PIPE HANDRAIL	METER	93	93												
M5401010	PRECAST CONCRETE BOX CULVERT 900MM X 800MM	METER	0.6	0.6												
M5403000	CONCRETE BOX CULVERTS	CUM	7.6	7.6												

* SPECIALTY ITEMS

- ** VETERANS & MORRIS TRAFFIC SIGNALS
- *** VETERANS & GREENWOOD TRAFFIC SIGNALS
- **** MORRIS & SIX POINTS TRAFFIC SIGNALS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SHEET 6 OF 12
 DRAWN BY
 CHECKED BY
 DATE 05-27-09

SUMMARY OF QUANTITIES