

**SCHEDULE OF QUANTITIES**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	DN&TS-1	McLEAN	497	50
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

	INLETS, TYPE A (EACH)	INLETS, TYPE B (EACH)	MANHOLE TY. A 1.2 m DIA. (EACH)	MANHOLE TY. A 2.7 m DIA. (EACH)	FLUSH INLET BOX FOR MEDIAN (EACH)	FRAMES & GRATES TY. 3 (EACH)	FRAMES & GRATES TY. 3V (EACH)	FAMES & GRATES TY. 4 (EACH)	GRATES TYPE 8 (EACH)	FRAMES & LIDS TY. 1, CLOSED LID (EACH)	FRAMES & LIDS TY. 1, OPEN LID (EACH)	INLET & PIPE PROTECTION (EACH)
<b>SIX POINTS ROAD</b>												
STA. 0+024.000, 7.825 m LT		1				1						1
STA. 0+024.000, 7.825 m RT		1				1						1
STA. 0+042.000, 7.825 m RT	1					1						1
STA. 0+103.300, 7.825 m LT		1					1					1
STA. 0+125.700, 7.825 m LT		1					1					1
STA. 0+125.700, 7.825 m RT		1					1					1
STA. 0+157.000, 7.825 m LT		1					1					1
STA. 0+157.000, 7.825 m RT	1						1					1
STA. 0+157.000, 9.800 m LT			1							1		1
STA. 0+179.000, 7.895 m RT	1						1					1
STA. 0+190.700, 8.085 m LT	1						1					1
STA. 0+190.700, 10.000 m LT			1							1		1
STA. 0+217.000, 8.520 m RT		1					1					1
STA. 0+219.600, 8.556 m LT	1						1					1
STA. 0+225.620, 10.600 m LT			1							1		1
STA. 0+225.620, 8.656 m LT		1				1						1
STA. 0+225.620, 5.600 m RT			1							1		1
STA. 0+225.620, 8.661 m RT		1				1						1
STA. 0+231.600, 8.752 m LT	1						1					1
STA. 0+231.600, 8.760 m RT	1						1					1
STA. 0+235.200, 10.800 m LT			1							1		1
STA. 0+261.000, 9.245 m RT	1						1					1
STA. 0+272.000, 9.413 m LT	1						1					1
STA. 0+317.200, 9.625 m LT		1					1					1
STA. 0+317.200, 9.625 m RT	1						1					1
STA. 0+369.000, 15.600 m LT			1						1			1
STA. 0+370.000, 9.625 m LT		1				1						1
STA. 0+370.000, 9.625 m RT		1				1						1
STA. 0+386.765, 15.684 m RT		1				1						1
STA. 0+434.500, 6.025 m RT	1					1						1
STA. 0+440.818, 6.025 m RT		1				1						1
STA. 0+448.600, 6.025 m RT	1					1						1
STA. 0+558.286, 6.547 m LT		1						1				1
STA. 0+602.128, 10.34m LT												1
STA. 0+614.000, 10.500 m RT		1							1			1
<b>TOTAL</b>	<b>12</b>	<b>16</b>	<b>6</b>			<b>11</b>	<b>15</b>	<b>1</b>	<b>2</b>	<b>5</b>		<b>35</b>
<b>SPRINGFIELD ROAD</b>												
STA. 1+075.300, 14.800 m LT			1						1	1		1
STA. 1+081.480, 25.010 m LT										1		1
STA. 16+355.000, 6.000 m LT	1										1	
STA. 16+398.111, 7.432 m LT	1					1						
<b>TOTAL</b>	<b>2</b>	<b>0</b>	<b>1</b>			<b>1</b>	<b>0</b>		<b>1</b>	<b>2</b>	<b>1</b>	<b>2</b>

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES
DATE 05-27-09		DRAWN BY MAC CHECKED BY PMH

**SCHEDULE OF QUANTITIES**