

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	11N&TS-1	McLEAN	497	52
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 70514				

	STORM SEWERS, CL. A, TY 1300 mm (METER)	STORM SEWERS, CL. A, TY 2 300 mm (METER)	STORM SEWERS, CL. A, TY 1375 mm (METER)	STORM SEWERS, CL. A, TY 2 375 mm (METER)	STORM SEWERS, CL. A, TY 1450 mm (METER)	STORM SEWERS, CL. A, TY 2 450 mm (METER)	STORM SEWERS, CL. A, TY 1600 mm (METER)	STORM SEWERS, CL. A, TY 2 600 mm (METER)	SLOTTED DRAIN 300 mm (METER)	STORM SEWERS, CL. A, TY 1 1200 mm (METER)	STORM SEWERS, CL. A, TY 2 1200 mm (METER)
VETERANS PARKWAY											
STA. 2+201.4, 10.010 m RT TO STA. 2+272.0, 8.240 RT						69.8					
STA. 2+273.5, 8.190 m RT TO STA. 2+329.6, 4.320 m RT		55.8									
STA. 2+330.4, 4.400 m RT TO STA. 2+334.5, 8.290 m RT	13.6										
STA. 2+405.0, 23.800 m RT TO STA. 2+445.4, 23.100 m RT									39.5		
STA. 2+411.1, 7.520 m RT TO STA. 2+411.8, 7.38 m RT									30.4		
STA. 2+442.7, 7.375 m RT TO STA. 2+444.4, 7.375 m RT	1.7										
STA. 2+445.2, 7.375 m RT TO STA. 2+447.0, 7.375 m RT	1.8										
STA. 2+444.8, 7.825 m RT TO STA. 2+444.8, 9.746 m RT					2.0						
STA. 2+445.4, 10.346 m RT TO STA. 2+504.4, 10.834 m RT					58.4						
STA. 2+446.2, 10.834 m RT TO STA. 2+456.9, 23.182 m RT									10.4		
STA. 2+505.0, 7.645 m RT TO STA. 2+505.0, 10.834 m RT		2.6									
STA. 2+505.6, 10.834 m RT TO STA. 2+564.4, 8.730 m RT								58.1			
STA. 2+565.0, 4.225 m RT TO STA. 2+565.0, 8.130 m RT		3.9									
STA. 2+565.8, 8.730 m RT TO STA. 2+595.8, 8.700 m RT								29.8			
STA. 2+597.0, 8.700 m RT TO STA. 2+609.4, 8.483 m RT				12.4							
STA. 2+610.0, 4.225 m RT TO STA. 2+610.0, 7.883 m RT		3.7									
STA. 2+610.6, 8.483 m RT TO STA. 2+701.9, 8.011 m RT				90.3							
STA. 2+703.0, 5.377 m RT TO STA. 2+702.5, 7.411 m RT		2.1									
STA. 2+703.1, 8.011 m RT TO STA. 2+739.0, 9.184 m RT	35.6										
STA. 2+739.6, 7.825 m RT TO STA. 2+739.6, 8.584 m RT	0.8										
STA. 2+740.2, 9.184 m RT TO STA. 2.779.7, 7.530 m RT	39.2										
VETERANS PARKWAY TOTAL	92.7	68.1			60.4	69.8	0	87.9	80.3		
MORRIS AVENUE											
STA. 0+143.6, 5.025 m RT TO STA. 0+143.6, 6.925 m LT	12.0										
STA. 0+234.4, 17.900 m LT TO STA. 0+237.989, 22.850 m LT	6.1										
STA. 0+238.0, 23.600 m LT TO STA. 0+234.1, 30.064 m LT			7.6								
STA. 0+238.6, 22.975 m LT TO STA. 0+246.5, 18.079 m LT			9.2								
STA. 0+245.5, 13.576 m LT TO STA. 0+246.5, 18.076 m LT			4.1								
STA. 0+245.6, 12.765 m LT TO STA. 0+263.5, 16.456 m RT			34.3								
STA. 0+264.2, 17.082 m RT TO STA. 0+265.9, 18.203 m RT	2.1										
STA. 0+321.5, 18.429 m LT TO STA. 0+330.9, 11.833 m LT	11.4										
FROM M-A TO M-B	25.0										
FROM M-B TO M-C	18.7										
FROM M-C TO M-D	23.5										
FROM M-E TO M-G	5.4										
FROM M-F TO M-G	6.3										
FROM M-G TO M-H	12.7										
FROM M-H TO M-I			6.4								
FROM M-I TO M-J				7.9							
FROM M-J TO M-K				9.5							
FROM M-K TO M-L				4.6							
FROM M-M TO M-L		21.5									
FROM M-N TO M-M	2.9										
FROM M-O TO M-P	2.9										
FROM M-P TO M-Q		28.4									
FROM M-L TO M-Q											
STA. 0+533.8, 7.132 m LT TO STA. 0+534.9, 6.895 m LT	1.1										
STA. 0+535.3, 6.618 m RT TO STA. 0+535.3, 6.346 m LT	13.0										
STA. 0+535.7, 6.784 m LT TO STA. 0+575.6, 5.589 m LT	39.9										
STA. 0+576.0, 5.125 m LT TO STA. 0+576.0, 5.631 m RT			10.8								
STA. 0+576.45, 6.081 m RT TO STA. 0+606.8, 6.830 m RT			30.7								
MORRIS AVENUE TOTAL	183.0	49.9	103.1	22.0	0.0	0.0	0.0	0.0	0.0		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 DRAWN BY MAC
 CHECKED BY PMH
 DATE 05-27-09

SCHEDULE OF QUANTITIES