

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TO4	DN&TS-1	MOLEAN	497	54
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

	STORM SEWERS, CL. A, TY 1300 mm (METER)	STORM SEWERS, CL. A, TY 2 300 mm (METER)	STORM SEWERS, CL. A, TY 1375 mm (METER)	STORM SEWERS, CL. A, TY 2 375 mm (METER)	STORM SEWERS, CL. A, TY 1450 mm (METER)	STORM SEWERS, CL. A, TY 2 450 mm (METER)	STORM SEWERS, CL. A, TY 1600 mm (METER)	STORM SEWERS, CL. A, TY 2 600 mm (METER)	SLOTTED DRAIN 300 mm (METER)	STORM SEWERS, CL. A, TY 1 1200 mm (METER)	STORM SEWERS, CL. A, TY 2 1200 mm (METER)
GREENWOOD AVENUE											
STA. 7+105.2, 7.737 m RT TO STA. 7+112.8, 3.237 m RT				9.6							
STA. 7+113.5, 3.562 m RT TO STA. 7+114.9, 7.716 m RT				4.5							
STA. 7+113.8, 2.782 m RT TO STA. 7+129.7, 0.460 m LT						16.5					
STA. 7+130.3, 0.750 m LT TO STA. 7+130.0, 7.200 m LT						6.8					
STA. 7+130.7, 7.275 m LT TO STA. 7+154.4, 7.689 m LT				24.1							
STA. 7+155.5, 8.081 m LT TO STA. 7+163.651, 14.823 m LT			10.7								
STA. 10+008.8, 8.047 m RT TO STA. 10+060.0, 9.295 m RT	50.0										
STA. 10+053.1, 15.718 m LT TO STA. 10+059.5, 10.184 m LT	8.6										
STA. 10+058.3, 6.310 m LT TO STA. 10+059.5, 6.046 m LT	1.3										
STA. 10+060.0, 4.712 m RT TO STA. 10+060.0, 9.295 m LT	4.2										
STA. 10+060.0, 6.399 m LT TO STA. 10+060.0, 9.299 m LT			2.8								
STA. 10+060.0, 9.295 m RT TO STA. 10+077.4, 10.647 m RT	18										
STA. 10+060.6, 9.794 m LT TO STA. 10+076.2, 9.800 m LT					15.8						
STA. 10+130.3, 3.630 m RT TO STA. 10+164.6, 3.485 m RT	34.3										
STA. 10+165.0, 3.025 m RT TO STA. 10+165.0, 6.149 m LT					9.2						
STA. 10+191.9, 7.800 m LT TO STA. 10+202.0, 7.514 m LT							10.1				
STA. 10+201.6, 9.677 m RT TO STA. 10+204.4, 8.054 m RT					3.3						
STA. 10+206.0, 8.059 m RT TO STA. 10+220.983, 9.000 m RT							11.5				
FROM G-C TO G-D	14.6										
FROM G-E TO G-F							13.5				
FROM G-F TO G-G							0.8				
FROM G-H TO G-G										3.0	
FROM G-G TO G-I											5.2
EX. 1.2 M SS TO G-I											3.1
FROM G-J TO G-I								19.8			
STA. 10+415.4, 11.168 m LT TO STA. 10+478.15, 6.251 m LT	66.2										
STA. 10+691.8, 8.259 m RT TO STA. 10+708.4, 7.146 m RT	14.7										
STA. 10+707.6, 7.019 m RT TO STA. 10+733.1, 3.536 m RT	25.6										
STA. 10+731.7, 6.089 m LT TO STA. 10+733.5, 3.925 m LT	2.9										
STA. 10+733.9, 3.481 m RT TO STA. 10+745.9, 5.521 m RT	12.0										
GREENWOOD AVENUE TOTAL	252.4	0	13.5	38.2	28.3	23.3	35.9	19.8	0	3	8.3
SZAREK STREET											
STA. 03+982.9, 3.970 m RT TO STA. 03+986.9, 4.530 m RT	4										
STA. 03+987.3, 4.1 m RT TO STA. 03+987.3, 4.1 m LT	8.2										
STA. 03+982.9, 3.970 m LT TO STA. 03+986.9, 4.530 m LT	4										
SZAREK STREET TOTAL	16.2										
TOTAL ALL ROADS	800.8	122.6	284.8	60.2	94.7	159.6	35.9	161.9	80.3	3.0	8.3

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p align="right">DRAWN BY MAC CHECKED BY PMH</p> <p>DATE 05-27-09</p>

SCHEDULE OF QUANTITIES