

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	(1)N&T5-1	McLEAN	497	56A
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

PAVED DITCH REMOVAL			M4405000
STATION	OFFSET	METER	
0+869.4 TO 0+879.0, SPRINGFIELD ROAD	LT	38.1	
0+885.9 TO 0+925.2, SPRINGFIELD ROAD	LT	9.6	
6+993 TO 7+061.7, GREENWOOD AVE.	RT \ LT	69.3	
7+019.7 TO 7+037.0, GREENWOOD AVE.	LT	20.1	
7+131.6 TO 7+161.2, GREENWOOD AVE.	LT	35.9	
10+415.3 TO 10+519.3, GREENWOOD AVE.	LT	107.5	
TOTAL		280.5	

STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A			M4430090
STATION	LANE	METER	
2+205.500 TO 2+361.200, VETERANS PKWY	N. BOUND	158	
2+331.904 TO 2+361.200, VETERANS PKWY	S. BOUND	29	
2+361.200, 3.100 M RT. TO 13.270 M RT.	INTERSEC	10	
2+385.6 TO 2+437.5, VETERANS PKWY	N. BOUND	52	
2+385.6, 5.8 M RT TO 16.0 M RT	INTERSEC	10	
2+385.6 TO 2+540.5	S. BOUND	155	
2+473.3 TO 3.050.4	S. BOUND	577	
2+586.3 TO 2+760.7	N. BOUND	174	
2+712.2 TO 2+734.8	MEDIAN	45	
TOTAL		1209	

AGGREGATE SHOULDERS, TYPE A 150 MM			M4810150
LOCATION	OFFSET	SQ M	
STA. 0+867.0 TO STA. 0+892.2, SPRINGFIELD ROAD	LT	30	
STA. 0+867.0 TO STA. 0+984.4, SPRINGFIELD ROAD	RT	141	
STA. 0+898.0 TO STA. 0+930.2, SPRINGFIELD ROAD	LT	38	
STA. 0+948.6 TO STA. 1+048.7, SPRINGFIELD ROAD	LT	120	
STA. 0+992.8 TO STA. 1+050.3, SPRINGFIELD ROAD	RT	69	
STA. 1+060.4 TO STA. 1+078.1, SPRINGFIELD ROAD	RT	18	
STA. 1+053.7 TO STA. 1+076.6, SPRINGFIELD ROAD	LT	28	
STA. 6+989.437 TO STA. 7+154.5, GREENWOOD AVE.	RT	198	
STA. 6+989.437 TO STA. 7+107.9, GREENWOOD AVE.	LT	142	
STA. 7+117.1 TO STA. 7+141.3, GREENWOOD AVE.	LT	29	
STA. 7+149.3 TO STA. 7+158.0, GREENWOOD AVE.	LT	8	
STA. 10+074.785 TO STA. 10+297.400, GREENWOOD AVE.	LT	320	
STA. 10+185.028 TO STA. 10+208.826, GREENWOOD AVE.	RT	30	
STA. 10+216.600 TO STA. 10+246.800, GREENWOOD AVE.	RT	34	
STA. 10+417.900 TO STA. 10+707.05, GREENWOOD AVE.	RT	249	
STA. 10+330.4 TO STA. 10+426.700, GREENWOOD AVE.	LT	160	
STA. 10+418.0 TO STA. 10+509.3, GREENWOOD AVE.	RT	110	
STA. 10+485.1 TO STA. 10+730.7, GREENWOOD AVE.	LT	295	
STA. 10+516.7 TO STA. 10+519.0, GREENWOOD AVE.	RT	3	
STA. 10+531.7 TO STA. 10+537.7, GREENWOOD AVE.	RT	7	
STA. 10+544.8 TO STA. 10+548.4, GREENWOOD AVE.	RT	4	
STA. 10+572.1 TO STA. 10+595.8, GREENWOOD AVE.	RT	28	
STA. 10+615.3 TO STA. 10+631.4, GREENWOOD AVE.	RT	20	
STA. 10+640.5 TO STA. 10+649.4, GREENWOOD AVE.	RT	11	
STA. 10+680.3 TO STA. 10+697.4, GREENWOOD AVE.	RT	45	
STA. 10+704.6 TO STA. 10.723.6, GREENWOOD AVE.	RT	19	
TOTAL		2156	

AGGREGATE SHOULDERS, TYPE B			M4812000
LOCATION		MTON	
STA. 2+205.500 TO STA. 2+331.500 VETERANS PARKWAY		6	
STA. 2+205.500 TO STA. 2+304.600 VETERANS PARKWAY		5	
STA. 2+785.200 TO STA. 3+050.400 VETERANS PARKWAY		13	
TOTAL		24	

HOT-MIX ASPHALT SHOULDERS 200MM			M4820600
LOCATION	OFFSET	SQ M	
STA. 2+416.020 TO STA. 2+646.010, VETERANS PARKWAY	LT	556	
STA. 2+646.010 TO STA. 2+672.285, VETERANS PARKWAY	LT (GORE)	80	
STA. 2+667.200 TO STA. 3+053.520, VETERANS PARKWAY	LT	1125	
STA. 2+401.250 TO STA. 2+586.289, VETERANS PARKWAY	RT	447	
STA. 2+586.289 TO STA. 2+698.143, VETERANS PARKWAY	RT	157	
STA. 2+739.500 TO STA. 2+750.700, VETERANS PARKWAY	RT	22	
STA. 0+673.930 TO STA. 0+693.159, SIX POINTS ROAD	LT	60	
TOTAL		2447	

PORTLAND CEMENT CONCRETE SHOULDERS, 150 MM			M4830150
LOCATION	OFFSET	SQ M	
STA. 0+530.000 TO STA. 0+673.930, SIX POINTS ROAD	RT	341	
STA. 0+545.000 TO STA. 0+673.930, SIX POINTS ROAD	LT	338	
TOTAL		679	

CONCRETE HEADWALL REMOVAL			50104400
STATION	OFFSET	EACH	
2+445 VETERANS PARKWAY	RT	1	
0+261 SIX POINTS ROAD	RT	1	
0+261 SIX POINTS ROAD	LT	1	
0+973 SPRINGFIELD ROAD	22M RT	1	
TOTAL		4	

CONCRETE RETAINING WALL REMOVAL			M5010480
STATION	OFFSET	METER	
0+354.7, SIX POINTS ROAD	LT	3.3	
TOTAL		3.3	

PIPE CULVERT REMOVAL			M5010522
STATION	OFFSET	METER	
0+221 TO 0+226 MORRIS AVE.	RT	5	
0+483 TO 0+498 MORRIS AVE.	RT	15	
0+538 TO 0+557 MORRIS AVE.	RT	19	
0+584 TO 0+596 MORRIS AVE.	RT	12	
0+004 TO 0+017 SIX POINTS RD.	LT	13	
0+016 TO 0+023 SIX POINTS RD.	RT	7	
0+031 TO 0+038 SIX POINTS RD.	LT	7	
0+044 TO 0+053 SIX POINTS RD.	RT	9	
0+044 TO 0+051 SIX POINTS RD.	LT	7	
0+078 TO 0+085 SIX POINTS RD.	LT	7	
0+078 TO 0+085 SIX POINTS RD.	RT	7	
0+108 TO 0+115 SIX POINTS RD.	LT	7	
0+139 TO 0+148 SIX POINTS RD.	LT	7	
0+168 TO 0+174 SIX POINTS RD.	LT	6	
0+191 TO 0+195 SIX POINTS RD.	LT	4	
0+197 TO 0+211 SIX POINTS RD.	LT	14	
0+348 TO 0+381 SIX POINTS RD.	LT	35	
0+879 TO 0+886 SPRINGFIELD RD.	LT	7	
0+925 TO 0+949 SPRINGFIELD RD.	LT \ RT	26	
10+005 TO 10+025, GREENWOOD AVE.	RT	20	
10+207 TO 10+217 GREENWOOD AVE.	RT	9	
10+409 TO 10+430 GREENWOOD AVE.	RT	21	
10+506 TO 10+525 GREENWOOD AVE.	RT	19	
10+806 TO 10+814 GREENWOOD AVE.	RT	8	
10+630 TO 10+641 GREENWOOD AVE.	RT	11	
10+647 TO 10+661 GREENWOOD AVE.	RT	14	
10+697 TO 10+707 GREENWOOD AVE.	RT	10	
2+352 TO 2+371 VETERANS PARKWAY	RT	19	
TOTAL		345	

HANDRAIL REMOVAL			M5090040
STATION	OFFSET	METER	
0+222 MORRIS AVE. (AT STEPS)	RT	6	
0+225 MORRIS AVE. (AT STEPS)	RT	6	
TOTAL		12	

PIPE HANDRAIL			M5090540
STATION	OFFSET	METER	
0+146.0 TO 0+182.0 MORRIS	LT	36	
0+193.0 TO 0+250.0 MORRIS	RT	57	
TOTAL		93	

DUCTILE IRON WATER MAIN 200MM			M5610420
LOCATION		METER	
STA. 0+112.130, 4.9 M LT TO STA. 0+116.048, 59.800 M RT	SIX POINT	67	
TOTAL		67	

TAPPING VALVES AND SLEEVES 200MM			M5611215
LOCATION	OFFSET	EACH	
STA. 0+112.130, SIX POINTS ROAD	4.9M LT	1	
TOTAL		1	

OUTLET SPECIAL			X0324058
STATION	OFFSET	EACH	
2+456.661, VETERANS PARKWAY	RT	1	
11+367.125, VETERANS PARKWAY	LT	1	
TOTAL		2	

CURB AND GUTTER OUTLET, SPECIAL			X0932150
STATION		EACH	
2+308.042, VETERANS PARKWAY	RT	1	
2+350.363, VETERANS PARKWAY	LT	1	
2+414.220, VETERANS PARKWAY	LT	1	
2+416.007, VETERANS PARKWAY	LT	1	
2+486.600, VETERANS PARKWAY	RT	1	
2+669.800, VETERANS PARKWAY	RT	1	
1+076.577, SPRINGFIELD ROAD	LT	1	
1+078.117, SPRINGFIELD ROAD	RT	1	
16+411.487, SPRINGFIELD ROAD	LT	1	
7+156.215, GREENWOOD AVE.	LT	1	
10+022.985, GREENWOOD AVE.	LT	1	
10+074.765, GREENWOOD AVE.	LT	1	
10+426.700, GREENWOOD AVE.	LT	1	
10+478.900, GREENWOOD AVE.	LT	1	
10+730.700, GREENWOOD AVE.	LT	1	
10+730.754, GREENWOOD AVE.	RT	1	
TOTAL		16	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

DRAWN BY MAC
CHECKED BY PMH

DATE 05-27-09

SCHEDULE OF QUANTITIES