

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	(1)N&TS-1	MCLEAN	497	57
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

CONCRETE GUTTER, TYPE A			M6060260
STATION	OFFSET	METER	
0+519.101, SIX POINTS ROAD	RT	21.5	
16+398.423, SPRINGFIELD ROAD	RT	12.5	
7+165.312, GREENWOOD AVE.	RT	15.1	
10+257.800, GREENWOOD AVE.	RT	17.6	
	TOTAL	66.7	

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.45			M6060600
LOCATION	OFFSET	METER	
STA. 2+231.904 TO STA. 2+336.472 VETERANS PKWY. S.BOUN	RT	7.3	
STA. 2+205.500 TO STA. 2+336.472 VETERANS PKWY. N.BOUN	RT	131.9	
STA. 2+338.887 TO STA. 2+344.935 VETERANS PKWY. S.BOUN	RT	9.6	
STA. 2+338.914 TO STA. 2+344.935 VETERANS PKWY. N.BOUN	RT	8.8	
STA. 2+401.733 TO STA. 2+414.221 VETERANS PKWY. S.BOUN	LT	12.5	
STA. 2+407.254 TO STA. 2+540.500 VETERANS PKWY. S.BOUN	RT	13.5	
STA. 0+022.000 TO STA. 0+285.081 MORRIS AVE.	RT	235.9	
STA. 0+024.000 TO STA. 0+116.838 MORRIS AVE.	LT	59.4	
STA. 0+141.998 TO STA. 0+237.842 MORRIS AVE.	LT	115.7	
STA. 0+243.303 TO STA. 0+255.788 MORRIS AVE. ISLAND	LT	22.8	
STA. 0+245.856 TO STA. 0+253.241 MORRIS AVE. ISLAND	LT	17	
STA. 0+289.608 TO STA. 0+379.739 MORRIS AVE.	LT	92.9	
STA. 0+311.879 TO STA. 0+403.022 MORRIS AVE.	RT	104.8	
STA. 0+430.438 TO STA. 0+606.000 MORRIS AVE.	RT	176.1	
STA. 0+433.657 TO STA. 0+554.106 MORRIS AVE.	LT	124.7	
STA. 0+560.993 TO STA. 0+563.316 MORRIS AVE.	LT	7.6	
STA. 0+567.229 TO STA. 0+606.000 MORRIS AVE.	LT	49.1	
STA. 0+013.771 TO STA. 0+099.544 SIX POINTS RD.	RT	85.8	
STA. 0+015.783 TO STA. 0+191.719 SIX POINTS RD.	LT	175.9	
STA. 0+124.295 TO STA. 0+284.088 SIX POINTS RD.	RT	159.8	
STA. 0+216.473 TO STA. 0+392.937 SIX POINTS RD.	LT	176.5	
STA. 0+315.850 TO STA. 0+393.228 SIX POINTS RD.	RT	27.4	
STA. 0+428.172 TO STA. 0+522.825 SIX POINTS RD.	RT	96.5	
STA. 0+431.403 TO STA. 0+520.000 SIX POINTS RD.	LT	95.1	
STA. 16+384.489 TO STA. 16+409.487 SPRINGFIELD RD.	LT & RT	113.8	
STA. 1+076.577 TO STA. 1+087.937 SPRINGFIELD RD.	LT	18.7	
STA. 1+079.097 TO STA. 1+087.471 SPRINGFIELD RD.	RT	14.3	
STA. 7+156.473 TO STA. 7+164.433 GREENWOOD AVE.	LT	13.4	
STA. 7+158.982 TO STA. 7+166.940 GREENWOOD AVE.	RT	11.8	
STA. 10+007.916 TO STA. 10+073.059 GREENWOOD AVE.	LT	133	
STA. 10+007.916 TO STA. 10+099.731 GREENWOOD AVE.	RT	131.9	
STA. 10+256.176 TO STA. 10+403.112 GREENWOOD AVE.	RT	158.2	
STA. 10+428.389 TO STA. 10+483.318 GREENWOOD AVE.	LT	56.2	
STA. 10+732.500 TO STA. 10+776.275 GREENWOOD AVE.	LT	43.6	
STA. 10+732.500 TO STA. 10+776.275 GREENWOOD AVE.	RT	78	
STA. 3+937.700 TO STA. 3+991.954 SZAREK ST.	LT	59.9	
STA. 3+937.700 TO STA. 3+991.970 SZAREK ST.	RT	59.9	
STA. 5+008.022 TO STA. 5+050.512 MCKAY ST.	RT	47.9	
STA. 5+008.620 TO STA. 5+050.512 MCKAY ST.	LT	47.7	
	TOTAL	2,994.9	

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.45 (DOWELLED)			M6060610
LOCATION	OFFSET	METER	
STA. 2+205.500 TO STA. 2+331.904 VETERANS PKWY. S. BOUN	RT	125.7	
STA. 2+405.000 TO STA. 2+456.854 VETERANS PKWY. S. BOUN	RT	53	
STA. 2+437.542 TO STA. 2+486.600 VETERANS PKWY. N. BOUN	RT	48.4	
STA. 2+540.500 TO STA. 2+712.399 VETERANS PKWY. S. BOUN	RT	172.5	
STA. 2+669.800 TO STA. 2+712.399 VETERANS PKWY. N. BOUN	RT	41.8	
STA. 2+734.800 TO STA. 3+038.900 VETERANS PKWY. S. BOUN	RT	304.2	
STA. 2+734.800 TO STA. 3+028.900 VETERANS PKWY. N. BOUN	RT	292.7	
	TOTAL	1,038.3	

COMB. CONC. CURB AND GUTTER, TYPE B-15.45, VAR. WIDTH GUTTER FLAG			M6060625
LOCATION	OFFSET	METER	
STA. 2+397.428 TO STA. 2+4-5.000 VETERANS PLWY. N. BOUN	RT	7	
STA. 2+456.854 TO STA. 2+466.526 VETERANS PKWY. N. BOUN	RT	9	
STA. 3+028.900 TO STA. 3+038.900 VETERANS PKWY. N. BOUN	RT	10	
STA. 0+520.000 TO STA. 0+545.000 SIX POINTS RD	LT	25	
	TOTAL	51	

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-10.45			M6061960
LOCATION	OFFSET	METER	
STA. 10+099.731 TO STA. 10+167.378 GREENWOOD AVE.	RT	68	
	TOTAL	68	

STEEL PLATE BEAM GUARDRAIL, TYPE A			M6300100
STATION	OFFSET	METER	
2+535.4 TO 2+638.270, VETERANS PARKWAY	RIGHT	102.87	
2+667.691 TO 780.530, VETERANS PARKWAY	LEFT	118.92	
2+785.2 TO STA. 2+862.4 VETERANS PARKWAY	RIGHT	77.2	
2+890.156 TO 3+031.126, VETERANS PARKWAY	LEFT	140.97	
0+648.156 TO 0+693.070, SIX POINTS ROAD	LEFT	44.91	
16+403.1 TO 16+422.2, SPRINGFIELD ROAD	RIGHT	19.1	
16+404.6 TO 16+423.7, SPRINGFIELD ROAD	LEFT	19.1	
	TOTAL	523.07	

GUARDRAIL REMOVAL			M6320030
STATION	OFFSET	METER	
2+737 TO 2+862 VETERANS PARKWAY	RT	125	
2+747 TO 2+863 VETERANS PARKWAY	LT	116	
0+246 TO 0+270 SIX POINTS ROAD	LT	24	
0+252 TO 0+276 SIX POINTS ROAD	RT	24	
16+403 TO 16+426 SPRINGFIELD ROAD	RT	23	
16+404 TO 16+427 SPRINGFIELD ROAD	LT	23	
10+832 TO 10+691 GREENWOOD AVE.	LT	59	
	TOTAL	394	

WOOD SIGN SUPPORT				M7300100
STATION	SIGN TYPE	OFFSET	METER	
11+200.0 VETERANS NB	R3-5	RT	4.6	
2+563.0 VETERANS SB	R3-5	RT	4.6	
2+870.0 VETERANS SB	R3-5	RT	4.6	
0+352.0 MORRIS AVE.	R3-8x	RT	4.5	
0+401.0 MORRIS AVE.	R3-1	RT	4.6	
0+431.0 MORRIS AVE.	R3-1	LT	4.6	
0+451.0 MORRIS AVE.	R3-8x	LT	4.5	
0+528.0 MORRIS AVE.	R3-9b	RT	4.5	
0+577.0 MORRIS AVE.	R3-9b	LT	4.5	
0+223.0 SIX POINTS RD.	W4-2	LT	4.9	
0+342.0 SIX POINTS RD.	R3-8x	RT	4.5	
0+443.0 SIX POINTS RD.	R5-1	RT	4.6	
0+443.0 SIX POINTS RD.	R5-1	LT	4.6	
0+473.0 SIX POINTS RD.	R5-1	RT	4.6	
0+473.0 SIX POINTS RD.	R5-1	LT	4.6	
0+530.0 SIX POINTS RD.	R3-8b	LT	9.1	
1+084.0 SPRINGFIELD RD.	R1-1	RT	4.6	
1+037.0 SPRINGFIELD RD.	R3-8x	RT	4.5	
7+161.0 GREENWOOD AVE.	R1-1	RT	4.6	
10+220.0 GREENWOOD AVE.	W3-1	RT	4.9	
10+306.0 GREENWOOD AVE.	R1-1	RT	4.6	
10+334.0 GREENWOOD AVE.	R3-8x	LT	4.5	
10+347.0 GREENWOOD AVE.	R1-1	LT	4.6	
10+441.0 GREENWOOD AVE.	W3-1	LT	4.9	
3+988.0 SZAREK ST	R1-1	RT	4.6	
5+010.0 MCKAY ST.	R1-1	LT	4.6	
	TOTAL		124.3	

SIGN PANEL - TYPE 1				M7200100
STATION	TYPE	OFFSET	SQ M	
11+200.0 VETERANS NB	R3-5	RT	0.68	
2+562.0 VETERANS SB	R3-5	RT	0.68	
2+869.0 VETERANS SB	R3-5	RT	0.68	
0+352.0 MORRIS AVE.	R3-8x	RT	0.63	
0+401.0 MORRIS AVE.	R3-1	RT	0.36	
0+431.0 MORRIS AVE.	R3-1	LT	0.36	
0+451.0 MORRIS AVE.	R3-8x	LT	0.56	
0+528.0 MORRIS AVE.	R3-9b	RT	0.56	
0+577.4 MORRIS AVE.	R3-9b	LT	0.56	
0+223.0 SIX POINTS RD.	W4-2	LT	0.81	
0+342.3 SIX POINTS RD.	R3-8x	RT	0.56	
0+443.0 SIX POINTS RD.	R5-1	RT	0.56	
0+443.0 SIX POINTS RD.	R5-1	LT	0.56	
0+473.0 SIX POINTS RD.	R5-1	RT	0.56	
0+473.0 SIX POINTS RD.	R5-1	LT	0.54	
1+084.0 SPRINGFIELD RD.	R1-1	RT	0.56	
1+037.0 SPRINGFIELD RD.	R3-8x	RT	0.56	
7+161.0 GREENWOOD AVE.	R1-1	RT	0.56	
10+220.0 GREENWOOD AVE.	W3-1	RT	0.81	
10+306.0 GREENWOOD AVE.	R1-1	RT	0.56	
10+338.5 GREENWOOD AVE.	R3-8x	LT	0.56	
10+347.0 GREENWOOD AVE.	R1-1	LT	0.56	
10+446.0 GREENWOOD AVE.	W3-1	LT	0.81	
3+987.0 SZAREK ST	R1-1	RT	0.56	
5+011.0 MCKAY ST.	R1-1	LT	0.56	
	TOTAL		14.76	

SIGN PANEL - TYPE 2				M7200200
STATION	TYPE	OFFSET	SQ M	
0+530.0 SIX POINTS RD	R3-8b	LT	0.90	
VETERANS PKWY STREET NAME SIGNS			7.43	
MORRIS AVE STREET NAME SIGNS			7.43	
SIX POINTS RD STREET NAME SIGNS			3.48	
GREENWOOD AVE STREET NAME SIGNS			3.72	
	TOTAL		22.96	

PAVEMENT MARKING REMOVAL			M78301000
LOCATION	OFFSET	SQ M	
STA. 2+473.0 TO STA. 3+050.5, VETERANS PKWY., STAGE 1	LT	58	
STA. 2+586.0 TO STA. 2+780.5, VETERANS PKWY., STAGE 3	RT	18	
STA. 2+304.0 TO STA. 2+405.0, VETERANS PKWY., STAGE 4	RT	10	
STA. 0+009.3 TO STA. 0+050.0, MORRIS AVE., STAGE 3	CENTERLINE	1	
STA. 0+200.0 TO STA. 0+240.0, MORRIS AVE., STAGE 3	CENTERLINE	8	
STA. 0+494.0 TO STA. 0+660.5, MORRIS AVE., STAGE 3	CENTERLINE	4	
	TOTAL	99	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p align="right">DRAWN BY MAC CHECKED BY PMH</p> <p>DATE 05-27-09</p>

SCHEDULE OF QUANTITIES