

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	(1)N&TS-1	McLEAN	497	58
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			
CONTRACT NO. 70514				

THERMOPLASTIC PAVEMENT MARKING
VETERANS PARKWAY

STATION TO STATION	LETTERS AND SYMBOLS		LINE								
	LEFT OR RIGHT ARROW	LANE LINE SKIP DASH WHITE 100 mm	LANE LINE DOTTED WHITE 100 mm	EDGE LINE SOLID YELLOW 100 mm	EDGE LINE SOLID WHITE 100 mm	LANE LINE SOLID WHITE 100 mm	CROSSWALK SOLID WHITE 150 mm	CROSSWALK SOLID WHITE 300 mm	STOP BAR SOLID WHITE 600 mm	MEDIAN SOLID WHITE 150 mm	MEDIAN SOLID WHITE 300 mm
	SQM	M	M	M	M	M	M	M	M	M	M
Veterans Parkway, Northbound											
2+205.0 TO 2+335.0		32.5									
2+205.0 TO 2+305.0					100						
2+236.8 TO 2+280.3			10.9								
2+280.3 TO 2+335.0						54.7					
2+280.3	1.47										
2+329.2	1.47										
2+335.0											
2+336.2 TO 2+338.6							23.9	24	11.3		
2+419.2 TO 2+707.4		72.0									
2+456.9 TO 2+585.5					128.6						
2+486.0 TO 2+670.0				184							
2+585.5 TO 2+630.8			11.3								
2+630.8 TO 2+705.5						74.7					
2+638.0	1.47										
2+664.5	1.47										
2+691.0	1.47										
2+707.4									8.4		
2+705.5 TO 2+714.9										26.2	14.9
2+736.7 TO 3+050.4		78.4									
2+760.7 TO 3+050.4					289.7						
Veterans Parkway, Southbound											
2+205.0 TO 2+336.5		32.9									
2+205.0 TO 2+336.5					131.5						
2+336.5 TO 2+338.9							24.1	24.0			
2+338.9 TO 2+356.6						18.5					14.2
2+408.7									10.9		
2+408.7 TO 2+646.9						238.2					
2+408.7 TO 3+050.4		160.4									
2+408.7 TO 2+486.4							77.7				
2+414.5	1.47										
2+438.4	1.47										
2+462.4	1.47										
2+486.4	1.47										
2+486.4 TO 2+563.0			19.2								
2+646.9 TO 2+672.3										51.2	79.2
2+648.8 TO 3+050.4					401.6						
2+738.6									10.8		
2+738.6 TO 3+050.4		78.0									
2+738.6 TO 2+803.0						64.4					
2+744.1	1.47										
2+763.7	1.47										
2+783.3	1.47										
2+803.0	1.47										
2+803.0 TO 2+869.3			16.6								
TOTAL	19.11	454.2	58	184	1308.1	271.5	48	48	41.4	77.4	108.3

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
DRAWN BY MAC
CHECKED BY PMH
DATE 05-27-09

SCHEDULE OF QUANTITIES