

SCHEDULE OF QUANTITIES

POLYUREA PAVEMENT MARKING, TYPE II
SIX POINTS ROAD, SPRINGFIELD ROAD, GREENWOOD AVE.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	(IN&TS-1	McLEAN	497	60
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

STATION TO STATION	LETTERS AND SYMBOLS		LINE										
	LEFT OR RIGH ARROW	COMB. LEFT (RIGHT) AND THROUGH ARRO	LANE LINE SOLID YELLOW 100 mm (DOUBLE)	LANE LINE SKIP DASH WHITE 100 mm	LANE LINE DOTTED WHITE 100 mm	EDGE LINE SOLID YELLOW 100 mm	EDGE LINE SOLID WHITE 100 mm	LANE LINE SOLID WHITE 100 mm	CROSSWALK SOLID WHITE 150 mm	CROSSWALK SOLID WHITE 300 mm	STOP BAR SOLID WHITE 600 mm	MEDIAN SOLID YELLOW 100 mm	MEDIAN SOLID YELLOW 300 mm
	SQ M	SQ M	M	M	M	M	M	M	M	M	M	M	M
SIX POINTS ROAD													
0+013.7 TO 0+100.0			172.6										
0+013.7 TO 0+066.8													
0+022.0 TO 0+075.0					13.3								
0+020.0	1.47												
0+066.8 TO 0+387.3					80.2								
0+075.0 TO 0+391					79.0								
0+111.9 TO 0+118.0													
0+124.0 TO 0+191.9			135.8									6.1	
0+198.3 TO 0+204.2													3.9
0+216.3 TO 0+285.9												282.4	37.8
0+307.0													3.6
0+307.0 TO 0+353.5													
0+307.0 TO 0+355.2			96.4										
0+312.8	1.47												
0+318.1	2.94												
0+333.2	1.47												
0+338.8	2.94												
0+353.5 TO 0+392.2					9.7								
0+353.5	1.47												
0+355.2 TO 0+392.2												74	13.6
0+361.9	2.94												
0+385.0	2.94												
0+390.8												12.0	
0+440.0												13.8	
0+440.0 TO 0+521.0													
0+445.8	1.47	2.42											
0+464.6	1.47	2.42											
0+483.4	1.47	2.42											
0+502.2	1.47	2.42											
0+521.0	1.47	2.42											
0+521.0 TO 0+673.9													
0+521.0 TO 0+673.9							152.9	152.9					
SPRINGFIELD ROAD													
0+865.5 TO 1+084.2			437.4										
0+865.5 TO 1+078.0													
0+998.6 TO 1+039.1					10.1								
1+039.1 TO 1+084.2													
1+039.1	2.94												
1+058.8	2.94												
1+078.4	2.94												
1+084.2													
GREENWOOD AVENUE													
6+989.4 TO 7+160.4			342.0										
6+989.4 TO 7+156.5													
7+160.4													
7+161.6													
7+164.0													
7+161.6 TO 7+164.0													
10+080.0 TO 10+304.0			448.0										
10+304.0													
10+308.3													
10+320.0, 14.0M LT TO 38.3M LT			48.6										
10+322.6, 14.0M LT	1.47												
10+322.6, 33.9M LT	1.47												
10+325.2, 14.0M LT TO 38.3M LT													
10+330.9, 14.0M LT	1.47												
10+330.9, 33.9M LT	1.47												
10+320.0 TO 10+336.4, 38.3M LT													
10+349.0													
10+349.0 TO 10+397.0			96.0										
TOTAL	39.69	12.1	1776.8	159.2	33.1	152.9	940.2	306.7	27.1	26.4	85.2	356.4	51.4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
DRAWN BY MAC
CHECKED BY PMH
DATE 05-27-09

SCHEDULE OF QUANTITIES