

**SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	(1)N&T5-1	McLEAN	497	485A
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

City of Bloomington Water Main work

FUNDING BREAKOUT = 100% CITY  
CONSTRUCTION CODE = 0043

Code No.	Pay Item	Unit	Quantity
* M5610430	DUCTILE IRON WATER MAIN, 300mm	METER	684
*	DUCTILE IRON WATER MAIN, 300mm (RESTRAINED JOINT)	METER	122
*	DUCTILE IRON WATER MAIN, 300mm (ENCASED)	METER	125
* M5610420	DUCTILE IRON WATER MAIN, 200mm	METER	297
*	DUCTILE IRON WATER MAIN, 200mm (RESTRAINED JOINT)	METER	15
*	DUCTILE IRON WATER MAIN, 200mm (ENCASED)	METER	13
* M5610415	DUCTILE IRON WATER MAIN, 150mm	METER	51
*	DUCTILE IRON WATER MAIN, 150mm (RESTRAINED JOINT)	METER	69
*	WATER SERVICE, TYPE "K" COPPER, 25mm DIA	METER	300
*	TAPPING SLEEVE VALVE 150mm x 150mm	EACH	3
*	SAMPLING AND CHLORINATION TAP 20 m	EACH	9
*	DUCTILE IRON WATER MAIN FITTINGS, 300mm PLUG	EACH	3
*	DUCTILE IRON WATER MAIN FITTINGS, 200mm PLUG	EACH	2
*	DUCTILE IRON WATER MAIN FITTINGS, 150mm PLUG	EACH	2
*	DUCTILE IRON WATER MAIN FITTINGS, 300mm x 300mm TEE	EACH	5
*	DUCTILE IRON WATER MAIN FITTINGS, 300mm x 150mm TEE	EACH	9
*	DUCTILE IRON WATER MAIN FITTINGS, 300mm x 200mm TEE	EACH	1
*	DUCTILE IRON WATER MAIN FITTINGS, 200mm x 200mm TEE	EACH	1
*	DUCTILE IRON WATER MAIN FITTINGS, 200mm x 150mm TEE	EACH	3
*	DUCTILE IRON WATER MAIN FITTINGS, 150mm x 150mm TEE	EACH	3
*	DUCTILE IRON WATER MAIN FITTINGS, 300mm x 150mm REDUCER	EACH	3
*	DUCTILE IRON WATER MAIN FITTINGS, 200mm x 150mm REDUCER	EACH	1
*	DUCTILE IRON WATER MAIN FITTINGS, 150mm x 50mm REDUCER	EACH	1
*	DUCTILE IRON WATER MAIN FITTINGS, 300mm 90 DEGREE BEND	EACH	1
*	DUCTILE IRON WATER MAIN FITTINGS, 300mm 45 DEGREE BEND	EACH	5
*	DUCTILE IRON WATER MAIN FITTINGS, 300mm 22 1/2 DEGREE BEND	EACH	2
*	DUCTILE IRON WATER MAIN FITTINGS, 200mm 45 DEGREE BEND	EACH	1
*	DUCTILE IRON WATER MAIN FITTINGS, 200mm 22 1/2 DEGREE BEND	EACH	1
*	DUCTILE IRON WATER MAIN FITTINGS, 150mm 90 DEGREE BEND	EACH	2
* MX033786	GATE VALVE AND BOX, 300mm	EACH	20
*	GATE VALVE AND BOX, 200mm	EACH	7
*	GATE VALVE AND BOX, 150mm	EACH	17
*	FIRE HYDRANT, CLOW F-2500	EACH	12
*	CURB STOP BOX FOR 20mm SERVICE	EACH	15
* M5620210	CORPORATION STOP FOR 20mm SERVICE	EACH	15
*	CURB STOP BOX FOR 50mm SERVICE	EACH	1
M5620235	CORPORATION STOP FOR 50mm SERVICE	EACH	1
XX006584	REMOVE CURB STOP BOX	EACH	16
X0323449	REMOVE WATER VALVE	EACH	16
X0327078	REMOVE FIRE HYDRANT AND VALVE ASSEMBLY	EACH	10

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
  
CITY OF BLOOMINGTON  
WATER MAIN  
SUMMARY OF QUANTITIES  
  
DRAWN BY  
05-27-09  
CHECKED BY