

## GENERAL NOTES

G.N.-100  
ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-105.09A  
ALL ELEVATIONS SHOWN IN THE PLANS ARE BASED ON NORTH AMERICAN VERTICAL DATUM OF 1988. (NAVD 88)

G.N.-107.12  
THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE LOCAL RAILROAD CONTACT IS:

Ms. Debbie Adams  
Division Office Manager-Illinois Division  
Norfolk Southern Railway Company  
1735 East Condit Street  
Decatur, IL. 62521  
(217) 425-2042

SPECIAL ATTENTION IS CALLED TO ARTICLE 107.12 REGARDING RAILROAD FLAGGERS. THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE RAILROAD CONTACT PERSON FOR FLAGGERS IS:

Mr. David Neumann  
Track Supervisor  
Norfolk Southern Railway Company  
Illinois Division  
2100 West College  
Normal, IL 61761  
(217) 714-2546

G.N.-201  
TREES THAT INTERFERE WITH THE CONSTRUCTION OPERATIONS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER. ANY TREE DUE TO ITS LOCATION AND DEEMED SUITABLE FOR SAVING BY THE ENGINEER SHALL BE PROTECTED DURING CLEARING AND SUBSEQUENT CONSTRUCTION OPERATIONS.

G.N.-250C-SPL  
SEEDING, CLASS 7 AND MULCH, METHOD 2 IS INCLUDED IN THIS CONTRACT TO SEED NEW EARTHWORK LOCATIONS DURING TIME PERIODS WHEN PERMANENT SEEDING IS NOT ALLOWED. SOME OR ALL OF THE CLASS 7 SEEDING AND MULCH WILL BE DELETED IF IT IS POSSIBLE TO PLACE PERMANENT SEEDING ON EARTH SHOULDERS AT THE TIME OF THEIR COMPLETION.

G.N.-406  
THE QUANTITIES INCLUDED IN THE PLANS FOR HOT-MIX ASPHALT RESURFACING ARE INTENDED TO GIVE THE COVERAGE SHOWN ON THE TYPICAL CROSS SECTIONS. IT IS NOT INTENDED TO INCREASE THE THICKNESS OF THE HOT-MIX ASPHALT MIXTURE IN ORDER TO USE ALL OF THE QUANTITIES INCLUDED IN THE CONTRACT.

G.N.-406.05b  
ALL LEVELING BINDER OR BINDER SHALL BE GIVEN A FOG COAT OF PRIME BEFORE THE SURFACE COURSE IS PLACED WHEN DIRECTED BY THE ENGINEER.

THE FOG COAT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER GALLON FOR BITUMINOUS MATERIAL (PRIME COAT) AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-406.10  
FOR MULTILANE RESURFACING

WHEN BEGINNING THE RESURFACING WITH NEW MIXTURES FOR LEVELING BINDER, BINDER COURSE, AND SURFACE COURSE MIXTURES, THE WORK WILL BE CONFINED TO THE INSIDE TRAFFIC LANE (PASSING LANE) FIRST. THE WORK WILL REMAIN ON THE INSIDE LANE UNTIL THE MIX HAS BEEN ADJUSTED AND APPROVED BY THE ENGINEER BEFORE ANY RESURFACING IS ALLOWED ON THE OUTSIDE (DRIVING) TRAFFIC LANE(S).

ANY DELAYS OR INCONVENIENCES CAUSED THE CONTRACTOR IN COMPLYING WITH THIS REQUIREMENT WILL BE CONSIDERED INCIDENTAL TO THE VARIOUS HOT-MIX ASPHALT PAY ITEMS, AS SHOWN IN THE CONTRACT, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-406H -- MIXTURE REQUIREMENTS Contract: 70550

Location	FAI 74 MAINLINE	FAI 74 MAINLINE	FAI 74 MAINLINE	FAI 74 MAINLINE	FAI 74 SHOULDER
Mixture Use	POLY BINDER BOTTOM LIFT	POLY, FG BINDER BOTTOM LIFT	POLY SURFACE TOP LIFT	POLY SURFACE BOTTOM LIFT	SURFACE SHLD BOTTOM LIFT >= 2 1/4"
AC/PG	SBS PG 70-22	SBS PG 70-22	SBS PG 70-22	SBS PG 70-22	PG 64-22
RAP % (Max)	10	10	10	10	10
Design Air Voids	4.0% @ Ndes=105	4.0% @ Ndes=105	4.0% @ Ndes=105	4.0% @ Ndes=105	4% @ Ndes=90
Mix Comp(Gradation)	IL 19.0	IL 19.0 F.G.	IL 9.5	IL 9.5	IL 9.5
Friction Aggregate	N.A.	N.A.	MIX "D"	MIX "C"	MIX "C"

Location	FAI 74 SHOULDER	C.H. 36 MAINLINE	C.H. 36 MAINLINE	C.H. 36 SHOULDER
Mixture Use	SHOULDER TOP LIFT < 2 1/4"	P.D. PATCH, SURFACE, & INCIDENTAL (FAI 74)	CLASS D PATCH	SHOULDER TOP LIFT < 2 1/4"
AC/PG	PG 64-22	PG 64-22	PG 64-22	PG 64-22
RAP % (Max)	30	15	25	30
Design Air Voids	4.0% @ Ndes=30	4.0% @ Ndes=50	4.0% @ Ndes=50	4.0% @ Ndes=30
Mix Comp(Gradation)	IL 9.5L	IL 9.5	IL 19.0	IL 9.5L
Friction Aggregate	MIX "C"	MIX "C"	N.A.	MIX "C"

FILE NAME *	USER NAME = hogenbj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\pwi\dot\hogenbj\d0158340\0570550-sht-genote.dgn	DRAWN -	REVISED -	74			(57-20)(11,21,22)RS-3	MCLEAN	150	4	
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	SCALE:			SHEET NO. 1 OF 2 SHEETS		TO STA.		
PLOT DATE = 10/20/2010	DATE -	REVISED -	ILLINOIS FED. AID PROJECT CONTRACT NO. 70550							