

LOCATION OF WORK:

FAI 74
RURAL
INTERSTATE
MCLEAN COUNTY
STA. 737+00 TO STA. 1111+00
E OF US 51 TO CH 36 AT DOWNS

FUNDING BREAKOUT:
CONSTRUCTION TYPE CODE:

90% FEDERAL / 10% STATE
0005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
44200517	CLASS A PATCHES, TYPE II, 7 INCH	SQ YD	50.0
44200521	CLASS A PATCHES, TYPE III, 7 INCH	SQ YD	20.0
44200523	CLASS A PATCHES, TYPE IV, 7 INCH	SQ YD	170.0
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	50.0
44200614	CLASS A PATCHES, TYPE IV, 13 INCH	SQ YD	70.0
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	305.0
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	100.0
44201031	CLASS B PATHCES, TYPE II, 15 INCH	SQ YD	155.0
44201063	CLASS B PATCHES, TYPE II, 18 INCH	SQ YD	40.0
44201294	CLASS B PATCH - EXPANSION JOINT	FOOT	25.0
44201299	DOWEL BARS 1 1/2"	EACH	1,235.0
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	710.0
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	125.0
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	205.0
44213000	PATCHING REINFORCEMENT	SQ YD	365.0
44213100	PAVEMENT FABRIC	SQ YD	100.0
44213200	SAW CUTS	FOOT	4,350.0
44213204	TIE BARS 3/4"	EACH	155.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	5,400.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	13,900.0

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = hoganbj	DESIGNED - BJH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pwwork\pwwork\hoganbj\d0158340\0570550-sht-500.dgn	DRAWN - BJH 10/12/2010	REVISED -						74	(57-20(1),21,22)RS-3	MCLEAN	150	9
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -			SCALE: _____ SHEET NO. 3 OF 7 SHEETS		STA. _____ TO STA. _____	CONTRACT NO. 70550				
PLOT DATE = 10/20/2010	DATE -	REVISED -			ILLINOIS FED. AID PROJECT							